

SHEET NUMBER												PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
6	7	8	9	12	13	14	15	62				01/STR	02/SAF						
28																		ROADWAY	
												28		202	23000	28	SY	PAVEMENT REMOVED	
			175									175		202	23000	175	SY	PAVEMENT REMOVED, 6"	
						67						67		202	30000	67	SF	WALK REMOVED	
							3,338					3,338		202	38000	3,338	FT	GUARDRAIL REMOVED	
							11					11		202	42000	11	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
							1					1		202	42010	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
							6					6		202	42040	6	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
							4					4		202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
							33					33		209	15000	33	STA	RESHAPING UNDER GUARDRAIL	
				15								15		209	60500	15	MILE	LINEAR GRADING	
14.2												14.2		209	72050	14.2	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	
							2,300					2,300		606	15050	2,300	FT	GUARDRAIL, TYPE MGS	
							925					925		606	15100	925	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
							100					100		606	17360	100	FT	GUARDRAIL, TYPE MGS, LONG-SPAN	
							12					12		606	26150	12	EACH	ANCHOR ASSEMBLY, MGS TYPE E	
							8					8		606	26550	8	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
							4					4		606	35002	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
						66						66		608	52000	66	SF	CURB RAMP	
2												2		623	39500	2	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE	
																		EROSION CONTROL	
							0.7					0.7		659	00300	0.7	CY	TOPSOIL	
							4					4		659	10000	4	SY	SEEDING AND MULCHING	
							0.01					0.01		659	20000	0.01	TON	COMMERCIAL FERTILIZER	
							0.01					0.01		659	35000	0.01	MGAL	WATER	
												5,000		832	30000	5,000	EACH	EROSION CONTROL	
																		DRAINAGE	
11												11		611	98630	11	EACH	CATCH BASIN ADJUSTED TO GRADE	
2												2		611	98634	2	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
5												5		611	99654	5	EACH	MANHOLE ADJUSTED TO GRADE	
																		PAVEMENT	
	1,961											1,961		253	02000	1,961	CY	PAVEMENT REPAIR	
				43,522		1,115						44,637		254	01000	44,637	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.75"	
				65,338								65,338		254	01000	65,338	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
				8,696		279						8,975		254	01000	8,975	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3.5"	
			350									350		254	01000	350	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
14			35									49		301	56000	49	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
			45	14,100		134						14,279		407	10000	14,279	GAL	TACK COAT	
				1,815								1,815		424	14001	1,815	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, (448), AS PER PLAN, 1"	6
90.4												90.4		424	14001	90.4	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, (448), AS PER PLAN, 3"	6
				3,630								3,630		441	10200	3,630	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (446), 2"	
			20									20		441	70000	20	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
50												50		441	70500	50	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS)	
15.4				1,828		43						1,886.4		442	00200	1,886.4	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), 1.75"	
13												13		442	00200	13	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), 3.5"	
				1,154		25						1,179		442	00201	1,179	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN, 1.75"	12,14
							56					56		442	90000	56	CY	ASPHALT CONCRETE, MISC.; BUTT JOINT INTERSECTIONS	14
				1,213								1,213		617	10100	1,213	CY	COMPACTED AGGREGATE	
	49,104				22,465							22,465	49,104	618	40900	71,569	FT	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				22,465								22,465		874	20000	22,465	FT	LONGITUDINAL JOINT PREPARATION	
				5,223								5,223		875	10000	5,223	LB	LONGITUDINAL JOINT ADHESIVE	
																		WATER WORK	
5												5		638	10800	5	EACH	VALVE BOX ADJUSTED TO GRADE	
																		TRAFFIC CONTROL	
					463							463		621	00100	463	EACH	RPM	
					463							463		621	54000	463	EACH	RAISED PAVEMENT MARKER REMOVED	
							62					62		626	00116	62	EACH	BARRIER REFLECTOR, TYPE 5, BIDIRECTIONAL	
				14.4								14.4		642	00104	14.4	MILE	EDGE LINE, 6", TYPE 1	
	9.3				6.9							6.9	9.3	642	00300	16.2	MILE	CENTER LINE, TYPE 1	

GENERAL SUMMARY



DESIGN AGENCY	
NC	
REVIEWER	
JLE	11/26/25
PROJECT ID	
101283	
SHEET	TOTAL
10	63

WIL-49-9.29/16.27

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 8/11/2026 TIME: 3:21:48 PM PLTDRV: OHDOT_PDF_Color.plt PENTBL: OHDOT_PenC.tbl USER: John.Erford@dot.ohio.gov WORKSPACE: OHDOTCEV02 WORKSET: 101283 PRODUCT: OpenRoadsDesigner 24.00.00.2025
 www\ohiodot-pw.bentley.com\ohdot-pw-02\Documents\01 Active Projects\District 02\Williams\101283400-Engineering\Roadway\Sheets\101283_GG002.dgn

[illegible]

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER

NC

REVIEWER

JLE 11/26/26

PROJECT ID

101283

SHEET TOTAL

11 | 63

REF NO.	SHEET NO.	STATION TO STATION			642	642	642	642	642	642	644	644	644	644	644	644	618	621	621	621
					EDGE LINE, 6", TYPE 1	CENTER LINE, TYPE 1, DASHED SOLID	CENTER LINE, TYPE 1, DOUBLE SOLID	CENTER LINE, TYPE 1, DASHED	CHANNELIZING LINE, 12", TYPE 1	DOTTED LINE, 6", TYPE 1	STOP LINE	CROSSWALK LINE, 24"	LANE ARROW	RAILROAD SYMBOL MARKING	TRANSVERSE/DIAGONAL LINE, YELLOW	ISLAND MARKING	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	RAISED PAVEMENT MARKER REMOVED	RPM(2-WAY YELLOW/YELLOW)	RPM(2-WAY WHITE/RED)
					MILE	MILE	MILE	MILE	FT	FT	FT	FT	EACH	EACH	FT	SF	FT	EACH	EACH	EACH
		WIL 49																		
	16	490+11.46	TO	500+00.00	0.37	0.10		0.08												
	17	500+00.00	TO	510+00.00	0.38	0.04	0.06	0.09						1						
	18	510+00.00	TO	512+83.92	0.11		0.05							1						
	19	521+07.89	TO	530+00.00	0.34	0.04		0.11				192								
	20	530+00.00	TO	540+00.00	0.38			0.19												
	21	540+00.00	TO	550+00.00	0.38	0.12		0.07												
	22	550+00.00	TO	560+00.00	0.38	0.12		0.07										8	8	
	23	560+00.00	TO	570+00.00	0.38	0.11		0.07										13	13	
	24	570+00.00	TO	580+00.00	0.38	0.14		0.05										13	13	
	25	580+00.00	TO	590+00.00	0.38	0.14		0.05										13	13	
	26	590+00.00	TO	600+00.00	0.38	0.06		0.13										13	13	
	27	600+00.00	TO	610+00.00	0.38	0.19												13	13	
	28 / 29	610+00.00	TO	622+40.00	0.47	0.07		0.15										16	16	
	35	773+00.00	TO	780+00.00	0.27		0.13		337.6		37.1		4					19	9	10
	36	780+00.00	TO	790+00.00	0.38		0.16		136.7				2					18	13	5
	37	790+00.00	TO	800+00.00	0.38		0.12		544.5	236.5	48.8		6		100.4	47		32	17	15
	38	800+00.00	TO	805+61.72	0.21		0.03		5.1	61.4					87.7			13	13	
	39	859+19.55	TO	865+00.00	0.22	0.03	0.08				33						580.4	8	8	
	40	865+00.00	TO	875+00.00	0.38	0.15	0.04										1000.0	13	13	
	41	875+00.00	TO	885+00.00	0.38	0.12	0.06										1000.0	13	13	
	42	885+00.00	TO	895+00.00	0.38	0.17	0.02										1000.0	13	13	
	43	895+00.00	TO	905+00.00	0.38	0.17	0.02										1000.0	13	13	
	44	905+00.00	TO	915+00.00	0.38	0.04		0.15									1000.0	13	13	
	45	915+00.00	TO	925+00.00	0.38	0.16		0.03									1000.0	13	13	
	46	925+00.00	TO	935+00.00	0.38	0.04	0.15										1000.0	13	13	
	47	935+00.00	TO	945+00.00	0.38	0.11	0.07										1000.0	13	13	
	48	945+00.00	TO	955+00.00	0.38	0.19											1000.0	13	13	
	49	955+00.00	TO	965+00.00	0.38	0.01	0.17										1000.0	13	13	
	50	965+00.00	TO	975+00.00	0.38	0.17	0.02										1000.0	13	13	
	51	975+00.00	TO	985+00.00	0.38	0.16	0.03										1000.0	13	13	
	52	985+00.00	TO	995+00.00	0.38		0.18										1000.0	13	13	
	53	995+00.00	TO	1005+00.00	0.38		0.19										1000.0	13	13	
	54	1005+00.00	TO	1015+00.00	0.38	0.12	0.07										1000.0	13	13	
	55	1015+00.00	TO	1025+00.00	0.38	0.04		0.15									1000.0	13	13	
	56	1025+00.00	TO	1035+00.00	0.38	0.13	0.04	0.02									1000.0	13	13	
	57	1035+00.00	TO	1045+00.00	0.38	0.11	0.08										1000.0	13	13	
	58 / 59	1045+00.00	TO	1057+70.83	0.48	0.06		0.18									1270.8	16	16	
	59	1058+94.85	TO	1065+00.00	0.23	0.11											605.1	8	8	
	60	1065+00.00	TO	1075+00.00	0.38	0.06	0.13										1000.0	13	13	
	61	1075+00.00	TO	1085+08.44	0.38	0.15	0.04										1008.4	13	13	
TOTALS CARRIED TO GENERAL SUMMARY					14.4	6.9			1024	298	119	192	12	2	188	47	22465	463	463	

PAVEMENT MARKING SUBSUMMARY

DESIGN AGENCY

DESIGNER

NC

REVIEWER

JLE 11/26/25

PROJECT ID

101283

SHEET

13

TOTAL

63