ENVIRONMENTAL COMMITMENTS

THE CONTRACTOR SHALL NOT REMOVE ANY TREES UNDER THIS
PROJECT FROM APRIL 1 THROUGH SEPTEMBER 30. THE PROJECT IS
LOCATED WITHIN THE KNOWN HABITAT RANGES OF THE FEDERALLY
LISTED AND PROTECTED INDIANA BAT AND NORTHERN LONG-EARED
BAT. ALL NECESSARY TREE REMOVAL SHALL OCCUR FROM OCTOBER 1
THROUGH MARCH 31. THIS REQUIREMENT IS NECESSARY TO AVOID
AND MINIMIZE IMPACTS TO THESE SPECIES AS REQUIRED BY THE
ENDANGERED SPECIES ACT. FOR THE PURPOSES OF THIS NOTE, A TREE
IS DEFINED AS A LIVE, DYING, OR DEAD WOODY PLANT, WITH A TRUNK
THREE INCHES OR GREATER IN DIAMETER AT A HEIGHT OF 4.5 FEET
ABOVE THE GROUND SURFACE, AND WITH A MINIMUM HEIGHT OF 13
FEET.

ENVIRONMENTAL STUDIES INDICATED THAT PETROLEUM
CONTAMINATED SOIL (PCS) WILL BE ENCOUNTERED DURING
EXCAVATIONS WITHIN THE PROJECT LIMITS FROM STA. 232+84, RT TO
STA. 233+70, RT. ENVIRONMENTAL STUDIES ARE AVAILABLE UPON
REQUEST. THE CONTRACTOR MUST DETERMINE APPROPRIATE
PERSONAL PROTECTIVE EQUIPMENT FOR THOSE WHO CONDUCT WORK
WITHIN THE LIMITS OF THE PCS.

ALL EXCAVATED PCS THAT CANNOT BE REUSED AS PROJECT FILL PER CMS 203.03(J)., SHALL BE MANAGED AND DISPOSED OF AT A LICENSED LANDFILL. THE ENGINEER MAY PERMIT THE CONTRACTOR TO DIRECT LOAD THE EXCAVATED PCS INTO TRUCKS FOR TRANSPORT AND DISPOSAL. AS AN ALTERNATE, THE ENGINEER MAY PERMIT THE CONTRACTOR TO TEMPORARILY STOCKPILE THE EXCAVATED PCS ON AN IMPERMEABLE MEMBRANE, IN AN AREA PROVIDE BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE STOCKPILE SHOULD BE SURROUNDED BY STRAW BALES TO REDUCE RUNOFF. THE CONTRACTOR WILL PROVIDE COMPLETED LOG FORMS AND MANIFESTS FOR TRANSPORT AND DISPOSAL TO THE ENGINEER FOR SIGNATURE. THE CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL TESTING THAT THE LANDFILL MAY REQUIRE FOR DISPOSAL.

ALL EXCAVATED AREAS SHALL BE BACKFILLED WITH SUITABLE MATERIAL IN ACCORDANCE WITH PROJECT PLANS, APPLICABLE ODOT SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL FURNISH ALL THE LABOR, EQUIPMENT AND MATERIALS NECESSARY TO PROPERLY MANAGE, STORE (IF NECESSARY), TEST FOR DISPOSAL, TRANSPORT AND DISPOSE OF REGULATED MATERIALS, INCLUDING ANY REQUIRED PERMITS OR FEES WITHIN THE IDENTIFIED LIMITS. PAYMENT FOR THIS WORK SHALL BE MADE AT THE CONTRACT PRICE BID. THE FOLLOWING ESTIMATED QUANTITES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY.

ITEM SPECIAL – WORK INVOLVING PETROLEUM CONTAMINATED SOILS 75 TON

ITEM 203 - EMBANKMENT 46 CY

ENVIRONMENTAL COMMITMENTS (CONTINUED)

ENVIRONMENTAL STUDIES INDICATED THAT SOLID WASTE CONSISTING OF DRY CLEANING FLUIDS WILL BE ENCOUNTERED DURING EXCAVATIONS WITHIN THE PROJECT LIMITS FROM STA. 233+60, RT TO STA. 235+08, RT. ENVIRONMENTAL STUDIES ARE AVAILABLE UPON REQUEST. THE CONTRACTOR MUST DETERMINE APPROPRIATE PERSONAL PROTECTIVE EQUIPMENT FOR THOSE WHO CONDUCT WORK WITHIN THE LIMITS OF THE SOLID WASTE.

ALL EXCAVATED SOLID WASTE THAT CANNOT BE REUSED ON THE PROJECT FILL SHALL BE MANAGED AND DISPOSED OF AT A LICENSED LANDFILL. THE ENGINEER MAY PERMIT THE CONTRACTOR TO DIRECT LOAD THE EXCAVATED SOLID WASTE INTO TRUCKS FOR TRANSPORT AND DISPOSAL. AS AN ALTERNATE, THE ENGINEER MAY PERMIT THE CONTRACTOR TO TEMPORARILY STOCKPILE THE EXCAVATED SOLID WASTE ON AN IMPERMEABLE MEMBRANE, IN AN AREA PROVIDE BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE STOCKPILE SHOULD BE SURROUNDED BY STRAW BALES TO REDUCE RUNOFF. THE CONTRACTOR WILL PROVIDE COMPLETED LOG FORMS AND MANIFESTS FOR TRANSPORT AND DISPOSAL TO THE ENGINEER FOR SIGNATURE. THE CONTRACTOR IS RESPONSIBLE FOR ANY ADDITIONAL TESTING THAT THE LANDFILL MAY REQUIRE FOR DISPOSAL.

ALL EXCAVATED AREAS SHALL BE BACKFILLED WITH SUITABLE MATERIAL IN ACCORDANCE WITH PROJECT PLANS, APPLICABLE ODOT SPECIFICATIONS OR AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL FURNISH ALL THE LABOR, EQUIPMENT AND MATERIALS NECESSARY TO PROPERLY MANAGE, STORE (IF NECESSARY), TEST FOR DISPOSAL, TRANSPORT AND DISPOSE OF REGULATED MATERIALS, INCLUDING ANY REQUIRED PERMITS OR FEES WITHIN THE IDENTIFIED LIMITS. PAYMENT FOR THIS WORK SHALL BE MADE AT THE CONTRACT PRICE BID. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY.

ITEM SPECIAL - WORK INVOLVING SOLID WASTE

100 TON

ITEM 203 - EMBANKMENT 62 CY

MAINTAIN SAFE PUBLIC ACCESS TO THE MAUMEE RIVER WATER TRAIL BOAT LAUNCH AREA AT ALL TIMES DURING CONSTRUCTION ACTIVITIES VIA FLAGGING OPERATIONS, A DETOUR, OR BOTH APPROVED BY THE PROJECT ENGINEER.

ODOT WILL ADHERE TO ALL APPROPRIATE WATERWAY PERMIT SPECIAL PROVISIONS THROUGHOUT CONSTRUCTION.

SCENIC RIVERS COMMITMENTS

THE CONTRACTOR SHALL NOT DISCHARGE TOXIC OR HAZARDOUS MATERIALS SUCH AS SEALANTS, PAINT, SOLVENTS, CLEANING AGENTS, EARTHEN MATERIALS, WASTE-WATER, FUELS OR DEBRIS OF ANY KIND TO A SCENIC RIVER, ITS TRIBUTARIES, OR DRAINAGE WAYS. IF REFUELING OF IMMOBILE EQUIPMENT IS NECESSARY WITHIN THE FLOODPLAIN OR NEAR ANY TRIBUTARY DRAINAGE WAYS, DITCHES, OR STREAM, THE CONTRACTOR SHALL PROVIDE SECONDARY CONTAINMENT WITH ENOUGH CAPACITY TO COMPLETELY CONTAIN AND COLLECT ALL POTENTIAL LIQUID WASTES IN THE EVENT OF A SPILL.

ANY AND ALL CONSTRUCTION DEBRIS, EARTHEN DEBRIS, EXCESS
ASPHALT OR CONCRETE, WOOD DEBRIS FROM CLEARING, EXCESS FILL
MATERIAL, AND TRASH SHOULD BE DISPOSED OF AT AN APPROVED
UPLAND SITE OR LAND FILL ABOVE FEMA 100-YEAR FLOOD ELEVATIONS.
DISPOSAL OF ANY SUCH MATERIALS WITHIN 1000 FEET OF THE
MAUMEE RIVER IS PROHIBITED.

KEEP ALL IDLE EQUIPMENT AND ANY STORAGE FOR/OF, FUELS,
LUBRICANTS, POTENTIALLY TOXIC OR HAZARDOUS MATERIALS BEYOND
1000 FEET OF THE MAUMEE RIVER. THE ONLY EXCEPTIONS WILL BE FOR
LARGE STATIONARY CRANES, DRILL RIGS, AND OTHER LARGE
CONSTRUCTION EQUIPMENT WITH LIMITED MOBILITY. IDLE
EQUIPMENT IS DEFINED AS CONSTRUCTION EQUIPMENT THAT WILL
NOT BE IN USE FOR THE FOLLOWING TWO CALENDAR DAYS. NOTIFY
THE ENGINEER OF WEATHER OR RIVER CONDITIONS THAT MAY IMPACT
THE WORK SITE AND PROVIDE A PLAN FOR IMMEDIATE MOVEMENT OF
ALL EQUIPMENT 1000 FEET OR MORE FROM THE RIVER.

THE CONTRACTOR SHALL DEVELOP AND IMPLEMENT A SEDIMENT AND EROSION CONTROL PLAN BEFORE EARTHWORK COMMENCES. THE PLAN SHALL INCLUDE A LIST OF APPLICABLE BMPS, PER SS 832 THAT WILL BE USED THROUGHOUT THE PROJECT, SUCH AS PERIMETER CONTROLS AND/OR SEEDING AND MULCHING AND MUST BE SUBMITTED TO THE PROJECT ENGINEER FOR REVIEW AND ACCEPTANCE. SEDIMENT AND EROSION CONTROLS SHALL BE PROPERLY INSTALLED AND MAINTAINED THROUGHOUT THE DURATION OF THE PROJECT. STRAW BALES SHALL NOT BE PERMITTED AS A FORM OF SEDIMENT CONTROL. ALL TEMPORARY SEDIMENT AND EROSION CONTROLS SHALL BE REMOVED UPON STABILIZATION OF THE PROJECT AREA. PARTICULAR ATTENTION SHALL BE GIVEN TO ANY DRAINAGE WAYS, UNPROTECTED SLOPES, DITCHES, AND STREAMS THAT COULD CONVEY SEDIMENT LADEN WATERS DIRECTLY TO THE MAUMEE RIVER.

WHEN CUTTING AND CLEARING OF ANY VEGETATION WITHIN 1000
FEET OF THE MAUMEE RIVER, THE CONTRACTOR SHALL LIMIT THE
AMOUNT OF VEGETATION BEING CLEARED TO THE ABSOLUTE
MINIMUM NECESSARY TO ACCOMPLISH THE GOAL OF THE PROJECT.
VERTICAL PRUNING OF TREES IS PERMITTED IF ANY OVERHANGING
LIMBS CAUSE A SAFETY HAZARD OR OBSTRUCT VIEW. THE
CONTRACTOR SHALL NOT USE A FLAIL MOWER FOR VERTICAL PRUNING.
THE CONTRACTOR MUST AVOID GIRDLING OR SCUFFING TREE TRUNKS.

THE CONTRACTOR SHALL MAKE EVERY ATTEMPT TO WORK FROM THE BRIDGE DECKS TO PLACE RCP AROUND THE STRUCTURE AND TO USE THE MINIMUM AMOUNT OF RCP NECESSARY TO PREVENT SCOUR. NEW OR USED CONCRETE OR ASPHALT ARE SPECIFICALLY PROHIBITED FROM USE AS FILL BELOW THE OHWM OR ON ANY PORTION OF THE SCENIC RIVER STREAM BANK.

THE CONTRACTOR MUST MAKE ALL REASONABLE ATTEMPTS TO DISTURB THE MINIMUM AMOUNT OF RIVERBANK VEGETATION. DISTURBED STREAM BANKS SHALL BE RE-VEGETATED, RETURNED TO PREVIOUSLY EXISTING CONTOURS AND ELEVATIONS, AND ANY TREES REMOVED TO PERFORM THE WORK SHALL BE REPLACED WITH NATIVE TREE SPECIES, WHERE PHYSICALLY PRACTICABLE.

THE CONTRACTOR SHALL MAKE EVERY ATTEMPT TO CONDUCT IN-STREAM WORK USING WATER DIVERSIONS SUCH AS SHEET PILING, MEMBRANE DAMS, ETC. THAT DO NOT REQUIRE THE PLACEMENT OF EARTHEN FILL. IN ACCORDANCE WITH ORC 3750.06, REPORTABLE SPILLS MUST BE REPORTED TO THE LOCAL FIRE DEPARTMENT (911), THE LOCAL EMERGENCY COORDINATOR (419) 354-9269, AND THE OHIO SPILL LINE (1-800-282-9378).

IN ACCORDANCE WITH THE SCENIC RIVER MOA BETWEEN ODNR AND ODOT (NO. 11323), TIER V COORDINATION WILL BE COMPLETED PRIOR TO THE START OF CONSTRUCTION. DOCUMENTATION OF COORDINATION WILL BE INCLUDED IN THE PROJECT FILE.

THE NORTHWEST OHIO ASSISTANT SCENIC RIVERS PROGRAM MANAGER, ROWAN COBURN-GRIFFIS (419-348-6731; rowan.coburn-griffis@dnr.ohio.gov), MUST BE INVITED TO A PRECONSTRUCTION MEETING WITH THE CONTRACTOR PRESENT AND BE NOTIFIED OF THE PROJECT START DATE A MINIMUM OF ONE WEEK PRIOR TO THE COMMENCEMENT OF WORK. ADDITIONALLY, MS. COBURN-GRIFFIS MUST BE INVITED TO A FINAL SITE INSPECTION ONE WEEK PRIOR TO THE COMPLETION OF THE PROJECT WITH THE CONTRACTOR PRESENT.

ITEM SPECIAL - FILL AND PLUG EXISTING CONDUIT

THIS ITEM CONSISTS OF THE CONSTRUCTION OF BULKHEADS IN AN CONDUIT AND FILLING THE AREA SEALED OFF WITH ITEM 613, SAND OR OTHER MATERIAL APPROVED BY THE ENGINEER.

LOCATE THE BULKHEADS AT THE LIMITS OF THE AREA TO BE FILLED, AS INDICATED ON THE PLANS. THE BULKHEADS CONSIST OF BRICK OR CONCRETE MASONRY WITH A MINIMUM THICKNESS OF 12 INCHES.

PUMP THE FILL MATERIAL INTO PLACE OR BY OTHER MEANS APPROVED BY THE ENGINEER, SO THAT AFTER SETTLEMENT, AT LEAST 90 PERCENT OF THE CROSS-SECTIONAL AREA OF THE CONDUIT, FOR ITS ENTIRE LENGTH IS FILLED. THE LENGTH OF FILLED AND PLUGGED CONDUIT TO BE PAID FOR IS THE ACTUAL NUMBER OF FEET (MEASURED ALONG THE CENTERLINE OF EACH CONDUIT FROM OUTER FACE TO OUTER FACE OF BULKHEADS) FILLED AND PLUGGED AS DESCRIBED ABOVE.

IN LIEU OF FILLING AND PLUGGING THE EXISTING CONDUIT, THE PIPE MAY BE CRUSHED AND BACKFILLED PER 203, OR IT MAY BE REMOVED. THE LENGTH, MEASURED AS PROVIDED ABOVE, WILL BE PAID FOR AT THE CONTRACT PRICE PER FOOT FOR, ITEM SPECIAL, FILL AND PLUG EXISTING CONDUIT.

DESIGN AGENCY



DESIGNER
GCB

REVIEWER
DTC 01/22/2!

PROJECT ID
107711

P.12 TOTAL 164

202 204 301 304 407 411 441 AREA SURFACE AREA (A=DxW/9 GENERATED **AVERAGE WIDTH** DISTANC (D) SIDE STATION RANGE SY CY CY CY CY FT FT SY SY SY GAL WOO-64-5.78 01/STR 403+11.00 TO 407+14.00 403.00 24.02 1075.56 1076 403+11.00 404+25.00 27.75 351.44 01/STR TO 114.00 39 32 403+11.00 404+25.00 28.41 359.80 01/STR TO 114.00 70 374.62 01/STR TO 403+11.00 404+25.00 114.00 29.58 375 62 32.00 622.22 01/STR 404+25.00 TO 406+00.00 175.00 68 56 406+00.00 32.66 01/STR 404+25.00 175.00 635.06 123 **CALCULATIONS** TO 404+25.00 406+00.00 33.83 657.81 01/STR 658 110 175.00 406+00.00 407+14.00 114.00 28.01 354.73 01/STR 39 32 28.67 363.09 01/STR TO 406+00.00 407+14.00 114.00 71 TO 377.91 01/STR 378 406+00.00 407+14.00 114.00 29.84 MITCHELL ROAD 37.44 01/STR 449 123+50.00 TO 124+58.05 449.43 108.05 123+62.05 22.32 01/STR 123+50.00 12.05 16.67 22 **PAVEMENT** TO 01/STR 123+62.05 124+58.05 96.00 380.70 381 123+50.00 123+63.81 15.00 23.02 01/STR 13.81 123+63.81 124+58.05 94.24 389.00 01/STR TO 43 123+63.81 16.67 25.57 01/STR 123+50.00 TO 13.81 123+63.81 TO 124+58.05 01/STR 67 94.24 401.70 01/STR 123+50.00 124+07.80 57.80 24.79 LT 50.25 62.67 01/STR 124+07.80 124+58.05 14 123+50.00 123+63.81 15.00 01/STR 13.81 23.02 TO 94.24 32 123+63.81 124+58.05 352.33 | 01/STR WOO-65-6.18 427+26.84 193.00 25.98 557.14 01/STR 425+33.84 TO 557 425+83.84 18 15 425+33.84 50.00 29.11 161.71 | 01/STR 425+33.84 425+83.84 29.78 165.42 01/STR 50.00 38 425+33.84 425+83.84 01/STR 29 50.00 31.10 172.78 173 34.00 56.67 01/STR 57 9) 425+83.84 TO 425+98.84 15.00 **425+83.84** 56.67 01/STR 57 426+76,84 34.00 426+61,84 15.00 160.93 01/STR 427+26.84 18 15 426+76.84 50.00 28.97 427+26.84 164.63 | 01/STR 38 426+76.84 50.00 29.63 TO 427+26.84 426+76.84 50.00 30.97 172.03 01/STR 172 29 WOO-65-23.39 232+80.00 454.00 1520 237+34.00 30.13 1519.99 | 02/BRO 232+80.00 232+93.05 13.05 27.71 40.18 02/BRO TO 9 7 DESIGN AGENCY TO 232+93.05 47.55 02/BRO 232+80.00 32.79 48 .78/6.18/2 13.05 234+16.70 370.95 87 02/BRO 41 33 232+93.05 TO 123.65 27.00 234+16.70 02/BRO 232+93.05 123.65 34.00 467.12 467 78 234+41.70 25.00 TO 45.58 126.60 02/BRO 127 21) 234+16.70 $\dot{\mathbf{C}}$ 126 21 235+53,09 25.00 45.51 235+28.09 126.41 02/BRO -64/65 DESIGNER 02/BRO 95 45 37 235+53.09 236+88.62 135.53 27.00 406.59 REVIEWER 236+88.62 512.00 02/BRO 512 235+53.09 TO 135.53 34.00 85 DTC 01/22/25 PROJECT ID 237+34.00 139.09 02/BRO 236+88.62 31 15 13 45.38 27.59 107711 236+88.62 TO 237+34.00 45.38 34.54 174.15 02/BRO 174 29 TOTALS CARRIED TO GENERAL SUMMARY P.23 164 3727 624 608 287 20 271