



TYPICAL SECTION IR 475

STATIONS APPLY
STA 0+30 TO 2+55 = 225 FEET

LEGEND

- ① ITEM 202 EXCAVATION
- ② ITEM 203 EMBANKMENT
- ③ 6" ITEM 203 GRANULAR MATERIAL, TYPE B
- ④ 18" ITEM 203 GRANULAR MATERIAL, TYPE D
- ⑤ ITEM 659 TOPSOIL
- ⑥ ITEM 659 SEEDING AND MULCHING

TYPICAL SECTIONS

DESIGN AGENCY



DESIGNER

DAR

REVIEWER

DC 1-12-23

PROJECT ID

115998

SHEET TOTAL

P.3 15

STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	EXCAVATION -END AREA	EMBANKMENT -END AREA	GRANULAR MATERIAL, TYPE B END AREA	GRANULAR MATERIAL, TYPE D END AREA	203	203	203	659	659	659	659	659	203	203	
										EXCAVATION	EMBANKMENT	BORROW	SEEDING AND MULCHING	TOPSOIL	REPAIR SEEDING AND MULCHING	COMMERCIAL FERTILIZER	WATER	LIME	GRANULAR MATERIAL, TYPE B	GRANULAR MATERIAL, TYPE D
					FT	SF	SF	SF	SF	CY	CY	CY	SY	CY	SY	TON	MGAL	ACRE	CY	CY
0+05.00	TO	0+30.00	A	RT	25.00	67.72	483.52	11.60	31.79	31.35	223.85	192.50	194.58	21.60	9.73	0.03	1.05	0.04	5.37	14.72
0+30.00	TO	0+50.00	A	RT	20.00	70.47	440.56	11.14	30.41	51.18	342.25	291.07	307.78	34.16	15.39	0.04	1.66	0.06	8.42	23.04
0+50.00	TO	0+75.00	A	RT	25.00	80.62	480.44	11.48	31.43	69.95	426.39	356.44	381.11	42.30	19.06	0.05	2.06	0.08	10.47	28.63
0+75.00	TO	1+00.00	A	RT	25.00	89.59	507.16	10.98	44.18	74.10	457.22	383.12	381.25	42.32	19.06	0.05	2.06	0.08	10.40	35.01
1+00.00	TO	1+25.00	A	RT	25.00	106.28	536.16	11.75	32.25	86.53	483.02	396.49	380.00	42.18	19.00	0.05	2.05	0.08	10.53	35.38
1+25.00	TO	1+50.00	A	RT	25.00	119.16	529.43	11.75	32.25	104.37	493.33	388.96	379.58	42.13	18.98	0.05	2.05	0.08	10.88	29.86
1+50.00	TO	1+75.00	A	RT	25.00	128.59	530.03	11.75	32.25	114.70	490.49	375.80	380.83	42.27	19.04	0.05	2.06	0.08	10.88	29.86
1+75.00	TO	2+00.00	A	RT	25.00	115.12	547.27	12.37	34.12	112.83	498.75	385.92	380.97	42.29	19.05	0.05	2.06	0.08	11.17	30.73
2+00.00	TO	2+25.00	A	RT	25.00	77.81	611.23	11.75	32.25	89.32	536.34	447.02	378.61	42.03	18.93	0.05	2.04	0.08	11.17	30.73
2+25.00	TO	2+50.00	A	RT	25.00	114.08	436.54	6.75	17.25	88.84	485.08	396.24	368.06	40.85	18.40	0.05	1.99	0.08	8.56	22.92
2+50.00	TO	2+55.00	A	RT	5.00	172.31	409.44	6.75	17.25	26.52	78.33	51.81	71.81	7.97	3.59	0.01	0.39	0.01	1.25	3.19
2+55.00	TO	2+66.00	A	RT	11.00	0.00	0.00	0.00	0.00	35.16	33.40	48.30	79.02	8.77	3.95	0.01	0.43	0.02	1.38	3.51
Extra Areas					AREA(SF)															
ACCESS - EAST					3673.00															
ACCESS - WEST					8807.00															
SUBTOTALS										884.79	4598.47	3713.68	5070.27	562.80	254	0.68	27	1.05	100.47	287.58
TOTALS CARRIED TO GENERAL SUMMARY										885	4598	3714	5071	563	254	0.68	28	1.05	101	288

SUBSUMMARY

DESIGN AGENCY

 DESIGNER
 DAR
 REVIEWER
 BB 7-25-23
 PROJECT ID
 115998
 SHEET TOTAL
 P.7 15