

PORTION TO BE IMPROVED	_
INTERSTATE HIGHWAY	
FEDERAL ROUTES	
STATE ROUTES	_
COUNTY & TOWNSHIP ROADS	_
OTHER ROADS	

DESIGN DESIGNATION

	SR 65	SR 18
CURRENT ADT (2022)	4300	1500
DESIGN YEAR ADT (2034)	4300	1600
DESIGN HOURLY VOLUME (2022)	450	150
DIRECTIONAL DISTRIBUTION	52%	10%
TRUCKS (24 HOUR B&C)	5%	5%
DESIGN SPEED	Varies	Varies
LEGAL SPEED	Varies	Varies
DESIGN FUNCTIONAL CLASSIFICATION:		
Rural Major Collector		
NHS PROJECT	NO	

DESIGN EXCEPTIONS

NONE

ADA DESIGN WAIVERS

H

NONE



INDEX OF SHEETS:

MAINTENANCE OF TRAFFIC NOTES

2-4

5

6

7.8

9-13

14-24

25-28

TITLE SHEET TYPICAL SECTIONS

GENERAL NOTES

SUBSUMMARY

PLAN SHEETS

CROSS SECTIONS

GENERAL SUMMARY

М WOO-65/18-0.00/18.53 DATE (ili) 7×11

FEDERAL PROJECT NUMBER

E150259

RAILROAD INVOLVEMENT

TOLEDO, LAKE ERIE, WESTERN RAILWAY, CSX

PROJECT DESCRIPTION

RESURFACE SR 65 FROM HENRY COUNTY LINE TO SR 235. RESURFACE SR 18 FROM SLM 18.53 TO SLM 19.48. PERFORM NECESSARY RELATED WORK.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: N/A ACRES ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A ACRES NOTICE OF INTENT EARTH DISTURBED AREA! N/A ACRES

2019 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION. INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY EXCEPT AS NOTED ON SHEET 6, AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED DATE 6/25/21 DISTRICT DEPUTY DIRECTON

Jack Marchlanks/AEQ APPROVED DATE 9-9-21 DIRECTOR, DEPARTMENT OF TRANSPORTATION

ESIGNE	R	
	JWZ	
RE	VIEWER	
IMF	06-25-21	
ROJEC	1D	
5	95796	
HEET	TOTAL	
1	28	
_		

DESIGN AGENCY

SHEET

ш Ē

ITEM 614, MAINTAINING TRAFFIC

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

APPLE BUTTER FESTIVAL OCTOBER, 2022

CHRISTMAS FOURTH OF JULY NEW YEAR'S LABOR DAY MEMORIAL DAY THANKSGIVING (OTHER HOLIDAY OR EVENT)

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF HOL	.IDAY TIME ALL LANES
OR EVENT	MUST BE OPEN TO TRAFFIC
SUNDAY	12:00N FRIDAY THROUGH 6:00AM MONDAY

ΜΟΝΠΑΥ 12:00N FRIDAY THROUGH 6:00AM TUESDAY 12:00N MONDAY THROUGH 6:00AM WEDNESDAY TUESDAY WEDNESDAY 12:00N TUESDAY THROUGH 6:00AM THURSDAY THURSDAY 12:00N WEDNESDAY THROUGH 6:00AM FRIDAY THURSDAY (THANKSGIVING ONLY)

6:00AM WEDNESDAY THROUGH 6:00AM MONDAY FRIDAY 12:00N THURSDAY THROUGH 6:00AM MONDAY SATURDAY 12:00N FRIDAY THROUGH 6:00AM MONDAY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS. THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT OF \$5000 FOR EACH DAY THE ABOVE DESCRIBED LANE CLOSURE RESTRICTIONS ARE VIOLATED.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

NOTICE OF CLOSURE SIGNS (W20-H13) SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. EAT THE APPROVAL OF THE ENGINEER, PORTABLE CHANGEABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLATSHEET SIGN FOR CLOSURE DURATIONS OF LESS THAN 1 WEEK.

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE. THE SIGNS MAY BE ERECTED ANYWHERE ON RAMPS AS LONG AS THEY ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS, THE SIGN SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING MOTORISTS.

Notice of Closure Sign Time Table

<u>ltem</u>	Duration of Closure	Sign Displayed to Public
Ramp &	>= 2 weeks	14 calendar days prior to closure
Road	> 12 hours & < 2 weeks	7 calendar days prior to closure
Closures	< 12 hours	2 business days prior to closure

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LAST LINE OF THE W20-HI3 SIGN LISTS A PHONE NUMBER WHICH A MOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS PHONE NUMBER SHALL BE 419-373-4428.

ITEM 614. MAINTAINING TRAFFIC (ROAD CLOSED SIGN)

THE CONTRACTOR SHALL PROVIDE. ERECT AND MAINTAIN STANDARD 48 X 30 INCH ROAD CLOSED SIGNS, SIGN SUPPORTS, BARRICADES AND LIGHTS, AS DETAILED IN SCD MT-101.60 AT THE FOLLOWING LOCATIONS DURING PERIODS IN WHICH THE AFFECTED ROADS ARE CLOSED TO TRAFFIC.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN
ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS
OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF
UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL
LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN
THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING
TRAFFIC UNLESS SEPARATELY ITEMIZED IN THE PLAN.

ITEM 614, REPLACEMENT SIGN

FLATSHEET SIGNS FURNISHED BY THE CONTRACTOR IN ACCOR-DANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICA-TIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT SIGNS SHALL BE NEW. OTHER MATERIALS MAY BE IN USED, BUT GOOD, CONDITION SUBJECT TO APPROVAL BY THE ENGINEER.

PAYMENT FOR THE NEW SIGNS SHALL BE MADE AT THE CONTRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT SIGN, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF DAMAGED SIGNS, HARDWARE AND SUPPORTS, AND PROVIDING THE NECESSARY REPLACEMENT HARDWARE, SUPPORTS, ETC.

AN ESTIMATED QUANTITY OF 5 EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.

ITEM 614, REPLACEMENT DRUM

DRUMS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT DRUMS SHALL BE NEW.

PAYMENT FOR THE NEW DRUMS SHALL BE MADE AT THE CON-TRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT DRUM, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF THE DAMAGED DRUM, AND PROVIDING AND MAINTAINING THE REPLACEMENT DRUM IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS FOR THE ORIGINAL DRUM.

AN ESTIMATED QUANTITY OF 5 EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.

PLACEMENT OF ASPHALT CONCRETE

TWO-WAY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES EXCEPT THAT ONE-WAY TRAFFIC WILL BE PERMITTED FOR MINIMUM PERIODS OF TIME CONSISTENT WITH THE REQUIREMENTS OF THE SPECIFICATIONS FOR PROTECTION OF COMPLETED ASPHALT CONCRETE COURSES.

TEMPORARY WEDGING

ALL TEMPORARY ASPHALT WEDGING/REMOVAL OF WEDGE REQUIRED TO PROVIDE A SMOOTH TRANSITION FROM MILLED SURFACES TO EXISTING SURFACES THROUGHOUT THE PROJECT (INCLUDING DRIVE APPROACHES AND CONCRETE PAVEMENT AREAS IN GRAND RAPIDS) ARE TO BE INCLUDED IN ITEM 614 MAINTAINING TRAFFIC.

WORK ZONE MARKINGS AND SIGNS

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT LOCATIONS IDENTIFIED BY THE ENGINEER FOR WORK ZONE PAVEMENT MARKINGS AND SIGNS PER THE REQUIREMENTS OF CMS 614.04 AND 614.11.

ITEM 614 -	WORK ZONE MARKING SIGN	28 EACH
ITEM 614 -	WORK ZONE EDGE LINE, CLASS I	39 MILE
ITEM 614 -	WORK ZONE CENTERLINE, CLASS I	24 MILE
ITEM 614 -	WORK ZONE STOP LINE, CLASS III	306 FT

ODOT NOTIFICATION CONTACT INFORMATION

THE ODOT PROJECT ENGINEER SHALL FORWARD THE CONSTRUCTION NOTIFICATION INFORMATION THE FOLLOWING DEPARTMENTS WITHIN THE TIMELINE OUTLINED IN TEM PART 642-58 TO ENSURE COMPLIANCE WITH FEDERAL NOTIFICATION REQUIREMENTS:

DISTRICT PUBLIC INFORMATION OFFICER (PIO) BY PHONE AT: (419) 373-4428 OR EMAIL AT: DO2.PIO@DOT.OHIO.GOV

DISTRICT PERMIT SECTION BY PHONE AT: (419) 373-4301 OR EMAIL AT: D02.PERMITS@DOT.OHIO.GOV

NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION (HAULING.PERMITS@DOT.OHIO.GOV) AND THE DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

ITEM

LANE

,	NOTIFICATION T	IME TABLE									
ITEM	DURATION OF CLOSURE	NOTICE DUE TO PERMITS & PIO									
RAMP & ROAD	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE									
CLOSURES	> 12HOURS & < 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE									
	< 12 HOURS	4 CALENDAR DAYS PRIOR TO CLOSURE									
LANE CLOSURES & RESTRICTION	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE									
	< 2 WEEKS	5 BUSINESS DAYS PRIOR TO CLOSURE									
START OF CONSTRUCTIC TRAFFIC PAT CHANGES	DN & N/A TERN	14 CALENDAR DAYS PRIOR TO IMPLEMENTATION									
ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO											

BE REPORTED TO THE PROJECT ENGINEER USING THE

NOTIFICATION TIME TABLE.

- NORTH SIDE OF SR 65 & 2ND ST. INTERSECTION - SOUTH SIDE OF SR 65 & FRONT ST. INTERSECTION

SR 65 INTERSE	CTION MAINTENANCE OF TRAFFIC
THE ROAD SH AS PER THE H NOT EXCEED SHALL BE AS REMAINS CLO	ALL BE CLOSED TO TRAFFIC AND DETOURED ROAD CLOSURE DETOUR. ROAD CLOSURE SHOULD 5 DAYS. DAMAGES IN THE AMOUNT OF \$5000 SESSED FOR EACH CALENDAR DAY THE ROADWAY SED TO TRAFFIC BEYOND THE SPECIFIED LIMIT.
SR 65	SR 65 SHALL BE CLOSED TO TRAFFIC. FROM STA. 53+50 TO STA. 58+50. SR 65 CLOSURE DETOUR: EASTBOUND SR 65 NORTH TO SR 110 WEST SR 110 WEST TO SR 109 NORTH SR 109 NORTH TO OLD US 24 EAST OLD US 24 EAST TO SR 295 SOUTH SR 295 SOUTH TO SR 65 EAST WESTBOUND SR 65 WEST TO SR 295 NORTH SR 295 NORTH TO OLD US 24 WEST OLD US 24 WEST TO SR 109 SOUTH SR 109 SOUTH TO SR 65 EAST SR 65 EAST TO SR 65 SOUTH
DESIGNATED LOCAL DETOUR ROUTE	WAPAKONETA RD TO US-6 TO SR 235 TO KELLOG RD KELLOG RD TO SR 235 TO US 6 TO WAPAKONETA RD

PART 1 AND PART 2 CAN BE DONE CONCURRENTLY.

CSXT RAILROAD SPECIAL PROVISIONS

ROADWAY FLAGGERS MUST BE PRESENT ON EACH SIDE OF THE RAILROAD CROSSING, ANYTIME TRAFFIC IS DIRECTED INTO OPPOSING TRAFFIC LANES AT THE RAILROAD CROSSING. CHANNELIZATION/MOT DEVICES SHALL BE PLACED A MINIMUM OF 15 FT FROM CENTER LINE OF RAILROAD TRACKS.

DESIGNATED LOCAL DETOUR ROUTE

IN ADDITION TO THE OFFICIAL, SIGNED DETOUR ROUTE, A LOCAL ROUTE HAS BEEN DETERMINED TO BE THE SECONDARY, UNSIGNED DETOUR ROUTE OR "DESIGNATED LOCAL DETOUR ROUTE." THIS ROUTE IS SHOWN ABOVE ON THIS SHEET. DURING THE TIME THAT TRAFFIC IS DETOURED, THE CONTRACTOR SHALL MAINTAIN THIS ROUTE IN A CONDITION WHICH IS REASONABLY SMOOTH AND FREE FROM HOLES, RUTS, RIDGES, BUMPS, DUST AND STANDING WATER. ONCE THE DETOUR IS REMOVED AND TRAFFIC RETURNED TO ITS NORMAL PATTERN. THE DESIGNATED LOCAL DETOUR ROUTE SHALL BE RESTORED TO A CONDITION THAT IS EQUIVALENT TO THAT WHICH EXISTED PRIOR TO ITS USE FOR THIS PURPOSE. ALL SUCH WORK SHALL BE PERFORMED WHEN AND AS DETERMINED BY THE ENGINEER.

THE FOLLOWING ESTIMATED QUANTITIES ARE PROVIDED FOR USE AS DETERMINED BY THE ENGINEER TO MAINTAIN AND SUBSEQUENTLY RESTORE THE DESIGNATED LOCAL DETOUR ROUTE.

ITEM 301, ASPHALT CONCRETE BASE ITEM 441, ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG 70-22M

100 CU. YD. 100 CU. YD.

SIGN AGENC





	SHEET NUM.								PART.			ITEM	GRAND				
	5	6	9	10	11	12	13				01/STR/PV	02/MPO/PV	IIEM	EXT	TOTAL		
										-			000	44000	1.0		
	-		400									400	202	11000	LS	ev.	
			499				12 150				12 150	499	202	30000	499	SF	
							12,100				12,100		202	32000	12,100	FT	CURB REMOVED
						2.600	10				2.600		202	38000	2.600	FT	GUARDRAIL REMOVED
															,		
						9					9		202	42000	9	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A
						3					3		202	42010	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E
						7					7		202	42040	7	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T
						3					3		202	42050	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B
						8					8		202	47000	8	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED
	175		357								175	357	203	10000	532	CY	
	200		001								200	007	203	20000	200	CY	EMBANKMENT
	200					36					36		209	15000	36	STA	RESHAPING UNDER GUARDRAIL
	200										200		601	20010	200	CY	CRUSHED AGGREGATE SLOPE PROTECTION
						1,563					1,563		606	15050	1,563	FT	GUARDRAIL, TYPE MGS
						988					988		606	15100	988	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS
						3					3		606	26050	3	EACH	ANCHOR ASSEMBLY, MGS TYPE B
						12					12		606	26150	12	EACH	ANCHOR ASSEMBLY, MGS TYPE E MASH 2016
						7			 		7		606	26550	7	EACH	ANCHOR ASSEMBLY, MGS TYPE T
	-					4					4		606	35002	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1
						4					4		606	35140	4	FACH	BRIDGE TERMINAL ASSEMBLY TYPE 4
							8.100				8.100		608	10000	8.100	SF	4" CONCRETE WALK
							4,050				4.050		608	52000	4.050	SF	CURB RAMP
							15				15		609	26000	15	FT	CURB, TYPE 6
						81					81		614	13310	81	EACH	BARRIER REFLECTOR, TYPE 1 ,BIDIRECTIONAL
									 _								
																	E
									 		5,000		832	30000	5,000	EACH	
	5										5		611	98630	5	EACH	CATCH BASIN ADJUSTED TO GRADE
	ue 2										2		611	98634	2	EACH	CATCH BASIN RECONSTRUCTED TO GRADE
	5										5		611	99654	5	EACH	MANHOLE ADJUSTED TO GRADE
	<u>ی</u> 2										2		611	99660	2	EACH	MANHOLE RECONSTRUCTED TO GRADE
	6/q6										1		623	39500	1	EACH	MONUMENT BOX ADJUSTED TO GRADE
	leets								 _								
ġ											1		638	10800	1	EACH	VALVE BOX ADJUSTED TO GRADE
	Dadwi																
9									 								
	Leeu		12	2							14		209	60500	14	MILE	LINEAR GRADING
	j 12.9										12.9		209	72050	12.9	MILE	PREPARING SUBGRADE FOR SHOULDER PAVIN
	2,471										2,471		253	02000	2,471	CY	PAVEMENT REPAIR
s	96/9																
jzien	2000																
SER		400	85,468	17,779					 		104,669	4 4 4	254	01000	104,669	SY OV	PAVEMENT PLANING, ASPHALT CONCRETE, 3 ½
ы М	58	100	83								100	141	301	46000	241		ASPHALI CONCRETE BASE, PG64-22
55 AI			12 021	2 /00							14 672	220	304	20000	220		
8.54		100	12,021	741							848.8		407	10100	848.8		ASPHALT CONCRETE SURFACE COURSE TYPE
<u>N</u> E	2, 7.0	100									010.0			10100	010.0		
21 T	32.1		4,183	865							5,052.1	28	441	10200	5,080.1	CY	ASPHALT CONCRETE INTERMEDIATE COURSE,
53	59										59		441	50100	59	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE
l ∞ [₽]											73.8		441	50300	73.8	CY	ASPHALT CONCRETE INTERMEDIATE COURSE,
L ID	<u>70.4</u>		3,583								3,632.4	21	442	10000	3,653.4	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5
			1,238	136							1,374		617	10100	1,374	CY	COMPACTED AGGREGATE
	dotop		7 700	4.004							0.040		075	40000	0.040		
			7,708	1,234							8,942		8/5	10000	8,942	LB	LONGITUDINAL JOINT ADHESIVE
L ISIZI	oy.cor								1	1							т
35 ™	Dente				320					1	320		621	00100	320	EACH	RPM
	bw.r				365						365		621	54000	365	EACH	RAISED PAVEMENT MARKER REMOVED
IX 📲					14						14		642	00104	14	MILE	EDGE LINE, 6", TYPE 1
ĭ ĭ ĭ																	
<u>ة</u> ح	đ																

DESCRIPTION	SEE SHEET NO.	
ROADWAY		
		≻
		AR
		Ϊ
		2
		SI
		AL
		L L L
		IN IN
ROSION CONTROL		GE
DRAINAGE		
BIGHNICE		
DAVEMENT		
<u></u>		
6		
n		
1, (446), PG70-22M		
TYPE 2, (446)		DESIGN AGENCY
1, (448), PG70-22M		
I YPE Z, (448) IM, TYPE A (446)		()
· · /		
		DESIGNER . IW/7
RAFFIC CONTROL		REVIEWER
		JIVIF MM-DD-YY PROJECT ID
		95796
		7 28

										209	254	407	407	442	441	617	875	202	203	301
				ION			(M)	(A)) AREA		PHALT	АТ 0.085	AT 0.055	RFACE A (446)	TYPE 2,	ATE	HESIVE	<u>A</u>		E, PG64-
				<u></u>		U U	L L	/1/9		5NIO	, AS	CO CO	CO	YPE	SE,	REG	LADI	IOVE	Z	BASI
	STAT	FION R	ANGE	SE	DE DE		NIC	AF X	I RA	RAC	RETI	ACK	ACK	M, TE	ONC OUF 6)	AGG	INIO	REV	ATIO	E TE
				AL	S.	lsi)	ų į	U U U	L H	AR G	PLAN	50	L DN	NCI 5 M	日 (44 (44 (44	ED	AL J	L	CAV	ACRI 22
				DI			DA D	A RF/	E E	INE/	UT N	CKI		17 CC	PHA DIA	ACT	NIQ	/EMI	ΕX	Ő
				∣≿			/ER	SU			EME	TRA	TRA	HAL	AS RME	IMO	GITL	PA		IALT
							A		S		PAV	NON	NON	ASF	NTE	0	LON			SPF
						FT	FT	SY	SY	MILE	SY	GAL	GAL	CY	CY	CY	LB	SY	CY	CY
		SR 65																		
	1+19.84		<u>5+00.00</u> 10+00.00		LI/RI	380.16	23.90	1009.54		0.14	1009.54	85.81	55.52 73.33	42.06	49.07 64.81	15.25	95.04			
	10+00.00	TO	15+00.00		LT/RT	500.00	23.60	1311.11		0.19	1311.11	111.44	72.11	54.63	63.73	20.06	125.00			
	15+00.00		20,00,00			500.00	26.50	2027 79		0.10	2027 79	170.06	111 50	94.40	09.57	20.06	105.00			
	20+00.00	TO	31+50.00		LT/RT	1150.00	24.60	3143.33		0.19	3143.33	267.18	172.88	130.97	152.80	46.14	287.50			
	31+50.00	ТО	43+00.00		LT/RT	1150.00	23.50	3002.78		0.44	3002.78	255.24	165.15	125.12	145.97	46.14	287.50			
	ፈ3+በበ በበ	то	53+00.00		I T/RT	1000.00	23.30	2588.80		<u> </u>	2588.89	220.06	142 30	107.87	125.85	<u>40 12</u>	250.00			
	53+00.00	TO	59+00.00		LT/RT	600.00	29.60	1973.33		0.23	1973.33	167.73	108.53	82.22	95.93	24.07	150.00			
	F0 00 00		04 00 55				07.65	4 105			4.05	410.17			00.05		405.00			
	59+00.00 64+00.00	10 TO	64+00.00		LI/RI	500.00	25.30 24.60	4373 33		0.19	1405.56 4373.33	119.47 371.73	77.31 240.53	58.56	68.33	20.06	125.00			
	80+00.00	TO	90+00.00		LT/RT	1000.00	25.90	2877.78		0.38	2877.78	244.61	158.28	119.91	139.89	40.12	250.00			
	00+00-00	то	01 + 99 00			100.00	26.60	EEE CA		0.07	EEE CA	47.00	20.56	00.15	27.01	7 5 4	47.00			
	90+00.00 93+65.00	TO	91+88.00		LT/RT	135.00	26.60	399.00		0.07	399.00	33.92	21.95	16.63	19.40	7.54 5.42	33.75			
	95+00.00	TO	100+00.00		LT/RT	500.00	25.20	1400.00		0.19	1400.00	119.00	77.00	58.33	68.06	20.06	125.00			
	100+00.00	TO	203+00.00		LT/RT	10300.00	23.60	27008.89		3.90	27008.89	2295.76	1485.49	1125.37	1312.93	413.27	2575.00			
	203+00.00	то	252+00.00		LT/RT	4900.00	23.60	12848.89		1.86	12848.89	1092.16	706.69	535.37	624.60	196.60	1225.00			
	252+00.00	TO	257+00.00		LT/RT	500.00	28.00	1555.56		0.19	1555.56	132.22	85.56	64.81	75.62	20.06	125.00			
	257+00.00	10	262+00.00		LI/RI	500.00	23.90	1327.78		0.19	1327.78	112.86	73.03	55.32	64.54	20.06	125.00			
	262+00.00	то	311+27.68		LT/RT	4927.68	23.90	13085.73		1.87	13085.73	1112.29	719.72	545.24	636.11	197.72	1231.92			
dgn	Wi	idenina S	R 65																	
S001.	53+47.00	TO	58+25.00		RT	478.00	8.70		499.00			55.00		21.00	28.00			499.00	357.00	83.00
5796_C																				
eets\9{																				
'ay\Sh	h	ntersectio	ons			00.00	10.00		00.00		00.00	7.00	4.02	0.70	4.00					
Roadw		Beach S	n t.		RT/LT	69.00	12.00		183.90		183.90	15.63	4.93	7.66	4.36 8.94					
ering∖l		West St			RT/LT	51.00	13.50		200.10		200.10	17.01	11.01	8.34	9.73					
Engine		Beaver S Mill St	St.		RT/LT	95.00	15.00		251.10		251.10	21.34	13.81	10.46	12.21					
3\400-E	Wa	apakoneta	a Rd.		RT	52.00	79.00		242.70		242.70	20.63	13.35	10.11	11.80					
195796		E. 2nd S	t.		RT	32.00	23.00		56.50		56.50	4.80	3.11	2.35	2.75					
///vood		Monroe S	 St.		RT	37.00	54.40 16.00		46.20		46.20	3.93	2.54	9.97 1.93	2.25					
rict 02'		E, Bridge	St.		RT	64.00	16.00		75.40		75.40	6.41	4.15	3.14	3.67					
ts\Dist	10	SR 295			LT	137.00	55.00		317.90		317.90	27.02	17.48	13.25	15.45					
Projec	S	Sycamore	Rd.		RT	68.00	10.00		52.70		52.70	4.48	2.90	2.20	2.56					
Active	Be	enschoter	Rd.		RT	75.00	9.00		61.20		61.20	5.20	3.37	2.55	2.98					
ts\01,		vveston R	(0.		RI	110.00	13.00		130,50		130,50	11.09	7.18	5.44	6.34					
ocume																				
-02/Do																				
ndot-pw																				
m:ohio																				
tley.co.																				
w.ben.																				
odot-p																				
w:\\oh									BTOTALS	11.70	85467.95	7319.77	4700.75	3582.15	4182.71	1237.01	7707.71	499.00	357.00	83.00
đ					TUTALS	CARRIEL		NERAL SU	μημακί	12	00400	1320	4/01	3003	4103	1230	1100	499	30 <i>1</i>	03

	304				
	ш				
	AS				
	6				
	5				
	Ö				
	A A				
	CY				
	01				
				 	ы
					ě,
					~
					5
					単
					<u>ب</u>
					<i>б</i>
					\succ
					Ŕ
					\checkmark
					5
					11
					5
					2
					000
					<u> </u>
					2
					0)
	111 00				
			 	 	DESIGN AGENCY
					\frown
					DESIGNER
					JVVZ
					REVIEWER
					JMF MM-DD-YY
					PROJECT ID
					95796
	111.00				SHEET TOTAL
	111				9 28
_					



MODEL: Sneet PAPERSIZE: 17x11 (in.) DATE: 9/23/2021 TIME: 1151:20 PM USER: Jziems pw://ohiodot-pw.bentley.com:ohiodot-pw-02/Documents/OlActive Projects/DIs

WOO-65/18-0.00/18.53