

## Estimate Estimator

Estimated Cost:\$4,722,899.31

Contingency: 5.20%

**Estimated Total: \$4,968,490.07**

STAGE 3

**Base Date: 04/15/26**

Spec Year: 23

Unit System: E

Work Type: ASPHALT

Highway Type:

Urban/Rural Type: URBAN CLASS

Season: SUMMER

County: HAMILTON

Latitude of Midpoint: 391205

Longitude of Midpoint: -842347

District: 08

Federal/State Project Number:

*Prepared by KJC on 04/15/26*

*Checked by SEF on 04/15/26*

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					

Group 0100: ROADWAY

0005	202E23000 PAVEMENT REMOVED	9,732.000	SY	\$12.88404	\$125,387.48
0006	202E30000 WALK REMOVED	13,692.000	SF	\$6.12919	\$83,920.87
0007	202E32000 CURB REMOVED	4,842.000	FT	\$15.20515	\$73,623.34
0008	202E35100 PIPE REMOVED, 24" AND UNDER	2,289.000	FT	\$18.11975	\$41,476.11
0009	202E35200 PIPE REMOVED, OVER 24"	553.000	FT	\$73.34324	\$40,558.81
0010	202E38000 GUARDRAIL REMOVED	24.000	FT	\$4.06570	\$97.58
0011	202E58000 MANHOLE REMOVED	16.000	EACH	\$982.77224	\$15,724.36
0012	202E58100 CATCH BASIN REMOVED	19.000	EACH	\$984.25197	\$18,700.79
0013	203E10000 EXCAVATION	75.000	CY	\$49.49659	\$3,712.24
0014	203E20000 EMBANKMENT	92.000	CY	\$45.39786	\$4,176.60
0015	203E35120 GRANULAR MATERIAL, TYPE C , 12"	3,318.000	CY	\$41.23562	\$136,819.79
0016	203E98000 ROADWAY, MISC.: ROCK MULCH, 18" MIN. DEPTH	75.000	CY	\$90.00000	\$6,750.00
0017	204E10000 SUBGRADE COMPACTION	10,145.000	SY	\$3.04737	\$30,915.57
0018	204E13000 EXCAVATION OF SUBGRADE , 12" DEEP	3,318.000	CY	\$55.65678	\$184,669.20
0019	204E50000 GEOTEXTILE FABRIC	9,952.000	SY	\$0.97953	\$9,748.28
0020	608E10000 4" CONCRETE WALK	9,155.000	SF	\$9.89424	\$90,581.77
0021	608E13020 7" CONCRETE WALK	2,000.000	SF	\$0.00000	\$0.00

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					
0022	608E52000 CURB RAMP	1,933.000	SF	\$29.67861	\$57,368.75
0023	608E53020 DETECTABLE WARNING	32.000	SF	\$51.77536	\$1,656.81
0024	608E98000 WALKWAY, MISC.: BRICK PAVERS	2,003.000	SF	\$55.00000	\$110,165.00
0025	638E10800 VALVE BOX ADJUSTED TO GRADE	48.000	EACH	\$575.76291	\$27,636.62
0026	690E98000 SPECIAL - CONCRETE PARKING BLOCK	227.000	EACH	\$165.00000	\$37,455.00
0027	690E65016 SPECIAL - WORK INVOLVING PETROLEUM CONTAMINATED SOIL	100.000	TON	\$87.02830	\$8,702.83

Total for Group 0100:\$1,109,847.80

**Group 0200:** EROSION CONTROL

0028	659E00100 SOIL ANALYSIS TEST	2.000	EACH	\$108.63653	\$217.27
0029	659E00300 TOPSOIL	122.000	CY	\$60.44141	\$7,373.85
0030	659E00500 SEEDING AND MULCHING, CLASS 1	1,096.000	SY	\$1.15894	\$1,270.20
0031	659E14000 REPAIR SEEDING AND MULCHING	55.000	SY	\$1.34805	\$74.14
0032	659E20000 COMMERCIAL FERTILIZER	1.000	TON	\$1,323.28128	\$1,323.28
0033	659E31000 LIME	1.000	ACRE	\$189.39822	\$189.40
0034	659E35000 WATER	6.000	MGAL	\$5.31086	\$31.87
0294	832E15000 STORM WATER POLLUTION PREVENTION PLAN	1.000	LS	\$2,000.00000	\$2,000.00
0295	832E15002 STORM WATER POLLUTION PREVENTION INSPECTIONS	1.000	LS	\$8,000.00000	\$8,000.00
0296	832E15010 STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	1.000	LS	\$11,000.00000	\$11,000.00

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
0297	832E30000 EROSION CONTROL	33,916.000	EACH	\$1.00000	\$33,916.00

Total for Group 0200:\$65,396.01

Group 0300: DRAINAGE

0036	605E14000 6" BASE PIPE UNDERDRAINS	3,633.000	FT	\$13.42222	\$48,762.93
0037	611E00510 6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	190.000	FT	\$37.29322	\$7,085.71
0038	611E04400 12" CONDUIT, TYPE B	1,161.000	FT	\$104.64499	\$121,492.83
0039	611E05900 15" CONDUIT, TYPE B	30.000	FT	\$203.95814	\$6,118.74
0040	611E07400 18" CONDUIT, TYPE B	426.000	FT	\$167.84930	\$71,503.80
0041	611E10400 24" CONDUIT, TYPE B	678.000	FT	\$185.15955	\$125,538.17
0042	611E13400 30" CONDUIT, TYPE B	369.000	FT	\$254.99973	\$94,094.90
0043	611E16400 36" CONDUIT, TYPE B	307.000	FT	\$262.01924	\$80,439.91
0044	611E20900 48" CONDUIT, TYPE B	10.000	FT	\$688.81728	\$6,888.17
0045	611E98150 CATCH BASIN, NO. 3	13.000	EACH	\$5,764.07443	\$74,932.97
0046	611E98180 CATCH BASIN, NO. 3A	3.000	EACH	\$4,582.12250	\$13,746.37
0047	611E98370 CATCH BASIN, NO. 6	11.000	EACH	\$3,924.59528	\$43,170.55
0048	611E99654 MANHOLE ADJUSTED TO GRADE	9.000	EACH	\$971.91222	\$8,747.21
0049	611E99574 MANHOLE, NO. 3	18.000	EACH	\$6,150.00000	\$110,700.00
0050	611E99582 MANHOLE, NO. 3 WITH 90" BASE I.D. AND 8" WEIR	1.000	EACH	\$16,723.52889	\$16,723.53

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
0051	895E10020	1.000	EACH	\$21,932.03571	\$21,932.04
	MANUFACTURED WATER QUALITY STRUCTURE, TYPE 2				

Total for Group 0300:\$851,877.83

**Group 0400: PAVEMENT**

0052	254E01000	3,578.000	SY	\$5.30447	\$18,979.39
	PAVEMENT PLANING, ASPHALT CONCRETE , 3"				
0053	301E56000	2,353.000	CY	\$168.03614	\$395,389.04
	ASPHALT CONCRETE BASE, PG64-22, (449)				
0054	304E20000	1,659.000	CY	\$75.05422	\$124,514.95
	AGGREGATE BASE				
0055	407E20000	2,195.000	GAL	\$4.08361	\$8,963.52
	NON-TRACKING TACK COAT				
0056	441E70000	542.000	CY	\$259.32453	\$140,553.90
	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22				
0057	441E70200	542.000	CY	\$272.20318	\$147,534.12
	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (449)				
0058	452E11010	193.000	SY	\$115.00000	\$22,195.00
	7" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P				
0059	609E24510	3,381.000	FT	\$34.00000	\$114,954.00
	CURB, TYPE 4-C				
0060	609E33200	1,728.000	FT	\$30.00000	\$51,840.00
	CURB, TYPE 10-B				

Total for Group 0400:\$1,024,923.92

**Group 0750: ODOT CONTRACT LIGHTING**

0285	625E25409	1,862.000	FT	\$12.00000	\$22,344.00
	CONDUIT, 2", 725.051, AS PER PLAN				
0286	625E25504	3,784.000	FT	\$12.19051	\$46,128.89
	CONDUIT, 3", 725.051				
0287	625E25908	1,010.000	FT	\$60.00000	\$60,600.00
	CONDUIT, JACKED OR DRILLED, 725.052 , 3"				
0288	625E25909	422.000	FT	\$60.00000	\$25,320.00
	CONDUIT, JACKED OR DRILLED, 725.052, AS PER PLAN , 2"				
0289	625E29011	1,892.000	FT	\$25.00000	\$47,300.00
	TRENCH, 30" DEEP, AS PER PLAN				

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
0290	625E30520 PULL BOX, 725.06, SIZE 7	15.000	EACH	\$1,250.41709	\$18,756.26
0291	625E31600 PULL BOX, MISC.: DUKE PULL BOX, INSTALLATION ONLY	12.000	EACH	\$800.00000	\$9,600.00
0292	625E36010 UNDERGROUND WARNING/MARKING TAPE	1,892.000	FT	\$1.72124	\$3,256.59
0293	625E98000 LIGHTING, MISC.: DUKE LIGHTING (not finalized)	1.000	EACH	\$265,000.00000	\$265,000.00

Total for Group 0750:\$498,305.74

Group 1100: TRAFFIC CONTROL

0125	630E03101 GROUND MOUNTED SUPPORT, NO. 3 POST, AS PER PLAN	716.000	FT	\$20.00000	\$14,320.00
0126	630E08600 SIGN POST REFLECTOR	5.000	EACH	\$48.70882	\$243.54
0127	630E80101 SIGN, FLAT SHEET, AS PER PLAN	168.000	SF	\$35.00000	\$5,880.00
0128	630E84900 REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	25.000	EACH	\$12.28648	\$307.16
0129	630E85100 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	2.000	EACH	\$94.25927	\$188.52
0130	630E86002 REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	17.000	EACH	\$20.70202	\$351.93
0131	630E87520 REMOVAL OF POLE MOUNTED SIGN AND REERECTION	2.000	EACH	\$142.90972	\$285.82
0132	630E97700 SIGNING, MISC.: STREET NAME SIGN, AS PER PLAN	10.000	EACH	\$85.00000	\$850.00
0133	644E00300 CENTER LINE	0.460	MILE	\$7,229.92063	\$3,325.76
0134	644E00400 CHANNELIZING LINE, 8"	80.000	FT	\$3.02048	\$241.64
0135	644E00500 STOP LINE	125.000	FT	\$8.92224	\$1,115.28
0136	644E00620 CROSSWALK LINE, 12"	727.000	FT	\$4.28228	\$3,113.22

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
0137	644E00700 TRANSVERSE/DIAGONAL LINE , WHITE	1,365.000	FT	\$6.07836	\$8,296.96
0138	644E00700 TRANSVERSE/DIAGONAL LINE , YELLOW	14.000	FT	\$6.07836	\$85.10
0139	644E00900 ISLAND MARKING , YELLOW	14.000	SF	\$5.19310	\$72.70
0140	644E01200 PARKING LOT STALL MARKING , 4"	3,048.000	FT	\$2.27274	\$6,927.31
0141	644E01300 LANE ARROW	2.000	EACH	\$145.41675	\$290.83
0142	644E19000 SHARED LANE MARKING	21.000	EACH	\$431.97511	\$9,071.48
0143	647E50110 PAVEMENT MARKING, MISC.: DECORATIVE CROSSWALK	2,974.000	SF	\$35.00000	\$104,090.00

Total for Group 1100:\$159,057.25

**Group 1600:** TRAFFIC SIGNALS

0221	625E00450 CONNECTION, FUSED PULL APART	4.000	EACH	\$181.50300	\$726.01
0222	625E00460 CONNECTION, UNFUSED PULL APART	4.000	EACH	\$140.94256	\$563.77
0223	625E00480 CONNECTION, UNFUSED PERMANENT	6.000	EACH	\$148.46600	\$890.80
0224	625E18001 BRACKET ARM, 10', AS PER PLAN	1.000	EACH	\$1,000.00000	\$1,000.00
0225	625E18201 BRACKET ARM, 15', AS PER PLAN	1.000	EACH	\$1,250.00000	\$1,250.00
0226	625E18501 BRACKET ARM, 25', AS PER PLAN	1.000	EACH	\$1,500.00000	\$1,500.00
0227	625E18511 BRACKET ARM, 30', AS PER PLAN	1.000	EACH	\$2,100.00000	\$2,100.00
0228	625E23000 NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	411.000	FT	\$4.33026	\$1,779.74
0229	625E23304 NO. 8 AWG 600 VOLT DISTRIBUTION CABLE	1,008.000	FT	\$2.80456	\$2,827.00
0230	625E23400 NO. 10 AWG POLE AND BRACKET CABLE	1,038.000	FT	\$1.90795	\$1,980.45

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					
0231	625E25400 CONDUIT, 2", 725.04	19.000	FT	\$33.39825	\$634.57
0232	625E25408 CONDUIT, 2", 725.051	125.000	FT	\$12.65831	\$1,582.29
0233	625E25504 CONDUIT, 3", 725.051	34.000	FT	\$12.19051	\$414.48
0234	625E25600 CONDUIT, 4", 725.04	30.000	FT	\$68.85708	\$2,065.71
0235	625E25604 CONDUIT, 4", 725.051	30.000	FT	\$21.38062	\$641.42
0236	625E25908 CONDUIT, JACKED OR DRILLED, 725.052 , 2"	188.000	FT	\$50.00000	\$9,400.00
0237	625E25908 CONDUIT, JACKED OR DRILLED, 725.052 , 4"	188.000	FT	\$65.00000	\$12,220.00
0238	625E26253 LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN IES-III, LED 9500-11000 LUMENS, AS PER PLAN	4.000	EACH	\$650.00000	\$2,600.00
0239	625E29000 TRENCH	144.000	FT	\$12.09261	\$1,741.34
0240	625E30520 PULL BOX, 725.06, SIZE 7	4.000	EACH	\$1,250.41709	\$5,001.67
0241	625E30700 PULL BOX, 725.08, 18"	1.000	EACH	\$1,105.61985	\$1,105.62
0242	625E30706 PULL BOX, 725.08, 24"	1.000	EACH	\$1,383.36349	\$1,383.36
0243	625E31510 PULL BOX REMOVED	3.000	EACH	\$367.26906	\$1,101.81
0244	625E32000 GROUND ROD	10.000	EACH	\$377.36026	\$3,773.60
0245	625E36010 UNDERGROUND WARNING/MARKING TAPE	144.000	FT	\$1.72124	\$247.86
0246	630E79100 SIGN HANGER ASSEMBLY, MAST ARM	6.000	EACH	\$356.77385	\$2,140.64
0247	630E80100 SIGN, FLAT SHEET	8.000	SF	\$29.77018	\$238.16
0248	631E90501 INTERNALLY ILLUMINATED FIXED MESSAGE SIGN, AS PER PLAN , D3-1	4.000	EACH	\$2,500.00000	\$10,000.00
0249	632E05006 VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, PO LYCARBONATE , BLACK	7.000	EACH	\$1,032.48998	\$7,227.43

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					
0250	632E05086	1.000	EACH	\$1,835.31292	\$1,835.31
VEHICULAR SIGNAL HEAD, (LED), 5-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, BLACK					
0251	632E20730	6.000	EACH	\$563.94012	\$3,383.64
PEDESTRIAN SIGNAL HEAD (LED), TYPE D2, COUNTDOWN					
0252	632E20750	6.000	EACH	\$904.92554	\$5,429.55
ACCESSIBLE PEDESTRIAN PUSHBUTTON					
0253	632E25000	8.000	EACH	\$42.46275	\$339.70
COVERING OF VEHICULAR SIGNAL HEAD					
0254	632E25010	6.000	EACH	\$35.23735	\$211.42
COVERING OF PEDESTRIAN SIGNAL HEAD					
0255	632E40400	319.000	FT	\$3.50000	\$1,116.50
SIGNAL CABLE, 4 CONDUCTOR, NO. 14 AWG					
0256	632E40500	1,538.000	FT	\$3.06594	\$4,715.42
SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG					
0257	632E40700	702.000	FT	\$4.00000	\$2,808.00
SIGNAL CABLE, 7 CONDUCTOR, NO. 14 AWG					
0258	632E64010	4.000	EACH	\$5,340.02142	\$21,360.09
SIGNAL SUPPORT FOUNDATION					
0259	632E64020	4.000	EACH	\$1,284.94545	\$5,139.78
PEDESTAL FOUNDATION					
0260	632E65300	879.000	FT	\$2.02198	\$1,777.32
LOOP DETECTOR LEAD-IN CABLE, 2 CONDUCTOR, NO. 14 AWG					
0261	632E68300	45.000	FT	\$6.55988	\$295.19
POWER CABLE, 3 CONDUCTOR, NO. 6 AWG					
0262	632E69500	55.000	FT	\$6.00000	\$330.00
SERVICE CABLE, 2 CONDUCTOR, NO. 6 AWG					
0263	632E70001	1.000	EACH	\$4,000.00000	\$4,000.00
POWER SERVICE, AS PER PLAN					
0264	632E79111	2.000	EACH	\$14,000.00000	\$28,000.00
COMBINATION SIGNAL SUPPORT, TYPE TC-81.22, DESIGN 4, AS PER PLAN					
0265	632E79131	2.000	EACH	\$18,500.00000	\$37,000.00
COMBINATION SIGNAL SUPPORT, TYPE TC-81.22, DESIGN 12, AS PER PLAN					
0266	632E89803	3.000	EACH	\$700.00000	\$2,100.00
PEDESTAL, 5', TRANSFORMER BASE, AS PER PLAN					
0267	632E90001	1.000	EACH	\$1,200.00000	\$1,200.00
PEDESTAL, 11', TRANSFORMER BASE, AS PER PLAN					
0268	632E90101	1.000	EACH	\$4,000.00000	\$4,000.00
REMOVAL OF TRAFFIC SIGNAL INSTALLATION, AS PER PLAN					

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					
0269	633E65511 CABINET, TYPE TS-2, AS PER PLAN	1.000	EACH	\$18,000.00000	\$18,000.00
0270	633E67100 CABINET FOUNDATION	1.000	EACH	\$2,242.07392	\$2,242.07
0271	633E75001 UNINTERRUPTIBLE POWER SUPPLY (UPS), 1000 WATT, AS PER PLAN	1.000	EACH	\$8,200.00000	\$8,200.00
0272	809E69100 STOP LINE RADAR DETECTION	5.000	EACH	\$8,586.88527	\$42,934.43
0273	809E69123 ATC CONTROLLER, AS PER PLAN	1.000	EACH	\$5,800.00000	\$5,800.00
0274	819E10000 RAILROAD PREEMPTION INTERFACE , BLUE ASH AT WEBSTER CROSSING #525278F	1.000	EACH	\$5,000.00000	\$5,000.00
0275	828E00100 LED BLANKOUT SIGN , R3-2 w/ "TRAIN"	2.000	EACH	\$4,760.22339	\$9,520.45

Total for Group 1600:\$294,876.60

**Group 2100:** MAINTENANCE OF TRAFFIC

0144	614E11110 LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	20.000	HOUR	\$95.26660	\$1,905.33
0145	614E12420 DETOUR SIGNING	1.000	LS	\$78,000.00000	\$78,000.00
0146	614E21100 WORK ZONE CENTER LINE, CLASS I, 642 PAINT	0.460	MILE	\$2,244.05725	\$1,032.27
0147	614E21550 WORK ZONE CENTER LINE, CLASS III, 642 PAINT	0.460	MILE	\$2,214.97298	\$1,018.89
0148	614E22100 WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT	0.460	MILE	\$1,382.87605	\$636.12
0149	614E22350 WORK ZONE EDGE LINE, CLASS III, 4", 642 PAINT	0.460	MILE	\$1,101.72712	\$506.79
0150	614E23200 WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	80.000	FT	\$1.03107	\$82.49
0151	614E23680 WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	80.000	FT	\$1.04382	\$83.51
0152	614E25200 WORK ZONE TRANSVERSE/DIAGONAL LINE, CLASS I, 642 PAINT	14.000	FT	\$3.00000	\$42.00

<u>Line #</u>	<u>Item Number</u>	<u>Quantity</u>	<u>Units</u>	<u>Unit Price</u>	<u>Extension</u>
<u>Description</u>					
<u>Supplemental Description</u>					
0153	614E25620	14.000	FT	\$3.00000	\$42.00
WORK ZONE TRANSVERSE/DIAGONAL LINE, CLASS III, 642 PAINT					
0154	614E26200	125.000	FT	\$4.19779	\$524.72
WORK ZONE STOP LINE, CLASS I, 642 PAINT					
0155	614E26610	125.000	FT	\$4.33270	\$541.59
WORK ZONE STOP LINE, CLASS III, 642 PAINT					
0156	614E27050	727.000	FT	\$2.36169	\$1,716.95
WORK ZONE CROSSWALK LINE, CLASS I, 12", 642 PAINT					
0157	614E27250	727.000	FT	\$2.17698	\$1,582.66
WORK ZONE CROSSWALK LINE, CLASS III, 12", 642 PAINT					
0158	614E30200	2.000	EACH	\$68.69344	\$137.39
WORK ZONE ARROW, CLASS I, 642 PAINT					
0159	614E30650	2.000	EACH	\$79.43494	\$158.87
WORK ZONE ARROW, CLASS III, 642 PAINT					
0160	614E32700	14.000	SF	\$2.00000	\$28.00
WORK ZONE ISLAND MARKING, CLASS I					
0161	614E32800	14.000	SF	\$2.00000	\$28.00
WORK ZONE ISLAND MARKING, CLASS III, 642 PAINT					
0162	616E10000	6.000	MGAL	\$91.09610	\$546.58
WATER					

Total for Group 2100:\$88,614.16

**Group 2300: INCIDENTALS**

0163	614E11000	1.000	LS	\$65,000.00000	\$65,000.00
MAINTAINING TRAFFIC					
0164	623E10000	1.000	LS	\$225,000.00000	\$225,000.00
CONSTRUCTION LAYOUT STAKES AND SURVEYING					
0165	624E10000	1.000	LS	\$340,000.00000	\$340,000.00
MOBILIZATION					

Total for Group 2300:\$630,000.00