## HAM-IR 74-11.16

## STATE OF OHIO **DEPARTMENT OF TRANSPORTATION**

HAM-IR 74-11.16

## HAMILTON COUNTY

#### **LOCATION MAP**

LATITUDE: N39°11'47" LONGITUDE: W84°39'51"

SEE SHEETS 2-3.3A

#### **DESIGN DESIGNATION**

CURRENT ADT (20 )	36,500	44,000	63,000
DESIGN YEAR ADT (20 )	36,500	56,500	77,000
DESIGN HOURLY VOLUME (20 )	3,600	5,600	7,700
DIRECTIONAL DISTRIBUTION	60.2%	60.2%	53.8%
TRUCKS (24 HOUR B&C)	9.0%	8.0%	8.0%
DESIGN SPEED	60 MPH	70 MPH	70 MPH
LEGAL SPEED	55 MPH	65 MPH	65 MPH
DESIGN FUNCTIONAL CLASSIFICATION:			
HAM-74 11.20-18.0 01 Interstate (Urban)			

NHS PROJECT \_\_\_\_\_\_ YES

**DESIGN EXCEPTIONS** 

#### ADA DESIGN WAIVERS

#### UNDERGROUND UTILITIES Contact Two Working Days Before You Dig

🖈 0H10811.org Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764 (Non members must be called directly)

PLAN PREPARED BY: OHIO DEPARTMENT OF TRANSPORTATION DISTRICT 8 ENGINEERING 505 SOUTH S.R. 741 LEBANON, OHIO, 45036

#### **INDEX OF SHEETS:**

TITLE SHEET	1
LOCATION MAP	2-3, 3A
GENERAL NOTES	4-6
MAINTENANCE OF TRAFFIC NOTES	7-9
GENERAL SUMMARY	10-11
PAVEMENT CALCULATIONS	12
PAVEMENT MARKINGS	13
GUARDRAIL/CURB RAMP QUANTITIES	14
CURB RAMP DETAILS	15
STRUCTURE NOTES	16-17
CONCRETE SEALING DETAILS	18
STRUCTURE QUANTITIES	19-20
STRUCTURE REPAIR	
HAM-74-11.16 L/R	21-30
HAM-74-12.92 L/R	31-38
HAM-74-16.18 L/R HAM-74-17 44 I /R	39-49
NAIVI-14-11.44 L/K	50-53

#### FEDERAL PROJECT NUMBER

E121002

#### RAILROAD INVOLVEMENT

NONE

#### **PROJECT DESCRIPTION**

MINOR PAVEMENT REHABILITATION ON IR-74 FROM NORTH OF BEEKMAN ST. TO SOUTH OF HARRISON AVE. BRIDGE REPAIRS INCLUDE CONCRETE SEALING, BRIDGE PAINTING, CONCRETE PATCHING AND GUARDRAIL UPGRADES.

#### EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: ESTIMATED CONTRACTOR EARTH DISTURBED AREA: 0.0 ACRES NOTICE OF INTENT EARTH DISTURBED AREA: N/A ACRES

#### LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.


#### **2023 SPECIFICATIONS**

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.


		ST	ANDARD	CONSTRUCTION	DRAWINGS	SUPPLEI SPECIFIC		SPECIAL PROVISIONS	
BP-3.1	1/19/24	MT-95.30	7/19/19	MT-101.90 7/17/20		800-2023	1/19/24	ULTRA SONIC	1
BP-7.1	7/21/23	MT-95.31	7/19/19	MT-102.20 4/19/19		807	1/21/22	TESTING AND	1
BP-9.1	1/18/19	MT-95.32	4/19/19	MT-102.30 10/16/15		808	1/18/19	INSPECTION	
		MT-95.40	7/21/23	MT-103.10 1/21/22		809	7/21/23	10/6/23	
MGS-1.1	7/16/21	MT-95.45	7/21/23	MT-104.10 4/26/23		821	4/20/12		L
MGS-2.1	1/19/18	MT-95.50	7/21/17	MT-105.10 1/17/20		832	7/21/23	ASBESTOS	1
MGS-4.3	1/18/13	MT-97.10	4/19/19			850	7/21/23	INSPECTION	1
MGS-5.3	7/15/16	MT-98.10	1/17/20	TC-61.30 7/19/19		872	1/21/22	REPORT	1
RM-4.2	4/17/20	MT-98.11	1/17/20	TC-65.11 7/15/22		878	1/21/22	10/6/23	1
RM-4.5	7/21/17	MT-98.21	7/21/23	TC-71.10 4/26/23		896	7/21/17		1
RM-4.6	7/19/13	MT-98.22	1/17/20	TC-72.20 7/21/23		905	4/17/20		1
		MT-98.29	1/17/20	TC-73.20 7/21/23		908	10/20/17		1
BR-1-13	1/17/14	MT-98.30	7/16/21	TC-74.10 7/21/23		909	7/21/23		1
EXJ-4-87	7/21/23	MT-101.70	4/26/23			921	4/20/12		1
GSD-1-19	1/15/21	MT-101.75	7/21/23						1
PCB-91	7/17/20	MT-101.80	1/17/20						1

ENGINEER'S SEAL
ROADWAY
JOHN DENNIS OTIS E-70344





ESIGNE	2
l	NCD
RE	VIEWER
DO	9/20/23
ROJECT	ID
8	8679
HEET	TOTAL
0.4	F 2




RAMP LOCATIONS

DES**I**GN AGENCY



DESIGNER NCD
REVIEWER
JDO 9/20/23
PROJECT ID
88679

88679 SHEET TOTAL 03 53



DES**I**GN AGENCY



DESIGNER
JED

REVIEWER
JDO 9/20/23

PROJECT ID

88679

SHEET TOTAL
03A 53

#### **CONTINGENCY QUANTITIES**

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK LISTED IN THE GENERAL SUMMARY FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER UNLESS AUTHORIZED BY THE ENGINEER". THE ACTUAL WORK LOCATIONS AND QUANTITIES USED AT THE ENGINEER'S DIRECTION SHALL BE MADE A MATTER OF RECORD BY INCORPORATION INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THE PROJECT.

#### PERMANENT PAVEMENT MARKINGS

THE CONTRACTOR SHALL REFERENCE ALL PAVEMENT MARKINGS INCLUDING AUXILIARY PAVEMENT MARKINGS BEFORE THE START OF THE RESURFACING OPERATION. THIS WILL BE NECESSARY TO ASSURE THE CORRECT PLACEMENT OF MARKINGS IN ORIGINAL LOCATIONS EXCEPT AS NOTED: EXIT RAMP GORES SHALL FOLLOW PAYMENT FOR THIS OPERATION SHALL BE INCLUDED WITH MARKING LAYOUT PER TC-72.20.


PAYMENT FOR THIS OPERATION SHALL BE INCLUDED WITH EACH RESPECTIVE PAVEMENT MARKING ITEM.

#### ITEM 623- CONSTRUCTION LAYOUT STAKES, AS PER PLAN

PRIOR TO THE START OF ROADWAY OPERATION, THE CONTRACTOR SHALL REFERENCE THE LENGTH OF THE PROJECT ON BOTH SIDES OF THE ROADWAY, IN A MANNER SATISFACTORY TO THE ENGINEER. THE PAVEMENT SHALL BE REFERENCED IN 500' FEET INCREMENTS, OR IN INCREMENTS ACCEPTABLE TO THE ENGINEER, IN A SEMIPERMANENT CONDITION.

#### ITEM 253- PAVEMENT REPAIR (A)

AN ESTIMATED QUANTITY OF 1400 CU YDS OF ITEM 253-PAVEMENT REPAIR HAS BEEN CARRIED TO THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER. THIS OPERATION SHALL BE PERFORMED BEFORE PAVEMENT PLANING OF ROADWAY.



EXISTING DETERIORATED ASPHALT SHALL BE REMOVED TO A DEPTH OF 4-1/4" INCHES OR AS DIRECTED BY THE ENGINEER AND REPLACED WITH ITEM 301, ASPHALT CONCRETE BASE. THE 301 SHALL BE COMPACTED AS PER 401.15 AND IN APPROXIMATELY EQUAL LAYERS. DO NOT DISTURB ANY SOUND CONCRETE SURFACE. REMOVE ANY DETERIORATED CONCRETE AND REPLACE WITH ITEM 301 AS NOTED ABOVE. THE LOCATIONS AND SIZE OF THE REPAIRS SHALL BE DETERMINED BY THE ENGINEER.

#### **ITEM 254- PAVEMENT PLANING, ASPHALT CONCRETE**

THE PAVEMENT PLANING SHALL BE SCHEDULED TO BE COVERED BY THE SURFACE COURSE PRIOR TO REOPENING THE LANE TO TRAFFIC, EXCEPT THE CONTRACTOR IS PERMITTED TO MILL AHEAD 1000 FEET BEYOND THE PLACED SURFACE COURSE. THE MILLED AHEAD SURFACE SHALL BE COVERED BY THE SURFACE COURSE ASPHALT WITHIN 72 HOURS OF BEING OPEN TO TRAFFIC. ADDITIONALLY, THE MILLED AHEAD SURFACE SHALL NOT BE LOCATED WITHIN AN INTERSECTION OR RAMP. THE MILLED AHEAD SURFACE SHALL BE SMOOTH, FREE OF DEBRIS, AND FREE OF POTHOLES. A DISINCENTIVE IN THE AMOUNT OF \$1,500 SHALL BE ASSESSED FOR EACH DAY THE CONTRACTOR FAILS TO MEET ANY OF THESE REQUIREMENTS.

#### ENIVRONMENTAL NOTE

NO IN STREAM WORK IS PERMITTED FOR THIS PROJECT. SPECIFICALLY, NOINSTREAM WORK IS TO BE PERFORMED IN THE STREAM ON THE EAST SIDE OF HAFT RD, UNDER I-74. IF INSTREAM WORK BECOMES NECESSARY, PLEASE CONTACT KEITH SMITH, ODOT DISTRICT 8 ENVIRONMENTAL COORDINATOR AT 513-933-6590.

#### ITEM 621- RAISED PAVEMENT MARKER REMOVED/REPLACED

RPM'S SHALL BE INSTALLED ACCORDING TO SCD TC-65.10, TC-65.11 AND TC-73.20.

THE FOLLOWING RPM QUANTITIES ARE TO BE USED ON HAM IR 74 EB/WB S.L.M.11.16-18.00 AND HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM 621- RPM, 1-WAY (WHITE)	. 1198 EA
ITEM 621- RPM, 2-WAY (YELLOW/RED)	
ITEM 621- RPM, 2-WAY (WHITE/RED)	275 EA

#### ITEM 621- RAISED PAVEMENT MARKER REMOVED......... 1776 E

#### **GUARDRAIL INSTALLATION**

THIS PROJECT REQUIRES THE INSTALLATION OF NEW GUARDRAIL POSTS. SURVEY WORK HAS NOT BEEN PERFORMED EVERYWHERE ON THIS PROJECT, NOR HAVE THE UTILITY LOCATIONS BEEN CONFIRMED IN THE FIELD. IN ADDITION TO CMS 105.07. IF. DURING THE COURSE OF INSTALLING ANY NEW GUARDRAIL COMPONENT, IT IS DETERMINED THAT A UTILITY CONFLICT MAY RESULT, THE CONTRACTOR IS TO NOTIFY THE PROJECT ENGINEER IMMEDIATELY, UTILITIES ARE NOT TO BE RELOCATED AS A RESULT OF THIS OPERATION. ADJUSTMENTS TO THE PROPOSED GUARDRAIL WILL ACCOMMODATE THE EXISTING UTILITY. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING THE GUARDRAIL VIA MEANS THAT WOULD BE COMPLIANT WITH THE IMPACTED UTILITY'S SAFETY GUIDELINES AS WELL AS STILL MEETING ODOT'S DESIGN CRITERIA. ANY MINOR ADJUSTMENTS MADE TO THE PROPOSED GUARDRAIL INSTALLATIONS SHALL BE INCIDENTAL TO PAY ITEM 606.

#### CONNECTION BETWEEN EXISTING AND PROPOSED GUARDRAIL

WHEN IT IS NECESSARY TO SPLICE PROPOSED GUARDRAIL TO EXISTING GUARDRAIL, ONLY THE EXISTING GUARDRAIL SHALL BE CUT, DRILLED, OR PUNCHED. THE CONNECTION SHALL BE MADE USING A W-BEAM, BEAM SPLICE AS SHOWN IN AASHTO M 180-12, EXCEPT THE BEAM WASHERS ARE NOT TO BE USED. PAYMENT SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE RESPECTIVE GUARDRAIL ITEMS.

#### ITEM 606 - ANCHOR ASSEMBLY, MGS TYPE E

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE GUARDRAIL END TERMINALS FOR TYPE MGS GUARDRAIL AS LISTED ON ROADWAY ENGINEERING'S WEB PAGE UNDER ROADSIDE SAFETY DEVICES FOR APPROVED GUARDRAIL END TREATMENTS. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE FACE OF THE TYPE E IMPACT HEAD SHALL BE COVERED WITH REBOUNDABLE RETROFLECTIVE SHEETING, PER CMS 730.191

REFER TO THE MANUFACTURER'S INSTRUCTIONS REGARDING THE INSTALLATION OF, AND THE GRADING AROUND THE FOUNDATION TUBES AND GROUND STRUT. THE TOP OF ANY FOUNDATION TUBE SHOULD BE LESS THAN 4 INCHES ABOVE THE GROUND. THE PLACEMENT OF THE FOUNDATION TUBES SHOULD BE AN APPROPRIATE DEPTH BELOW THE LEVEL LINE IN ORDER TO MAINTAIN THE FINISHED GUARDRAIL HEIGHT OF 31 INCHES FROM THE EDGE OF THE SHOULDER.

ON-SITE GRADING IS REQUIRED IF THE TOP OF THE FOUNDATION TUBES OR TOP OF THE GROUND STRUT DOES PROJECT MORE THAN 4 INCHES ABOVE THE GROUND LINE.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, ANCHOR ASSEMBLY, MGS TYPE E, EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL ANCHOR ASSEMBLY SYSTEM, INCLUDING ALL RELATED TRANSITIONS, REFLECTIVE SHEETING, HARDWARE, GRADING, EMBANKMENT AND EXCAVATION NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

#### GUARDRAIL REPLACEMENT

NO HAZARD SHALL BE LEFT UNPROTECTED EXCEPT FOR THE ACTUAL TIME NECESSARY TO REMOVE THE EXISTING GUARDRAIL, PREPARE THE SITE, AND INSTALL THE NEW GUARDRAIL/BARRIER IN A CONTINUOUS OPERATION. THE REMOVAL OF ALL GUARDRAIL/BARRIER SHALL AT ALL TIMES BE AS DIRECTED BY THE ENGINEER. NO GUARDRAIL/BARRIER SHALL BE REMOVED UNTIL THE REPLACEMENT MATERIAL IS ON SITE, READY FOR INSTALLATION. FAILURE TO COMPLY WITH THIS REQUIREMENT SHALL BE DEEMED SUFFICIENT CAUSE TO ORDER WORK SUSPENDED UNTIL SUCH TIME AS THE ENGINEER IS ASSURED OF COMPLIANCE.

## ITEM 606 - IMPACT ATTENUATOR, TYPE 2 (UNIDIRECTIONAL OR BIDIRECTIONAL)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING THE PLAN SPECIFIED TYPE 2 IMPACT ATTENUATORS AS LISTED ON THE OFFICE OF ROADWAY ENGINEERING'S WEB PAGE (REFER TO THE POSTED SHOP DRAWINGS FOR THE MOST CURRENT APPROVED PRODUCT MODELS). WHEN BI-DIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, IMPACT ATTENUATOR, TYPE 2 (62 MPH), HAZARD WIDTH (69"), (UNIDIRECTIONAL OR BIDIRECTIONAL)], EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS/BACKSTOPS, TRANSITIONS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

#### WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

#### PROFILE AND ALIGNMENT

PLACE THE PROPOSED PAVEMENT TO FOLLOW THE ALIGNMENT AND PROFILE OF THE EXISTING PAVEMENT. UNLESS OTHERWISE NOTED IN THE PLANS.

#### **NESTING BIRDS**

ECOLOGICAL STUDIES IDENTIFIED SWALLOW NESTS ON THE STEEL SUPERSTRUCTURE AND STEEL PORTIONS OF THE PIERS ON THE HAM-74-11.16 L/R BRIDGES. THESE NESTS AND BIRD DROPPINGS MUST BE REMOVED FROM THE STRUCTURE PRIOR TO THE START OF ULTRA SONIC TESTING AND INSPECTION (UTI), CONCRETE BARRIER REHABILITATION AND/OR PAINTING OF THE STRUCTURAL STEEL.

IF CONSTRUCTION ACTIVITIES WILL OCCUR BETWEEN MAY 1 AND AUGUST 31 ON THIS STRUCTURE, INSPECT THE STRUCTURE FOR EVIDENCE OF AN ACTIVE BIRD NEST CONTAINING AN EGG OR CHICK PRIOR TO STARTING WORK. PROVIDE WRITTEN CONFIRMATION OF THE INSPECTION, INCLUDING A STATEMENT WHETHER AN ACTIVE NEST WAS FOUND, TO THE ENGINEER.

IF NO NESTS ARE ENCOUNTERED DURING THE INSPECTION, OR IF ONLY INACTIVE NESTS THAT DO NOT CONTAIN AN EGG OR CHICK ARE ENCOUNTERED, PROCEED WITH CONSTRUCTION ACTIVITIES. THE CONTRACTOR MAY REMOVE AND DESTROY INACTIVE NESTS. THE CONTRACTOR MAY INSTALL EXCLUSION MEASURES BETWEEN AUGUST 31 AND MAY 1 TO PREVENT MIGRATORY BIRDS FROM NESTING ON THE STRUCTURE, PROJECTS PERFORMING CONSTRUCTION ACTIVITIES BETWEEN THE DATES OF SEPTEMBER 1 AND APRIL 30 DO NOT REQUIRE AN INSPECTION FOR MIGRATORY BIRDS OR AVOIDANCE MEASURES.

IF AN ACTIVE NEST CONTAINING AN EGG OR CHICK IS ENCOUNTERED, AVOID IMPACTS TO THE NEST UNTIL ALL DEVELOPING BIRDS ARE ABLE TO INDEPENDENTLY FLY FROM THE NEST. IF AN ACTIVE NEST CONTAINING AN EGG OR CHICK CANNOT BE AVOIDED, CONTACT THE ENGINEER AT LEAST 4 WEEKS PRIOR DESTROYING AN ACTIVE NEST SO THE DEPARTMENT CAN OBTAIN A DEPREDATION PERMIT FROM THE U.S. FISH AND WILDLIFE SERVICE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS AND COMPLETING ALL TASKS RELATED TO OBTAINING THE DEPREDATION PERMIT EXCEPT FOR DIRECT COORDINATION WITH THE MIGRATORY BIRDREGIONAL PERMIT OFFICE. DO NOT PROCEED WITH ACTIVITIES THAT WILL IMPACT AN ACTIVE NEST UNTIL THE DEPARTMENT CONFIRMS THE DEPREDATION PERMIT IS RECEIVED.

#### CONCRETE TESTING

REFER TO STRUCTURE NOTES FOR CONCRETE TESTING REQUIREMENTS THAT SHALL APPLY TO ALL ROADWAY & STRUCTURE CONCRETE WORK.

#### **ASBESTOS ABATEMENT**

AN ASBESTOS SURVEY FOR SFN's 3115437, 3115429, 3108767, 3108732, 3108619, 3108589, 3108430, AND 3108465 SCHEDULED FOR RENOVATION WORK WAS CONDUCTED ON 8/30/2023 BY A LICENSED ASBESTOS HAZARD EVALUATION SPECIALIST. THE ASBESTOS SURVEY DID NOT IDENTIFY THE PRESENCE OF ANY ASBESTOS CONTAINING MATERIALS.

#### **ELECTRONIC SUBMISSION:**

THE CONTRACTOR SHALL SUBMIT ELECTRONICALLY TO OEPA A COMPLETED NOTIFICATION OF DEMOLITION & RENOVATION FORM (NDRF) AND APPLICABLE FEES ALONG WITH THE ASBESTOS SURVEY REPORT. THE COMPLETED NDRF MUST BE SUBMITTED TO OEPA AT LEAST 10 DAYS PRIOR TO ANY DEMOLITION AND RENOVATION ACTIVITY. THE CONTRACTOR IS RESPONSIBLE FOR RETAINING AN ELECTRONIC COPY OF THE NDRF (IN PDF FORM) FOR SUBMISSION TO THE DISTRICT ENVIRONMETNAL STAFF AND A ONE HARD COPY TO THE PROJECT ENGINEER.

(GO TO THE OEPA EBUSINESS CENTER AND SUBMIT THE DNRF AND PAYMENT ALONG WITH THE ASBESTOS SURVEY REPORT)

#### HARD COPY SUBMISSION:

THE CONTRACTOR MAY ELECT TO SUBMIT A HARD COPY OF THE COMPLETED NDRF AND PAYMENT ALONG WITH THE ASBESTOS SURVEY REPORT TO THE FOLLOWING:

ASBESTOS PROGRAM
OHIO EPA, DAPC
P.O. BOX 1049
COLUMBUS, OHIO 43216-1049
ASBESTOS PROGRAM
OHIO EPA, DAPC
50 W. TOWN ST., SUITE 700
COLUMBUS, OHIO 43215

IF THE CONTRACTOR ELECTS TO SUBMIT A HARD COPY TO OEPA THEY ARE RESPONSIBLE FOR RETAINING A HARD COPY OF THE NDRF FOR SUBMISSION TO THE DISTRICT ENVIRONMETNAL STAFF AND A ONE HARD COPY TO THE PROJECT ENGINEER.

#### BASIS OF PAYMENT

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE WORK NOTED ABOVE:

690E98400 ITEM SPECIAL - MISC.: WORK INVOLVING ASBESTOS

CONTAINING MATERIALS - LUMP SUM

DESIGN AGE



NCD
REVIEWER
JDO 9/20/23
PROJECT ID
88679

04 TOTAL 53

### 442 ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), PWL. 2025. AS PER PLAN

ALL REQUIREMENTS OF C&MS ITEM 442 APPLY EXCEPT AS SHOWN.

MAT DENSITY ACCEPTANCE - FOLLOW THE REQUIREMENTS OF 446 MAT DENSITY ACCEPTANCE, EXCEPT AS MODIFIED BELOW. OBTAIN 6-INCH DIAMETER CORES FOR EACH LOT. THE PWL CALCULATOR, LOCATED ON THE ODOT WEBSITE AT THE OFFICE OF CONSTRUCTION ADMINISTRATION, WILL BE USED TO DETERMINE THE LOT PWL AND THE LOT AASHTO PAY FACTORS.

THE DEPARTMENT WILL DETERMINE THE PAY FACTOR FOR EACH LOT CORED BY THE FOLLOWING TABLE.

LOWER SPECIFICATION LIMIT I	INTERMEDIATE WITH 3 JOINT CORES PAY FACTOR CRITERIA	PAY FACTOR (PF)
91%	AND PWL ≥90	PF =1 OR AASHTO PF WHICH
	IF 90 > PWL > 50	Aashto Pf
	IF PWL ≤=50	REMOVE AND REPLACE

## ITEM 632 DETECTOR LOOP, AS PER PLAN ITEM 632 LOOP DETECTOR TIE-IN, AS PER PLAN

PRIOR TO THE PLANNING OPERATION, THE LOCATION OF THE EXISTING LOOP DETECTORSSHALL BE REFERENCED SO THAT THE REPLACEMENT LOOPS CAN BE REINSTALLED AT THE PROPER LOCATIONS. THE NEW LOOP DETECTORS SHALL BE CONNECTED TO THE LEAD-IN CABLE WITH PROPER CONNECTION KITS AND TESTED TO MAKE CERTAIN THAT THEY ARE OPERATIONAL.

ALL STOP LINE INDUCTANCE DETECTOR LOOPS SHOWN IN THE PLANS SHALL BE POWERHEAD CONFIGURATION SHOWN ON TC-82.10. THE WIDTH SHALL BE AS SPECIFIED ON TC-82.10 AND THE LENGTH SHALL BE AS DIRECTED BY THE PROJECT ENGINEER. THE STOP LINE DETECTOR LOOPS SHALL NOT BE WIRED TO ANY OTHER LOOPS AND SHALL HAVE ITS OWN DETECTOR CHANNEL. THE LOCATION OF THESE LOOPS SHALL BE SUCH THAT THE POWERHEAD IS LOCATED AT THE STOP LINE, NOT PAST IT.

ALL DILEMMA ZONE INDUCTANCE DETECTOR LOOPS CALLED FOR IN THE PLANS SHALL BE ANGULAR DESIGN DETECTION (ADD) LOOP AS SHOWN ON TC-82.10. DIMENSIONS SHALL BE AS SPECIFIED ON TC-82.10.

 $\ensuremath{\mathsf{SYSTEM}}$  LOOPS SHALL BE AS DEPICTED IN THE PLANS.

WB IR 74 TO HARRISON AVE
WB IR 74 TO MONTANA RD
EB IR 74 TO NORTH BEND RD
2 EACH

ALL STOP LINE DETECTOR ZONES SHALL BE TESTED FOR A BICYCLETARGET AND ALL DILEMMA DETECTION ZONES SHALL BE TESTED FOR A MOTORCYCLE TARGET.

THE CONTRACTOR SHALL NOTIFY THE DISTRICT 8 TRAFFIC ENGINEER A MINIMUM OF 3 DAYS IN ADVANCE OF ANY LOOP DETECTOR INSTALLATIONS TO PERMIT TIME FOR LOOP LOCATION ADJUSTMENTS AND TO SPECIFY THE LENGTH OF THE LOOPS IF NEEDED.

THE FOLLOWING QUANTITIES OF DETECTOR LOOPS AND LOOP DETECTOR TIE-INS HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 632 DETECTOR LOOP, AS PER PLAN 6 EACH ITEM 632 LOOP DETECTOR TIE-IN, AS PER PLAN 6 EACH

#### SPEED MEASUREMENT MARKINGS

THE CONTRACTOR SHALL PLACE A SERIES OF SPEED MEASURE-MENT MARKINGS ON THE ROADWAY TO ESTABLISH AN AIR SPEED CHECK ZONE TO ASSIST IN THE ENFORCEMENT OF SPEED REGULATIONS WITHIN THE WORK ZONE. EACH SPEED MEASURE-MENT MARKING SHALL CONSIST OF ONE WHITE TRANSVERSE 24-INCH LINE MEASURED IN THE DIRECTION OF TRAVEL AND 4 FEET IN LENGTH. THE MARKINGS SHALL BE PLACED AT ONE-QUARTER MILE INTERVALS FOR A MINIMUM OF 1 MILE ALONG THE ROADWAY, AT LOCATIONS AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. SPEED MEASUREMENT MARKINGS SHOULD AVOID BEING LOCATED IN THE VICINITY OF A TAPER, SHIFT, CROSSOVER, ENTRANCE RAMP OR EXIT RAMP.

ON MULTILANE HIGHWAYS WITH SHOULDER WIDTHS OF AT LEAST 6 FEET, CENTER THE SPEED MEASUREMENT MARKING ENTIRELY ON THE SHOULDER. IF THE SHOULDER WIDTH IS BETWEEN 2 FEET AND 6 FEET, CENTER THE MARKING ON THE EDGE LINE. IF THE SHOULDER WIDTH IS LESS THAN 2 FEET, CENTER THE MARKING IN LANE IMMEDIATELY ADJACENT TO THE EDGE LINE. TO ASSURE VISIBILITY OF THE MARKINGS AND REDUCE PARALLAX ERRORS ON MULTI-LANE HIGHWAYS, FOR EACH DIRECTION UTILIZING AN AIR SPEED CHECK ZONE, A SET OF TWO MARKINGS (LEFT AND RIGHT SIDE) SHALL BE USED AT EACH ONE-QUARTER MILE INTERVAL.

ON TWO-LANE HIGHWAYS, ONE MARKING SHOULD BE USED AT EACH ONE-QUARTER MILE INTERVAL AND INSTALLED ACROSS THE CENTER LINE

THE MARKINGS SHALL BE LAID OUT BY A REGISTERED SURVEYOR. MEASURE EACH SET OF MARKINGS SEPARATELY TO ELIMINATE RADIAL DISTANCE ERRORS. A RECORD IS TO BE KEPT AND ONE ORIGINAL SIGNED AND SEALED DOCUMENT IS TO BE SENT TO THE DISTRICT TRAFFIC ENGINEER AND ONE COPY IS TO BE SENT TO THE DISTRICT CONSTRUCTION ENGINEER.

PAYMENT WILL BE FOR EACH 24-INCH-WIDE BY 4 FEET LONG MARKING AND SHALL INCLUDE THE PAVEMENT MARKING MATERIAL USED AND THE SURVEYING WORK. THE FOLLOWING QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY TO BE USED AS DIRECTED BY THE ENGINEER:

ITEM 614 SPEED MEASUREMENT MARKING, 642 TRAFFIC PAINT
\_\_22\_EACH
ITEM 644 SPEED MEASUREMENT MARKING, \_\_22\_EACH

WHEN CALLED FOR IN THE PLANS, PLACE AREA PATROLLED BY AIRCRAFT (D12-H15A) BLACK-ON-FLUORESCENT ORANGE SIGNS IN THE ADVANCED WORK ZONE AREA BETWEEN THE FIRST AND SECOND SIGNS IN THE SERIES AND REPEATED AT EACH ENTRANCE RAMP WITHIN THE AIR SPEED CHECK ZONE. PAYMENT FOR AIR SPEED CHECK ZONE RELATED SIGNS IS INCLUDED IN THE LUMP SUM BID PRICE FOR MAINTAINING TRAFFIC.

#### AIRWAY/HIGHWAY CLEARANCE FOR AIRPORTS AND HELIPORTS

THIS PROJECT HAS BEEN IDENTIFIED AS BEING WITHIN THE INFLUENCE AREA OF A PRIVATE-USE AIRPORT OR HELIPORT, NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT, AT MAXIMUM OPERATING HEIGHT, SHALL EXCEED A HEIGHT OF \_160\_\_ FT (GOOD SAMARITAN) AND 46 FT (MERCY HEALTH) IF ANY TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT WILL EXCEED THIS HEIGHT, COORDINATION WITH THE AIRPORT OWNER AND THE ODOT OFFICE OF AVIATION WILL BE NECESSARY PRIOR TO ERECTING SUCH TEMPORARY STRUCTURES OR OPERATING SUCH EQUIPMENT ON THE PROJECT. FOR PRIVATE USE AIRPORTS OR HELIPORTS. COORDINATE WITH THE AIRPORT OWNER AND THE ODOT OFFICE OF AVIATION. NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT SHALL EXCEED THE PERMISSIBLE HEIGHT, UNTIL COORDINATION IS MET AND DOCUMENTATION HAS BEEN FURNISHED TO THE PROJECT ENGINEER. IF COORDINATION IS NOT OBTAINED, THEN THE PROJECT ENGINEER WILL HAVE THE AUTHORITY TO PROVIDE RESTRICTIONS AS REQUIRED.

Good Samaritan Western Ridge 6949 Good Samaritan Drive Cincinnati, Ohio 45247 513-246-9800

Mercy Health West Hospital 3300 Mercy Health Blvd. Cincinnati, Ohio 45211 513-215-5000

#### ITEM 201, CLEARING AND GRUBBING, AS PER PLAN

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201 - CLEARING AND GRUBBING, AS PER PLAN.

REMOVE ANY TREES, BRUSH OR STUMPS NOT SPECIFICALLY MARKED FOR REMOVAL IF LOCATED UNDER OR WITHIN TEN FEET OF THE BRIDGE STRUCTURES. REMOVE BRUSH WITHIN THE LIMITS OF STATE RIGHT-OF-WAY. THE REMOVAL OF DEBRIS FROM AROUND THE ABUTMENTS AND/OR PIERS AS DIRECTED BY THE ENGINEER SHALL ALSO BE INCLUDED WITH THIS ITEM FOR PAYMENT. CONTRACTOR SHALL VERIFY POSITIVE DRAINAGE.

ALL PROVISIONS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING, AS PER PLAN.

DESIGN AGEN



DESIGNER
JED

REVIEWER
JDO 9/20/23

PROJECT ID

88679

05 TOTAL 53

# HAM-IR

#### ITEM 614 - MAINTAINING TRAFFIC

GENERAL: MAINTAIN ALL EXISTING LANES AT ALL TIMES. EXCEPT LANE CLOSURES ARE PERMITTED IN ACCORDANCE WITH THE LANE VALUE CONTRACT TABLE, BY USE OF THE EXISTING PAVEMENT AND THE COMPLETED PAVEMENT.

#### I-74 RESURFACING:

MAINTAIN A MINIMUM OF 1 LANE OF TRAFFIC IN EACH DIRECTION PER THE LANE VALUE CONTRACT TABLE.

MAINTAIN A MINIMUM OF 1 LANE OF TRAFFIC IN EACH DIRECTIONS. LANE CLOSURES ARE PERMITTED ACCORDING TO THE LANE VALUE CONTRACT TABLE AND THE MAINTENANCE OF TRAFFIC POLICY **EXCEPTION NOTE** 

PROVIDE PORTABLE BARRIER USING SHOULDER CLOSURES TO PROTECT REMOVED PORTIONS OF EXISTING PARAPET INCLUDING AT THE EXPANSION JOINTS. DURING THE WEEKEND LANE CLOSURES, PORTABLE BARRIER MAY BE RELOCATED INTO THE LANE FOR TRAFFIC PROTECTION AND THEN BACK TO THE SHOULDER BEFORE REOPENING THE LANE. THIS RELOCATION OF PORTABLE BARRIER FOR WEEKEND LANE CLOSURES IS NOT ITEMIZED AND SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614 MAINTAINING TRAFFIC.

IN GENERAL, MAINTAIN A MINIMUM OF 1 LANE OF TRAFFIC IN EACH DIRECTION PER THE LANE VALUE CONTRACT TABLE. TO PERFORM THE MEDIAN BARRIER UPGRADES, CLOSE ONE LANE IN EACH DIRECTION USING PORTABLE BARRIER AND PROVIDE A 480' SOUTH-BOUND LEFT TURN LANE; THIS LANE CLOSURE MAY REMAIN IN PLACE UP TO 3 WEEKS.

#### SHEPHERD CREEK:

MAINTAIN A MINIMUM OF ONE LANE OF TWO WAY TRAFFIC DURING WORKING HOURS.

MAINTAIN A MINIMUM OF ONE LANE OF TRAFFIC IN EACH DIRECTION PER THE LANE VALUE CONTRACT TABLE.

#### ITEM 614 - MAINTAINING TRAFFIC

MAINTAIN ALL EXISTING LANES AT ALL TIMES, EXCEPT LANE CLOSURES ARE PERMITTED IN ACCORDANCE WITH THE LANE VALUE CONTRACT TABLE, BY USE OF THE EXISTING PAVEMENT AND THE COMPLETED

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR SPECIAL EVENTS:

NEW YEAR'S (OBSERVED) TOTAL SOLAR ECLIPSE (4/8/24) THANKSGIVING

MEMORIAL DAY

FOURTH OF JULY (OBSERVED) LABOR DAY

CHRISTMAS (OBSERVED) (OTHER HOLIDAY OR SPECIAL EVENT) SOLOR ECLIPSE (4/8/24)

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR SPECIAL EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE

DAY OF HOLIDAY TIME ALL LANES OR SPECIAL EVENT MUST BE OPEN TO TRAFFIC

SUNDAY 12:00N FRIDAY THROUGH 6:00 AM MONDAY MONDAY 12:00N FRIDAY THROUGH 6:00 AM TUESDAY MONDAY (TOTAL SOLAR ECLIPSE)

12:00N MONDAY THROUGH 6:00 AM WEDNESDAY TUESDAY 12:00N MONDAY THROUGH 6:00 AM WEDNESDAY TUESDAY (GEN./REG. ELECTION)

5:00 AM TUESDAY THROUGH 12:00 AM WEDNESDAY WEDNESDAY 12:00N TUESDAY THROUGH 6:00 AM THURSDAY THURSDAY 12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY THURSDAY (THANKSGIVING ONLY)

6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY FRIDAY 12:00N THURSDAY THROUGH 6:00 AM MONDAY SATURDAY 12:00N FRIDAY THROUGH 6:00 AM MONDAY

DURING THE SAME PERIODS. MAINTAIN PEDESTRAIN ACCESS IF PEDESTRIAN ACCESS WAS PRESENT PRIOR TO CONSTRUCTION. INEWLY CONSTRUCTED LANE ADDITIONS, ONCE COMPLETED AND INITIALLY OPENED TO TRAFFIC. SHALL BE OPEN TO TRAFFIC DURING ALL SUBSEQUENT DESIGNATED HOLIDAYS AND SPECIAL EVENTS, AND RELATED PERIODS OF TIME, SPECIFIED ABOVE.]

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER THE LANE VALUE CONTRACT (PN 127).

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

NOTICE OF CLOSURE SIGNS (W20-H13) SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. [AT THE APPROVAL OF THE ENGINEER, PORTABLE CHANGEABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLATSHEET SIGN FOR CLOSURE DURATIONS OF LESS THAN 1 WEEK.]

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS, ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE. THE SIGNS MAY BE ERECTED ANYWHERE ON RAMPS AS LONG AS THEY ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS, THE SIGN SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING MOTORISTS.

NOTICE OF CLOSURE SIGN TIME TABLE SIGN DISPLAYED DURATION OF CLOSURE TO PUBLIC RAMP & >=2 WEEKS 14 CALENDAR DAYS PRIOR TO CLOSURE ROAD> 12 HOURS 7 CALENDAR DAYS & < 2 WEEKS PRIOR TO CLOSURE CLOSURES <= 12 HOURS 2 BUSINESS DAYS

PRIOR TO CLOSURE

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LAST GENERAL/REGULAR ELECTION DAY ((NOV) LINE OF THE W20-H13 SIGN LISTS A PHONE NUMBER WHICH A MOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS IS TO BE A SPECIFIC OFFICE WITHIN THE DISTRICT RATHER THAN THE GENERAL SWITCHBOARD NUMBER

> ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE

#### NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION

(HAULING.PERMITS@DOT.OHIO.GOV) AND THE DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

NOTIFICATION OF TRAFFIC RESTRICTIONS TIME TABLE

DURATION OF NOTICE DUE TO

CLOSURE PERMITS & PIO

RAMP & >= 2 WEEKS 21 CALENDAR DAYS ROAD CLOSURES PRIOR TO CLOSURE > 12 HOURS 14 CALENDAR DAYS

& < 2 WEEKS PRIOR TO CLOSURE <= 12 HOURS 4 CALENDAR DAYS PRIOR TO CLOSURE

LANE >= 2 WEEKS 14 CALENDAR DAYS CLOSURES & PRIOR TO CLOSURE RESTRICTIONS

> < 2 WEEKS 5 BUSINESS DAYS PRIOR TO CLOSURE

START OF N/A 14 CALENDAR DAYS CONSTRUCTION & PRIOR TO IMPLEMENTATION

TRAFFIC PATTERN CHANGES

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME

#### ITEM 614, WORK ZONE IMPACT ATTENUATOR FOR 24" WIDE HAZARDS (UNIDIRECTIONAL OR BIDIRECTIONAL)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING A NON-GATING IMPACT ATTENUATOR FURNISH AN IMPACT ATTENUATOR FROM THE OFFICE OF ROADWAY ENGINEERING'S APPROVED LIST FOR WORK ZONE IMPACT ATTENUATORS, FROM THE ROADWAY STANDARDS APPROVED PRODUCTS WEB PAGE.

INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS IN ACCORDANCE WITH THE MANUFACTURER'S **SPECIFICATIONS** 

THE CONTRACTOR SHALL REPAIR OR REPLACE A DAMAGED UNIT WITHIN 24 HOURS OF A DAMAGING IMPACT

WHEN BIDIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS. WHEN GATING IMPACT ATTENUATORS ARE DESIRED, THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE ENGINEER FOR ACCEPTANCE.

THE COST FOR THE ADDITIONAL BARRIER REQUIRED FOR A GATING IMPACT ATTENUATOR SHALL BE INCLUDED IN THE COST OF THE GATING IMPACT ATTENUATOR.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT AND MAINTAIN A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM. INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

#### DELINEATION OF PORTABLE AND PERMANENT BARRIER

BARRIER REFLECTORS AND OBJECT MARKERS SHALL BE INSTALLED ON ALL PORTABLE BARRIER (PB) USED FOR TRAFFIC CONTROL; AND, ON PERMANENT CONCRETE BARRIER (INCLUDING BRIDGE PARAPETS) LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE.

BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THE SPACING SHALL BE AS PER TRAFFIC SCD MT-101.70. OBJECT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614.03 AND SCD MT-101.70. WHEN THE PB CONTAINS GLARE SCREEN, ONE SET OF THREE VERTICAL STRIPES OF SHEETING SHALL BE CONSIDERED EQUIVALENT TO AN OBJECT MARKER, ONE-WAY.

[INCREASED BARRIER DELINEATION, AS SPECIFIED HEREIN, SHALL BE INSTALLED ON ALL PB AND PERMANENT CONCRETE BARRIER LOCATED WITHIN 5 FEET OF THE EDGE OF THE TRAVELED LANE UNDER EITHER OF THE FOLLOWING CONDITIONS: ALONG TAPERS AND TRANSITION AREAS; OR ALONG CURVES (OUTSIDE ONLY) WITH DEGREE OF CURVATURE GREATER THAN OR EQUAL TO 3 DEGREES.] [THE INCREASED BARRIER DELINEATION SHALL CONSIST OF EITHER DELINEATION PANELS OR THE TRIPLE STACKING OF

[DELINEATION PANELS SHALL CONSIST OF PANELS OF DELINEATION, APPROXIMATELY 34 INCHES LONG AND 6 INCHES WIDE AND SHALL BE "CRIMPED." PANELS SHALL BE INSTALLED AND SPACED PER TRAFFIC SCD MT-101.70.]

[TRIPLE-STACKED BARRIER REFLECTORS SHALL CONSIST OF ALIGNING THREE BARRIER REFLECTORS VERTICALLY, AT LOCATIONS WHERE A SINGLE BARRIER REFLECTOR WOULD BE OTHERWISE ATTACHED. THERE SHALL BE NO OPEN SPACE BETWEEN THE ADJACENT BARRIER REFLECTORS. THE TRIPLE-STACKED BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THEY SHALL BE SPACED AND ALIGNED PER TRAFFIC SCD MT-101.70.1

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE PLANS AND CARRIED TO THE GENERAL SUMMARY:

ITEM 614, BARRIER REFLECTOR, TYPE 1 ONE-WAY 104 EACH

ITEM 614, OBJECT MARKER, \_ONE-WAY

WORK ZONE BARRIER REFLECTORS.]

104 EACH

PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, INCIDENTALS AND EQUIPMENT NECESSARY FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING EACH OF THE ABOVE ITEMS.

[ALONG RUNS OF INCREASED BARRIER DELINEATION WHERE THIS ITEM IS PROVIDED. THE QUANTITY SHALL BE MEASURED AS THE ENTIRE LENGTH OF THE RUN OF INCREASED BARRIER DELINEATION, INCLUDING THE SPACES BETWEEN THE INDIVIDUAL DELINEATION PANELS OR STACKS OF BARRIER REFLECTORS.]

FLOODLIGHTING OF THE WORK SITE FOR OPERATIONS CONDUCTED DURING NIGHTTIME PERIODS SHALL BE ACCOMPLISHED SO THAT THE LIGHTS DO NOT CAUSE GLARE TO THE DRIVERS ON THE ROADWAY. TO ENSURE THE ADEQUACY OF THE FLOODLIGHT PLACEMENT. THE CONTRACTOR AND THE ENGINEER SHALL DRIVE THROUGH THE WORK SITE EACH NIGHT WHEN THE LIGHTING IS IN PLACE AND OPERATIVE PRIOR TO COMMENCING ANY WORK. IF GLARE IS DETECTED, THE LIGHT PLACEMENT AND SHIELDING SHALL BE ADJUSTED TO THE SATISFACTION OF THE ENGINEER BEFORE WORK PROCEEDS.

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614. MAINTAINING TRAFFIC.



NCD SK 9/20/23

88679 06 53

#### WORK ZONE SPEED ZONES (WZSZS)

THE FOLLOWING WORK ZONE SPEED ZONE (WZSZ) SPEED LIMIT REVISION(S) HAVE BEEN APPROVED FOR USE ON THIS PROJECT WHEN WORK ZONE CONDITIONS AND FACTORS ARE MET AS DESCRIBED BELOW:

WZSZ REVISION NUMBER(S) COUNTY-ROUTE-SECTION(S) DIRECTION(S) WZ- 45122 HAM-74 EB/WB

POTENTIAL WZSZ LOCATIONS SHALL HAVE AN ORIGINAL (PRE-CONSTRUCTION) POSTED SPEED LIMIT OF 55 MPH OR GREATER, A QUALIFYING WORK ZONE CONDITION OF AT LEAST 0.5 MILE IN LENGTH, AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS, AND A WORK ZONE CONDITION IN PLACE THAT REDUCES THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS (I.E., LANE CLOSURE, LANE SHIFT, CROSSOVER, CONTRAFLOW AND/OR SHOULDER CLOSURE). THE LENGTH OF THE WORK ZONE CONDITION IS MEASURED FROM THE BEGINNING OF THE TAPER FOR THE SUBJECT WORK ZONE CONDITION IMPACTING THE TRAVEL LANES AND/OR SHOULDER TO THE END OF THE DOWNSTREAM TAPER, WHERE DRIVERS ARE RETURNED TO TYPICAL ALIGNMENT. AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS IS REQUIRED TO BALANCE THE ADDITIONAL EXPOSURE CREATED BY INSTALLING AND REMOVING WZSZ SIGNING WITH THE TIME NEEDED TO COMPLETE THE WORK.

IF THE WORK ZONE MEETS THESE MINIMUM CRITERIA. IT SHALL BE ANALYZED FURTHER USING TABLE 1 BELOW TO DETERMINE IF AND WHEN IT QUALIFIES FOR A SPEED LIMIT REDUCTION. DEPENDING ON THE ORIGINAL POSTED SPEED LIMIT, THE TYPE OF TEMPORARY TRAFFIC CONTROL USED, AND WHETHER OR NOT WORKERS ARE PRESENT, A WARRANTED WZSZ WILL VARY IN THE APPROVED SPEED LIMIT TO BE POSTED OVER TIME.

C&MS ITEM 614, PARAGRAPH 614.02(B), INDICATES THAT TWO DIRECTIONS OF A DIVIDED HIGHWAY ARE CONSIDERED SEPARATE HIGHWAY SECTIONS. THEREFORE, IF THE WORK ON A MULTI-LANE DIVIDED HIGHWAY IS LIMITED TO ONLY ONE DIRECTION, A SPEED LIMIT REDUCTION IN THE DIRECTION OF THE WORK DOES NOT AUTOMATICALLY CONSTITUTE A SPEED LIMIT REDUCTION IN THE OPPOSITE DIRECTION. EACH DIRECTION SHALL BE ANALYZED INDEPENDENTLY FROM EACH OTHER.

ALL WZSZS FLUCTUATE BETWEEN TWO APPROVED REDUCED SPEED LIMITS OR BETWEEN AN APPROVED REDUCED SPEED LIMIT AND THE ORIGINAL POSTED SPEED LIMIT. ONLY ONE OF TWO SIGNING STRATEGIES SHALL BE USED TO IMPLEMENT A

WZSZS USING DSL SIGN ASSEMBLIES SHALL BE IN ACCORDANCE WITH THIS NOTE, APPROVED LIST, SUPPLEMENTAL SPECIFICATIONS (SS) 808 AND 908, AND TRAFFIC SCD MT-104.10.

[WZSZS USING TEMPORARY FLATSHEET SPEED LIMIT SIGNS SHALL BE IN ACCORDANCE WITH THIS NOTE AND SCD MT-104 10. ADDITIONALLY PAYMENT MAY BE REMOVED. OR A DISINCENTIVE APPLIED, FOR WZSZS USING TEMPORARY FLATSHEET SPEED LIMIT SIGNS THE SAME AS DESCRIBED IN THE MOST RECENT PUBLICATION OF SS 808 IN REGARDS TO WZSZS USING DSL SIGN ASSEMBLIES (SEE SS 808.06 PARAGRAPHS 4 THROUGH 7, INCLUDING TABLE 1).]

ONLY ONE WARRANTED SPEED LIMIT APPLIES AT ANY ONE TIME: SPEED LIMIT REDUCTIONS ARE NOT CUMULATIVE. WZSZS SHALL NOT BE USED FOR MOVING/MOBILE ACTIVITIES, AS DEFINED IN OMUTCD PART 6

WHEN LOOKING UP THE WARRANTED WORK ZONE SPEED LIMITS, ALWAYS USE THE ORIGINAL PRECONSTRUCTION POSTED SPEED LIMIT. DO NOT USE A PRIOR OR CURRENT WORK ZONE SPEED LIMIT AS A LOOK UP VALUE IN THE TABLE. POSITIVE PROTECTION IS GENERALLY REGARDED AS PORTABLE BARRIER OR OTHER RIGID BARRIER IN USE ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION, WITHOUT POSITIVE PROTECTION IS GENERALLY REGARDED AS USING DRUMS, CONES, SHADOW VEHICLE, ETC., ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WORKERS ARE CONSIDERED AS BEING PRESENT WHEN ON-SITE, WORKING WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION WHEN THE WORK ZONE CONDITION REDUCING THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS IS REMOVED. THE SPEED LIMIT DISPLAYED SHALL RETURN TO THE ORIGINAL POSTED SPEED LIMIT.

TABLE 1: WARRANTED WORK ZONE SPEED LIMITS (MPH) FOR WORK ZONES ON HIGH-SPEED (55 MPH OR GREATER) MULTI-LANE HIGHWAYS

	WITH POSIT	WITHOUT PROTECT	POSITIVE ION	
ORGINAL	WORKERS	WORKERS NOT	WORKERS	WORKERS NO
POSTED	PRESENT	PRESENT	PRESENT	PRESENT
SPEED				
LIMIT				
70	60	65	55	65
65	55	60	50	60
60	55	60	50	60
55	50	55	45	55

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY

[ITEM 808, DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY 6 SIGN MNTH [ASSUMING 8 DSL SIGN ASSEMBLY(IES) FOR 6 MONTH(S)]

## ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGNS, AS

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND REMOVE, WHEN NO LONGER NEEDED, A CHANGEABLE MESSAGE SIGN. THE SIGN SHALL BE OF A TYPE SHOWN ON A LIST OF APPROVED PCMS UNITS AVAILABLE ON THE OFFICE OF MATERIALS MANAGEMENT WEB PAGE. THE LIST CONTAINS CLASS A AND B UNITS WITH MINIMUM LEGIBILITY DISTANCES OF 800 FEET AND 650 FEET, RESPECTIVELY.

FACH SIGN SHALL BE TRAILER-MOUNTED AND FOUIPPED WITH A FUNCTIONAL DIMMING MECHANISM, TO DIM THE SIGN DURING DARKNESS, AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE OF BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. THE PCMS SHALL BE DELINEATED IN ACCORDANCE WITH C&MS 614.03.

MAINTENANCE AND ALL ACTIVATION OF

THE SIGNS BY THE CONTRACTOR SHALL BE AS DIRECTED BY THE ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE ENGINEER, RELOCATE THE PCMS TO IMPROVE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS SHALL BE TURNED OFF. ADDITIONALLY, WHEN NOT IN USE FOR EXTENDED PERIODS OF TIME, THE PCMS SHALL BE TURNED AWAY FROM ALL TRAFFIC.

THE ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ODOT PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT, AND TO REVISE SIGN MESSAGES. IF NECESSARY.

ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE ENGINEER. A LIST OF ALL REQUIRED PRE-PROGRAMMED MESSAGES WILL BE GIVEN TO THE CONTRACTOR AT THE PROJECT PRECONSTRUCTION CONFERENCE. THE SIGN SHALL HAVE THE CAPABILITY TO STORE UP TO 99 MESSAGES. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS SHALL NOT SURFACE COURSE BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. THREE-LINE PRESENTATION FORMATS WITH UP TO SIX MESSAGE PHASES SHALL BE SUPPORTED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ AT LEAST TWICE.

THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DEACTIVATED OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.

(THE PCMS SHALL CONTAIN A CELLULAR TELEPHONE DATA LINK WHICH WILL (IN ACTIVE CELLULAR PHONE AREAS) ALLOW REMOTE SIGN ACTIVATION, MESSAGE CHANGES, MESSAGE ADDITIONS AND REVISIONS TO TIME OF DAY PROGRAMS. THE SYSTEM SHALL ALSO PERMIT VERIFICATION OF CURRENT AND PROGRAMMED MESSAGES. ONE REMOTE DATA INPUT DEVICE (LAPTOP COMPUTER PLUS MODEM OR EQUIVALENT) SHALL BE FURNISHED FOR USE BY THE DISTRICT TRAFFIC ENGINEER, OR EQUIVALENT, AND SHALL BE INSURED AGAINST THEFT.) THE PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF C&MS 614.07. THE CONTRACTOR SHALL, PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS, WITH AN AUTHORIZED SERVICE THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED AGENT FOR THE PCMS, TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT IN THE SIGN ENGINEER FOR THE MAINTENANCE OF TRAFFIC. BEING OUT OF SERVICE FOR MORE THAN 12 HOURS, INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL ITEM 622, PORTABLE BARRIER, UNANCHORED TRAFFIC. THE ENTIRE COST TO CONTROL TRAFFIC, ACCRUED BY THE DEPARTMENT DUE TO THE CONTRACTOR'S NONCOMPLIANCE, WILL BE DEDUCTED FROM MONEYS DUE, OR TO BECOME DUE THE CONTRACTOR ON HIS CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24-HOUR-PER-DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES WHEN THE PLAN REQUIRES THEIR USE

PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.

ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN 14 SIGN MONTH (ASSUMING 2 PCMS SIGN(S) FOR 7 MONTH(S)

#### ITEM 614- WORK ZONE MARKINGS

THE CONTRACTOR SHALL PLACE WORK ZONE PAVEMENT MARKINGS UPON COMPLETION OF THE ASPHALT INTERMEDIATE AND SURFACE COURSE PRIOR TO OPENING THE ROADWAY TO TRAFFIC

THE FOLLOWING ESTIMATED QUANITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT LOCATIONS IDENTIFIED BY THE ENGINEER FOR WORK ZONE PAVEMENT MARKINGS PER THE REQUIREMENTS OF PER C&MS 614.11.

TEM 614-WORK ZONE EDGE LINE 6", CLASS I, 807 PAINT -	32.26 MILES
TEM 614-WORK ZONE LANE LINE, CLASS I, 807 PAINT -	17 MILES
TEM 614-WORK ZONE STOP LINE, CLASS III, 642 PAINT -	144 FEET
TEM 614-WORK ZONE CROSSWALK LINE, CLASS III, 642 PAINT -	418 FEET
TEM 614-WORK ZONE CHANNELIZING LINE CLASS I, 807 PAINT -	9952 FEET

ITEM 614-WORK ZONE WORD ON PAVEMENT 96" CLASS III, 642 PAINT - 1 EACH ITEM 614-WORK ZONE DOTTED LINE, CLASS I, 807 PAINT -4076 FEET ITEM 614-WORK ZONE ARROW, CLASS III, 642 PAINT -44 EACH

#### SURFACE COURSE FOR BRIDGES

0.58 MILES ITEM 614-WORK ZONE EDGE LINE 6", CLASS I, 807 PAINT -ITEM 614-WORK ZONE LANE LINE, CLASS I, 807 PAINT -0.29 MILES 572 FEET ITEM 614-WORK ZONE CHANNELIZING LINE CLASS III, 642 PAINT -

#### HARRISON RD WORK ZONE MARKINGS

ITEM 614-WORK ZONE ARROW, CLASS I, 740.06, TYPE I 6 EACH ITEM 614-WORK ZONE EDGE LINE, CLASS I,6", 740.06, TYPE I -0.29 MILES ITEM 614-WORK ZONE CHANNELIZING LINE, CLASS I, 8", 740.06, TYPE I 480 FEET

#### ITEM 614, MAINTAINING TRAFFIC (ESTIMATED QUANTITIES)

IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE

ITEM 614. WORK ZONE IMPACT ATTENUATOR. 11 EACH



NCD SK 9/20/23 88679

07 53

HAM-IR

## APPROVED MAINTENANCE OF TRAFFIC (MOT) POLICY EXCEPTION(S)

PORTIONS OF THE MOT PLANS AS DESCRIBED BELOW HAVE APPROVED MOT EXCEPTION(S) PER TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)).

#### APPROVED MOT EXCEPTION(S) INCLUDE:

THE CONTRACTOR IS PERMITTED 4 WEEKEND LANE CLOSURES IN THE EASTBOUND DIRECTION AND 4 WEEKEND LANE CLOSURES IN THE WESTBOUND DIRECTION TO COMPLETE THE EXPANSION JOINT REPLACEMENT. THESE WEEKEND LANE CLOSURES MAY OCCUR IN THE SAME DIRECTION AT THE SAME TIME; IT IS NOT REQUIRED. EXTRA ADVANCED WARNING SIGNING AT THE 3 MILE CLUSTER AND WZQDWS SHALL BE PROVIDED IN EACH DIRECTION DURING THE WEEKEND LANE CLOSURE.

•WESTBOUND I-74: THE WEEKEND LANE CLOSURE WILL BEGIN FRIDAY NIGHT AT 7 PM AND REOPEN MONDAY MORNING BY 9 AM. •EASTBOUND I-74: THE WEEKEND LANE CLOSURE WILL BEGIN FRIDAY NIGHT AT 7 PM AND REOPEN MONDAY MORNING BY 6 AM.

A MAINTENANCE OF TRAFFIC MEETING SHALL BE HELD A MINIMUM OF [\_30\_] CALENDAR DAYS PRIOR TO IMPLEMENTATION OF EACH APPROVED MOT EXCEPTION. THIS MEETING SHALL INCLUDE THE DISTRICT WORK ZONE TRAFFIC MANAGER AND AS WELL AS THE CONTRACTOR, WORKSITE TRAFFIC SUPERVISOR (WTS) AND ANY SUBCONTRACTORS INVOLVED WITH TEMPORARY TRAFFIC CONTROL.

IN ADDITION TO ANY NOTIFICATIONS REQUIRED IN OTHER NOTES, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER AT LEAST 3 BUSINESS DAYS IN ADVANCE OF IMPLEMENTATION OF THE APPROVED MOT EXCEPTION(S) REFERENCED ABOVE SO THAT THE PROJECT ENGINEER CAN SEND EMAIL NOTIFICATION TO THE OFFICE OF ROADWAY ENGINEERING, STATEWIDE TMC, DWZTM AND SPECIAL HAULING PERMITS AT LEAST 2 BUSINESS DAYS IN ADVANCE OF THE IMPLEMENTATION OF THE APPROVED MOT EXCEPTION(S) REFERENCED ABOVE. REFERENCE "EXCEPTION REQUEST APPROVAL DATED [8/23/2023] FOR PID [PID 88679]" IN THE NOTIFICATION AND OTHER CORRESPONDENCE.

ANY CHANGES TO THE MOT THAT IMPACT THE PREVIOUSLY APPROVED MOT EXCEPTION(S) LISTED ABOVE SHALL BE APPROVED IN WRITING BY THE MOT EXCEPTION COMMITTEE (MOTEC). IN THE EVENT THAT SUCH CHANGES ARE PROPOSED, THE REQUEST SHALL BE COORDINATED THROUGH THE DISTRICT WORK ZONE TRAFFIC MANAGER (DWZTM) A MINIMUM OF 30 CALENDAR DAYS PRIOR TO THE DESIRED IMPLEMENTATION DATE. IF THE DISTRICT AGREES WITH THE PROPOSED CHANGES THE DWZTM SHALL SEEK APPROVAL FROM THE MOTEC. IN THE EVENT THE PROPOSED CHANGES ARE APPROVED IN WRITING, THE CLOSURES ARE STILL SUBJECT TO NOTIFICATION REQUIREMENTS WITHIN THIS NOTE PRIOR TO IMPLEMENTATION.

#### VERTICAL CLEARANCE

ANY WORK (FALSEWORK, TRAFFIC PROTECTION, CONTAINMENT, ETC.) OVER LIVE TRAFFIC BY THE CONTRACTOR THAT REDUCES THE EXISTING VERTICAL CLEARANCE IS PROHIBITED UNLESS 30 DAYS ADVANCED NOTICE IS PROVIDED WITH NEW PROPOSED VERTICAL CLEARANCES, THE CONTRACTOR SHALL PROVIDE FIELD MEASURE-MENTS BEFORE ALLOWING TRAFFIC UNDERNEATH. IF ANY WORK IS TO OCCUR BELOW 14'-6", THEN SIGNS ON THE STRUCTURE AND ADVANCE WARNING SIGNS SHALL BE INSTALLED A MINIMUM OF 2 WEEKS PRIOR TO PERFORMING SUCH WORK. SIGNING SHALL BE IN ACCORDANCE WITH THE "OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" (OMUTCD) AND THE OHIO "TRAFFIC ENGINEERING MANUAL" (TEM). NO WORK OVER TRAFFIC SHALL OCCUR WITH A VERTICAL CLEARANCE LESS THAN 14'-0". LOWERING THE VERTICAL CLEARANCE DURING CONSTRUCTION IS CONSIDERED THE CONTRACTOR'S MEANS AND METHODS OF ACCOMPLISHING THE WORK, AND THEREFORE THE STATE IS NOT RESPONSIBLE FOR ANY DAMAGE FROM VEHICULAR IMPACTS THAT MAY RESULT AS PER 107.10."

#### **EXTRA ADVANCE WARNING SIGNS (NOTE A)**

AN EXTRA ADVANCE WARNING SIGN GROUP CONSISTS OF TWO W20-1 (ROAD WORK AHEAD) SIGNS, TWO W20-5 (RIGHT/LEFT LANE CLOSED AHEAD) SIGNS WITH W16-3A DISTANCE PLATES, AND TWO W3-H7 (WATCH FOR STOPPED TRAFFIC) SIGNS AND REQUIRED WARNING LIGHTS.

THE CONTRACTOR SHALL PROVIDE, ERECT, MAINTAIN AND REMOVE EXTRA ADVANCE WARNING SIGN GROUPS AS SHOWN ON TRAFFIC SCD MT-95.50 AT THE FOLLOWING DISTANCES IN ADVANCE OF THE LANE TAPERS WITH THE APPROPRIATE W16-3A DISTANCE PLATES:

- 1) EB 74 AT HAM-IR 74-11.16 3 MILES.
- 2) WB 74 AT HAM-IR 74-11.16

[THE CONTRACTOR SHALL HAVE AN ADDITIONAL EXTRA ADVANCE WARNING SIGN GROUP (6 SIGNS AND 2 DISTANCE PLATES) AVAILABLE FOR USE WHEN DIRECTED BY THE ENGINEER. THE DISTANCE PLATES FOR THIS GROUP SHALL BE ABLE TO BE MODIFIED IN THE FIELD TO SHOW APPROPRIATE WHOLE MILES TO THE LANE TAPER.]

PAYMENT FOR PROVIDING, ERECTING, MAINTAINING AND REMOVING EXTRA ADVANCE WARNING SIGN GROUPS SHALL BE INCLUDED IN THE LUMP SUM BID FOR ITEM 614, MAINTAINING TRAFFIC.

#### **ACCESS MANAGEMENT FOR DAILY/NIGHTLY WORK OPERATIONS**

ACCESS MANAGEMENT IS PART OF THE CONTRACTOR'S MEANS AND METHODS. IT IS ANTICIPATED THAT EQUIPMENT WILL BE STORED WITHIN THE RIGHT-OF-WAY AT A LOCATION(S) DETERMINED BY THE CONTRACTOR.

IF IT IS NECESSARY TO CROSS OPEN LANES OF TRAVEL, MT-99.60 IS THE GOVERNING STANDARD AND SHALL BE PERFORMED BETWEEN MIDNIGHT AND 5:00 AM. REMOVE, TURN, OR COVER ALL SIGNS USED IN THE SHORT-DURATION CLOSURE IF THE NEXT SHORT-DURATION CLOSURE WILL OCCUR MORE THAN 2 HOURS LATER. THIS INCLUDES TURNING OFF OR REVISING THE MESSAGE ON THE PORTABLE CHANGEABLE MESSAGE SIGN.

ALL COSTS ASSOCIATED WITH ACCESS MANAGEMENT INCLUDING LAW ENFORCEMENT OFFICERS AND PORTABLE CHANGEABLE MESSAGE SIGNS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC.

## ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED.

IN ADDITION TO THE REQUIREMENTS OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.

DURING A TRAFFIC SIGNAL INSTALLATION WHEN IMPACTING THE NORMAL FUNCTION OF THE SIGNAL OR THE FLOW OF TRAFFIC, OR WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT).

IN ADDITION TO THE REQUIREMENT OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHOULD BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS AS APPROVED BY THE ENGINEER:

FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES/SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP).

FOR OPERATIONS WITHOUT POSITIVE PROTECTION
OCCURRING WITHIN 10 FEET OF AN OPEN TRAVELED LANE
THAT MEET ALL OF THE FOLLOWING CRITERIA:

ON A MULTI-LANE DIVIDED INTERSTATE, OTHER FREEWAY OR EXPRESSWAY; AND AN AUTHORIZED SPEED LIMIT OF 45 MPH OR GREATER TAND.

AADT OF 50,000 (OR AADT OF 30,000 WITH 25% OR HIGHER PERCENT TRUCKS)

"WITHOUT POSITIVE PROTECTION" MEANS USE OF DRUMS, CONES, SHADOW VEHICLE, ETC, WITHOUT PROTECTION FROM PORTABLE BARRIER OR OTHER RIGID BARRIER ALONG THE WORK AREA. THIS PHRASE DOES NOT APPLY TO CASES WHERE POSITIVE PROTECTION IS REQUIRED. MOBILE OPERATIONS ARE REGARDED AS "WITHOUT POSITIVE PROTECTION". FOR WORK ZONES USING A COMBINATION OF BARRIER AND TEMPORARY TRAFFIC CONTROL DEVICES (CONES, DRUMS, ETC), THE DESIGNATION SHALL BE BASED UPON THE TYPE OF DEVICES USED IN THE AREA THAT WORKERS ARE LOCATED.

IF MULTIPLE ACTIVE LOCALIZED QUALIFYING WORK AREAS OCCUR WITHOUT POSITIVE PROTECTION, PER MAINLINE TRAFFIC DIRECTION, PROVIDE A UNIFORMED LEO AND OFFICIAL PATROL CAR IN ADVANCE OF:

THE FIRST ACTIVE WORK AREA THAT DRIVERS WILL ENCOUNTER: OR

THE ACTIVE WORK AREA LATERALLY CLOSEST TO THE OPEN TRAVELED LANE; OR

OTHER LOCATION AS APPROVED BY THE ENGINEER.

THE UNIFORMED LEO AND OFFICIAL PATROL CAR MAY RELOCATE AMONG THE LISTED LOCATIONS AS APPROPRIATE AS THE OPERATIONS PROCEED IN THE LOCALIZED QUALIFYING WORK AREAS.

IN GENERAL, LEOS SHOULD BE POSITIONED IN ADVANCE OF AND ON THE SAME SIDE AS THE LANE RESTRICTION (OR AT THE POINT OF ROAD CLOSURE), AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH SIGNALIZED INTERSECTIONS IN WORK

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL
RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE
TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS
ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE
MOTORIST IS APPROPRIATE.

THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR.
THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE
SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES
AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH
RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL
HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT,
AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE
TWO PARTIES.

ENSURE PROVIDED LEOS HAVE BEEN TRAINED APPROPRIATE TO THE JOB DECISIONS THEY ARE REQUIRED TO MAKE WHILE ON THE PROJECT, IN ACCORDANCE WITH C&MS 614.03.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE THAT SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC
MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT
PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT
OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING
ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL
SUMMARY

## ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE \_\_750\_ HOURS

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE)
INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES
OF A LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR
ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR
FOR ASSISTANCE.

#### WORK ZONE QUEUE DETECTION WARNING SYSTEM

THE CONTRACTOR SHALL FURNISH, INSTALL, AND MAINTAIN AN APPROVED WORK ZONE QUEUE DETECTION WARNING SYSTEM (WZQDWS) AS PER SUPPLEMENTAL SPECIFICATION 896.

IT IS EXPECTED THAT WZQDWS DEVICES LOCATIONS WILL VARY BASED ON PLANNED OR UNPLANNED PHASE AND TRAFFIC PATTERN CHANGES. PLACEMENT, OPERATION, MAINTENANCE AND ALL ACTIVATION OF THE DEVICES BY THE CONTRACTOR SHALL BE DIRECTED BY THE FINGINFER

THE FOLLOWING TRAFFIC SENSOR THRESHOLDS AND PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS) MESSAGES SHALL BE USED:

GREATER THAN OR EQUAL TO 50 MPH - USE FOUR CORNER FLASHING CAUTION MODE BETWEEN 50 MPH AND 25 MPH - TRAFFIC AHEAD XX MPH / SLOW DOWN BELOW OR EQUAL TO 25 MPH - TRAFFIC AHEAD XX MPH / PREPARE TO STOP

FOUR CORNER FLASHING CAUTION MODE SHALL CONSIST OF THE USE OF ONE ASTERISK IN EACH CORNER OF THE PCMS DISPLAY (4 TOTAL ASTERISKS).

XX SHALL BE ROUNDED UP TO THE NEAREST MULTIPLE OF 5 MPH MINUS 1. OCCUPANCY MAY BE DIRECTED TO BE USED BASED ON CERTAIN TRAFFIC CONDITIONS AND SCENARIOS. ODOT WILL DIRECT THE CONTRACTOR OF THE THRESHOLDS TO BE USED FOR THOSE AREAS WHERE OCCUPANCY IS DIRECTED TO BE USED.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 896, PORTABLE NON-INTRUSIVE TRAFFIC SENSOR.

CLASS \_\_2\_\_ SIGN MONTH ASSUMING

\_\_8\_\_ SENSOR(S) FOR \_\_2\_\_ MONTH(S)

ITEM 896, PORTABLE CHANGEABLE MESSAGE SIGN, AS
PER PLAN \_\_2 \_\_ SIGN MONTH ASSUMING
\_\_2 \_\_ PCMS SIGN(S) FOR \_\_2 \_\_ MONTH(S)

BEGION MOEN



DESIGNER
JED

REVIEWER
SK 9/20/23

PROJECT ID
88679

SHEET TOTAL

PERMITTED LANE CLOSURE TIMES SHORT TERM LANE CLOSURES ARE THOSE WHICH ARE PERMITTED BY THE PERMITTED LANE CLOSURE NOTE. THESE TIMES SHALL NOT BE REVISED WITHOUT PRIOR APPROVAL FROM THE DISTRICT 8 WORK ZONE TRAFFIC CONTROL ENGINEER. SHORT TERM LANE CLOSURES SHALL ONLY BE IMPLEMENTED WHEN WORK IS BEING CONTINUOUSLY PERFORMED IN THE LANE. THE CLOSURE SHALL BE REMOVED AS SOON AS POSSIBLE AFTER WORK HAS STOPPED. PERMITTED LANE CLOSURES SHALL ONLY BE ALLOWED DURING THE TIMES SPECIFIED IN THE LANE VALUE CONTRACT TABLE INCLUDED IN THESE PLANS. NO LANE OR SHOULDER CLOSURE SHALL BE IN PLACE WHEN NO WORK IS BEING PERFORMED.

#### LANE VALUE CONTRACT TABLE

DESCRIPTION OF CRITICAL LANE/RAMP TO BE MAINTAINED		RESTRIC TIME PE		TIME UNIT	DISINCENTIVE \$ PER TIME UNIT PER LANE			
		M-F S-S 1 MINUTE						
I-74: ALL LANES OPEN TO TRAFFIC	ЕВ	6 AM TO 7 PM	9 AM TO 7 PM		\$315			
	WB	9 AM TO 8 PM	11 AM TO 7 PM		,			
I-74: ALL RAMPS OPEN TO TRAFFIC		5 AM TO	10 PM	1 MINUTE	\$315			
HARRISON AVENUE;		M-F	S-S	1 MINUTE				
ALL LANES OPEN TO TRAFFIC	NB	3 PM TO 7 PM	NO RESTRICTION		\$315			
	SB	2 PM TO 7 PM	NO RESTRICTION		ψοτο			
HAFT ROAD: ALL LANES OPEN TO TRAFFIC		NO REST	RICTION	1 MINUTE	\$315			
SHEPHERD CREEK: ALL LANES OPEN TO TRAFFIC		NO REST	RICTION	1 MINUTE	\$315			
MONTANA AVENUE: ALL LANES OPEN TO TRAFFIC	6	AM TO 9 AM AN	D 3 PM TO 7 PM	1 MINUTE	\$315			

#### ŅOTE

- 1. ON I-74 MAINTAIN A MINIMUM OF 1 LANE OF TRAFFIC IN EACH DIRECTION AT ALL TIMES.
- 2. THE EXIT RAMP FROM I-74 (EITHER DIRECTION) TO NORTH BEND ROAD SHALL BE MAINTAINED AT ALL TIMES.
- 3. TURN LANE REDUCTION ON ANY RAMP SHALL FOLLOW THE I-74 LANES OPEN TIMES. ONLY 1 RAMP IS PERMITTED TO BE CLOSED AT A TIME.
- 4. NO CLOSURES 2 HOURS BEFORE (EASTBOUND) AND 2
  HOURS AFTER (WESTBOUND) EVENTS AT GREAT AMERICAN
  BALL PARK, PAYCOR STADIUM, TQL STADIUM, OR HERITAGE
  BANK AREA. THIS RESTRICTION ALSO APPLIES TO ANY OTHER
  LOCAL VENUE GENERATING AN EVENT ATTENDANCE OF 15,000+.
- 5. NO SHORT-TERM SHOULDER CLOSURES INCLUDING RAMPS BETWEEN 6AM TO 9AM AND 3PM TO 7PM MONDAY THROUGH FRIDAY.

#### INTERIM COMPLETION REQUIREMENTS

THE PROJECT HAS AN INTERIM COMPLETION DATE.
SEE BELOW TABLE FOR FURTHER INFORMATION.

THE CONTRACT WILL BE SUBJECT TO DAILY DISINCENTIVES FOR FAILURE TO COMPLETE ALL THE REQUIRED WORK, AND ASSOCIATED INCIDENTALS RELATED TO THE WORK, AS OUTLINED IN THE TABLE INCLUDED IN THIS NOTE. APPLICATION OF THE DISINCENTIVES WILL BE BASED ON THE OVERALL CONTRACT AMOUNT. DAILY DISINCENTIVES ARE APPLICABLE TO THE WORK REQUIRED TO THE INTERIM COMPLETION DATE ONLY. THE CONTRACT IS STILL SUBJECT TO LIQUIDATED DAMAGES AS OUTLINED IN CMS 108.07 FOR THE REMAINDER OF THE CONTRACT.

Description or Location of Critical Work	Completion Date	Time Period	Disincentive \$ per Time Period
ALL PAVEMENT REPAIR WORK EXCEPT PAVEMENT REPAIR FOR CURB RAMP INSTALLATION	11/1/2024	DAY	\$5,000

#### PROJECT COORDINATION

COORDINATION WITH PID 110563

PID 110563 (RACE ROAD BRIDGEOVER I-74) AND THIS PROJECT PID 88679 (I-74 2"MILL/FILL WITH BRIDGE REHAB) WILL BE UNDER CONSTRUCTION AT THE SAME TIME. PID 110563 WILL HAVE THE I-74 MEDIAN AND OUTSIDE SHOULDERS CLOSED IN BOTH DIRECTIONS AT RACE ROAD WITH CLOSURES LIKELY EXTENDING BEYOND THIS PROJECT'S COMPLETION DATE THE PID 88679 (I-74 2"MILL/FILL WITH BRIDGE REHAB). THE CONTRACTOR FOR PID 110563 SHALL COORDINATE THEIR WORK AND MOT WITH THIS PROJECT; WORK AND MOT ON PID 88679 GOVERNS AND CONTROLS.

TO PREVENT REWORK, THE I-74 SHOULDER RESURFACING SHALL BE OMITTED FROM THIS PROJECT APPROXIMATELY 1240 CY' FROM THE RACE ROAD BRIDGE IN BOTH DIRECTIONS. THE TRAVEL LANES INCLUDING EDGE LINES SHALL BE RESURFACED.

COORDINATION WITH PID 104668:
THIS PROJECT AND PID 104668
(I-74 RECONSTRUCTION) WILL BE UNDER CONSTRUCTION AT THE SAME TIME. PID 104668 WILL HAVE THE
WB BEEKMAN EXIT RAMP CLOSED AND TRAFFIC DETOURED USING A TEXAS TURN AROUND (TTA) AT MONTANA AVENUE DURING 2024
WHILE MAINLINE WORK CONTINUES THROUGH 2025. THE
CONTRACTOR FOR THIS PROJECT SHALL COORDINATE THEIR WORK AND PID 104668. WORK AND MOT ON PID
104668 GOVERNS AND CONTROLS WITH ADDITIONAL REQUIREMENTS AS FOLLOWS:

- CURB RAMP RECONSTRUCTION ON MONTANA AVENUE SHALL
   NOT BEGIN UNTIL APRIL 1, 2025 WHEN THE TTA HAS BEEN REMOVED
   AND MONTANA AVENUE PLACED IN FINAL CONFIGURATION.
- 2. RESURFACING ON THE MONTANA AVENUE ENTRANCE/EXIT RAMPS SHALL NOT BEGIN UNTIL APRIL 1, 2025 WHEN THE TTA HAS BEEN REMOVED AND MONTANA AVENUE ENTRANCE/EXIT RAMPS PLACED IN FINAL CONFIGURATION.
- 3. RESURFACING ON 1-74 MAINLINE SHALL BE COORDINATED WITH THE PID 104668 THAT WILL BE PERFORMING WORK INCLUDING RESURFACING ON 1-74 MAINLINE UNTIL SEPTEMBER 1, 2025.

DESIGN AGEN



DESIGNER
JED
REVIEWER
SK 9/20/23
PROJECT ID
88679

09 TOTAL 53

SHEET NUM. PART. ITEM GRAND SEE UNIT DESCRIPTION ITEM SHEET NO 4A 10 12 19 20 01/IMS/05 02/IMS/13 EXT TOTAL **ROADWAY** 4A LUMP LUMP 201 11001 LS CLEARING AND GRUBBING, AS PER PLAN 17 17 PAVEMENT REMOVED 13 202 23000 178 178 178 SF WALK REMOVED 202 30000 16 16 202 32000 16 FT **CURB REMOVED** 825 825 202 38000 825 FT GUARDRAIL REMOVED EACH ANCHOR ASSEMBLY REMOVED, TYPE E 2 202 42010 2 EACH IMPACT ATTENUATOR REMOVED, AS PER PLAN 202 47801 20 475 475 606 15100 475 FT GUARDRAIL, TYPE MGS WITH LONG POSTS 337.5 337.5 606 15150 337.5 FT GUARDRAIL, TYPE MGS HALF POST SPACING 606 26101 EACH ANCHOR ASSEMBLY, TYPE E, AS PER PLAN, (MASH 2016) 12 2 60040 IMPACT ATTENUATOR, TYPE 3 UNIDIRECTIONAL 606 EACH 64 64 SF 4" CONCRETE WALK 64 608 10000 130 130 608 52000 130 SF CURB RAMP **EROSION CONTROL** GEOTEXTILE FABRIC 350 350 204 50000 350 SY GENERAL SUMMARY 97 97 601 28000 97 CY DUMPED ROCK FILL, TYPE D 2,000 832 30000 2,000 EACH EROSION CONTROL, (MASH 2016) ENVIRONMENTAL / REMEDIATION LS SPECIAL LS MISC,: WORK INVOLVING ASBESTOS CONTAINING MATERIALS LS 69098400 PAVEMENT 1,400 1,400 PAVEMENT REPAIR, (A) 2 2 253 02000 2 CY PAVEMENT REPAIR, (B) 391,779 391,779 254 01000 391,779 SY PAVEMENT PLANING, ASPHALT CONCRETE, 2" 254 3,934 SY PATCHING PLANED SURFACE 3.934 3.934 01600 23,507 23,507 407 20000 23,507 GAL NON-TRACKING TACK COAT 13,621 13,621 442 00100 13,621 ANTI-SEGREGATION EQUIPMENT 21,766 21,766 442 10000 21,766 CY ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446) COMPACTED AGGREGATE 753 753 617 10100 753 CY 18,515 18,515 617 18,515 SY SHOULDER PREPARATION 20000 15 15 617 15 25000 MGAL WATER RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE) 30.8 30.8 618 40600 30.8 MILE 211,624 211,624 872 10000 211,624 FT VOID REDUCING ASPHALT MEMBRANE (VRAM) TRAFFIC CONTROL 1 776 1,776 1.776 621 00100 EACH RAISED PAVEMENT MARKER REMOVED 1,776 1,776 621 54000 1,776 EACH 15 626 00110 15 EACH BARRIER REFLECTOR, TYPE 2, BI-DIRECTIONAL 0.58 0.58 EDGE LINE, 6", TYPE 1 0.58 642 00104 MILE 0.58 0.58 642 00104 0.58 MILE EDGE LINE, 6", TYPE 1 0.29 0.29 642 00204 0.29 MILE LANE LINE, 6", TYPE 1 0.29 0.29 642 0.29 MILE 00204 LANE LINE, 6", TYPE 1 572 572 572 FT 642 00404 CHANNELIZING LINE, 12", TYPE 1 572 572 642 00404 572 FT CHANNELIZING LINE, 12", TYPE 1 144 144 644 00500 144 FT STOP LINE 418 418 644 418 CROSSWALK LINE, 12" 00620 60 60 644 00700 60 TRANSVERSE/DIAGONAL LINE 809 809 CHEVRON MARKING 644 00720 809 HAM-IR 74-11.16 33 33 644 01300 33 EACH LANE ARROW 11 11 644 01360 11 EACH WRONG WAY ARROW 644 01410 EACH WORD ON PAVEMENT, 96" NCD 644 22 22 40000 22 EACH SPEED MEASUREMENT MARKING 32.94 32.94 807 10010 32.94 WET REFLECTIVE TRAFFIC PAINT, EDGE LINE, 6" IDO 9/20/23 17 807 10110 17 MILE WET REFLECTIVE TRAFFIC PAINT, LANE LINE, 6" 9,952 9,952 807 10310 9,952 FT WET REFLECTIVE TRAFFIC PAINT, CHANNELIZING LINE, 12" 88679 4,076 10420 4,076 WET REFLECTIVE TRAFFIC PAINT, DOTTED LINE, 8" 10 53

- (A) EXISTING ASPHALT CONCRETE PAVEMENT, 4-1/2"+/- ASPHALT, 10"+/- CONCRETE
- 1) ITEM 442 2" ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A,(446) PWL, 2025 AS PER PLAN
- 2) ITEM 254 2" PAVEMENT PLANING, ASPHALT CONCRETE
- 3 ITEM 407 NON-TRACKING TACK COAT

HAM-IR 74-11.16

4 COMPACTED AGGREGATE, 1.5" DEPTH, 12" WIDTH

										254		407		442			617		618	872					
PLAN SPLIT	COUNTY-	COUNTY- ROUTE				LOG POI	NT (MILE)	LEN	NGTH	PAVEMENT AREA (Micro- Station	PAVEMENT AREA WITH NO SHOULDERS	PAVEMENT AREA	1	ENT PLANING T CONCRETE	PLANED	NON TRACKING TACK COAT @	SURFAC TYPE A,	HALT CONCRETE EE COURSE, 12.5 MM, (446), PWL, 2025 AS PER PLAN	SEGREGATION	COMPACTED AGGREGATE, 1.5" DEPTH, 12"	SHOULDER PREPARATION	WATER @ 20 GAL/CU	RUMBLE STRIPS, SHOULDER	VOID REDUCING ASPHALT	NOTES
			FROM	то			Generated Area)			DEPTH			0.06 GAL/SQ YE	THICK- NESS		EQUIPMENT	WIDTH		YD	(ASPHALT CONCRETE)	MEMBRANE				
				MILES	FT	SQ FT	SQ FT	SQ YD	INCHES	SQ YD	SQ YD	GAL	INCHES	CU YD	CU YD	CU YD	SQ YD	MGAL	MILES	FEET					
04/1140/05	DAMP FROM HARRIGON AVE TO LIZA FR	0.00	0.40	0.40	050	05040	40400	0040	0.00	0040.0	200	400.0	0.00	450.0	400.0	0.0	044.0	0.0	0.00	0054					
01/IMS/05	RAMP FROM HARRISON AVE TO I-74 EB	0.00	0.18	0.18	950	25313	16193	2813	2.00	2812.6	29	168.8	2.00	156.3	100.0	8.8	211.2	0.2	0.36	2851					
01/IMS/05	HAM-74 EB	11.16	12.38	1.22	6442	252522	149530	28058	2.00	28058.0	281	1683.5	2.00	1558.8	923.0	59.6	1431.5	1.2	2.36	18690					
01/IMS/05	HAM-74 EB	12.38	12.70	0.32	1690	68682	40550	7631	2.00	7631.3	77	457.9	2.00	424.0	250.3	15.6	375.5	0.3	0.64	5070					
01/IMS/05	HAM-74 EB	12.70	13.30	0.60	3168	83787	76032	9310	2.00	9309.7	94	558.6	2.00	517.2	469.3	29.3	399.0	0.6	0.68	9504	SHOULDER WORK OMITTED SEE SHEE				
01/IMS/05	HAM-74 EB	13.30	13.95	0.65	3432	65480	76032	7276	2.00	7275.6	73	436.5	2.00	404.2	469.3	1 11	400.0	0.4	0.40	7128	FOR DETAILS				
01/IMS/05	HAM-74 EB	13.95	14.40	0.45	2376	79822	61350	8869	2.00	8869.1	89	532.1	2.00	492.7	378.7	4.4	106.0	0.1	0.18	4752					
01/IMS/05	HAM-74 EB	14.40	14.70	0.30	1584	89544	47033	9949	2.00	9949.3	100	597.0	2.00	552.7	290.3	14.7	352.0	0.3	0.60	11088					
01/IMS/05	HAM-74 EB	14.70	15.40	0.70	3696	181624	129555	20180	2.00	20180.4	202	1210.8	2.00	1121.1	799.7	34.2	821.3	0.7	1.40	12672					
01/IMS/05	HAM-74 EB	15.40	16.20	0.80	4224	163332	101376	18148	2.00	18148.0	182	1088.9	2.00	1008.2	625.8	39.1	938.7	0.8	1.60	3960					
01/IMS/05	HAM-74 EB	16.20	16.50	0.30	1584	62738	31680	6971	2.00	6970.9	70	418.3	2.00	387.3	195.6	14.7	352.0	0.3	0.50	14256					
1/IMS/05	HAM-74 EB	16.50	17.40	0.90	4752	190330	114048	21148	2.00	21147.8	212	1268.9	2.00	1174.9	704.0	44.0	1056.0	0.9	1.80	8712					
1/IMS/05	HAM-74 EB	17.40	18.00	0.60	3168	155622	69670	17291	2.00	17291.3	173	1037.5	2.00	960.6	430.1	29.3	704.0	0.6	1.10	3486					
01/IMS/05	RAMP FROM EB IR 74 TO NORTH BEND RD	0.00	0.22	0.22	1162	32863	21450	3651	2.00	3651.4	37	219.1	2.00	202.9	132.4	10.8	258.1	0.2	0.44	1162					
01/IMS/05	RAMP FROM NORTH BEND RD SB TO IR 74 EB	0.00	0.14	0.14	739	18191	11830	2021	2.00	2021.2	21	121.3	2.00	112.3	73.0	6.8	164.3	0.1	0.28	739					
01/IMS/05	RAMP FROM NORTH BEND RD NB TO IR 74 EB	0.00	0.16	0.16	845	20927	13516	2325	2.00	2325.2	24	139.5	2.00	129.2	83.4	7.8	187.7	0.2	0.32	845					
01/IMS/05	RAMP FROM MONTANA AVE TO IR 74 EB	0.00	0.11	0.11	581	39357	14300	4373	2.00	4373.0	44	262.4	2.00	242.9	88.3	5.4	129.1	0.1	0.22	581					
01/IMS/05	HAM-74 WB	11.16	12.38	1.22	6442	259059	149530	28784	2.00	28784.3	288	1727.1	2.00	1599.1	923.0	59.6	1431.5	1.2	2.36	18690					
01/IMS/05	HAM-74 WB	12.38	12.70	0.32	1690	65586	40550	7287	2.00	7287.3	73	437.2	2.00	404.9	250.3	15.6	375.5	0.3	0.64	5070					
01/IMS/05	HAM-74 WB	12.70	13.30	0.60	3168	82965	76032	9218	2.00	9218.3	93	553.1	2.00	512.1	469.3	29.3	704.0	0.6	1.20	9504	SHOULDER WORK OMITTED SEE SHEI				
01/IMS/05	HAM-74 WB	13.30	13.95	0.65	3432	68853	76032	7650	2.00	7650.3	77	459.0	2.00	425.0	469.3	31.8	762.7	0.6	1.20	7128	FOR DETAILS				
01/IMS/05	HAM-74 WB	13.95	14.40	0.45	2376	90160	61352	10018	2.00	10017.8	101	601.1	2.00	556.5	378.7	22.0	528.0	0.4	0.90	4752	TOTABE TABLES				
01/IMS/05	HAM-74 WB	14.40	14.70	0.30	1584	131107	77603	14567	2.00	14567.4	146	874.0	2.00	809.3	479.0	14.7	352.0	0.3	0.60	11088					
01/IMS/05	HAM-74 WB	14.70	15.40	0.70	3696	196056	142074	21784	2.00	21784.0	218	1307.0	2.00	1210.2	877.0	34.2	821.3	0.7	1.40	12672					
01/IMS/05	HAM-74 WB	15.40	16.20	0.80	4224	214619	152064	23847	2.00	23846.6	239	1430.8	2.00	1324.8	938.7	39.1	938.7	0.8	1.60	3960					
01/IMS/05	HAM-74 WB	16.20	16.50	0.30	1584	79826	47520	8870	2.00	8869.6	89	532.2	2.00	492.8	293.3	14.7	352.0	0.3	0.50	14256					
01/IMS/05	HAM-74 WB	16.50	17.40	0.90	4752	245808	171072	27312	2.00	27312.0	274	1638.7	2.00	1517.3	1056.0	44.0	1056.0	0.9	1.80	8712					
01/IMS/05	HAM-74 WB	17.40	18.00	0.60	3168	166591	104544	18510	2.00	18510.1	186	1110.6	2.00	1028.3	645.3	29.3	704.0	0.6	1.10	3486					
01/IMS/05	RAMP FROM WB IR 74 TO MONTANA RD	0.00	0.05	0.05	264	7316	16618	813	2.00	812.9	9	48.8	2.00	45.2	102.6	2.4	58.7	0.0	0.10	792	PROTION OF MONTANA RAMP WILL E				
01/IMS/05	RAMP FROM WB IR 74 TO NORTH BEND RD	0.00	0.23	0.23	1214	31615	23383	3513	2.00	3512.8	36	210.8	2.00	195.2	144.3	11.2	269.9	0.2	0.46	1214	RESURFACE WITH PID 104668				
01/IMS/05	RAMP FROM NORTH BEND RD NB TO IR 74 WB	0.00	0.15	0.15	792	19275	11166	2142	2.00	2141.7	22	128.5	2.00	119.0	68.9	7.3	176.0	0.1	0.30	792					
01/IMS/05	RAMP FROM NORTH BEND RD SB TO IR 74 WB	0.00	0.14	0.14	739	17547	13291	1950	2.00	1949.7	20	117.0	2.00	108.3	82.0	6.8	164.3	0.1	0.28	739					
01/IMS/05	RAMP FROM NB HARRISON RD TO IR 74 WB	0.00	0.28	0.28	1478	38396	26680	4266	2.00	4266.2	43	256.0	2.00	237.0	164.7	13.7	328.5	0.3	0.56	1478					
01/IMS/05	RAMP FROM IR 74 WB TO HARISON RD	0.00	0.34	0.34	1795	63450	42960	7050	2.00	7050.0	71	423.0	2.00	391.7	265.2	16.6	398.9	0.3	0.68	1795					
1		1			1				1		1		1												
TOTALS CA	ARRIED TO GENERAL SUMMARY			•	•		•			367596	3693	22056		20422	13621	717	16908	14	28.16	211624					

DES**I**GN AGENCY



DESIGNER
NCD
REVIEWER
JDO 9/20/23
PROJECT ID
88679
SHEET TOTAL

MODEL: Sheet PAPERSIZE: 17x11 (in.) DAI

	PM00
	88679 PI
	\Sheets\
	Roadway
	Veering√
	00-Engir
	88679\4
jdavis4	\Hamilton
1 USER	jects\District 08\Hamilton\88679\400-En
DATE: 2/1/2024 TIME: 1:26:28 PM	jects\Dis
TIME: 1:	ctive Pro
/1/2024 T	ents\01 A
DATE: 2/	\Docum
1 (in )	ot-pw-02\D
ZE: 17x1	m:ohiod
PAPERSIZE: 17x11 (in.) DATE: 2/1/2024 TIME: 1:26:28 PM USER	entley.co
α.	q


							807 THERM	10			642 T	TRAFFIC PAIN	IT.			850							644					
PART	COUNTY- ROUTE	LOG PO	INT (MILE)	TOTAL	EDGE	E LINE 6"	6" LANE LINE WHITE	12" CHANNELIING LINE	6" DOTTED LINE	EDGE	LINE 6"	6" LANE LINE WHITE	12" CHANNELIZING LINE	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	GROOVING FOR 8" RECESSED PAVEMENT MARKING, (CONCRETE)	GROOVING FOR 12' RECESSED PAVEMENT MARKING, (CONCRETE)	24" CHEVRON LINE	24" TRANSVERS DIAGONAL YELLOW	24" STOP LINE	WORD ON PAVEMENT ONLY	WRONG WAY ARROW	LEFT	LANE ARR	ROWS LEFT/R <b>I</b> GHT	12" ROSSWALK	REMARKS
		FROM	TO	MILE	MILE	MILE	MILE	FEET	FEET	MILE	MILE	MILE	FEET	FEET	MILES	FEET	MILES	FEET	FEET	FEET	FEET	EACH	EACH	EACH	EACH	EACH	FEET	
									<u> </u>												1							
01/IMS/05	RAMP FROM HARRISON AVE TO 1-74 EB	0.00	0.18	0.18	0.18	0.18									0.36													
01/IMS/05	HAM-74 EB	11.16	12.38	1.22	1.33	1.28	1.23	253	660					253	3.84	660												
01/IMS/05	HAM-74 EB	12.38	12.70	0.32	0.32	0.32	0.32								0.96													
01/IMS/05	HAM-74 EB	12.70	13.30	0.60	0.6	0.6	0.6								1.8													
01/IMS/05	HAM-74 EB	13.30	13.95	0.65	0.65	0.65	0.65								1.95													
01/IMS/05	HAM-74 EB	13.95	14.40	0.45	0.45	0.45	0.45		546						1.35	546												
01/IMS/05	HAM-74 EB	14.40	14.70	0.30	0.41	0.41	0.3	580						580	1.12				132									
01/ <b>I</b> MS/05	HAM-74 EB	14.70	15.40	0.70	0.9	0.89	0.7	1343						1343	2.49													
01/IMS/05	HAM-74 EB	15.40	16.20	0.80	0.78	0.78	0.78								2.34													
01/IMS/05	HAM-74 EB	16.20	16.50	0.30	0.3	0.3	0.3								0.9		0.06											
01/IMS/05	HAM-74 EB	16,50	17.40	0.90	0.9	0.9	0.9		<u> </u>			1			2.7						1							
01/IMS/05	HAM-74 EB	17,40	18,00	0.60	0,69	0,69	0.81	2420	L			<b>_</b>		2420	2.19		0.12				24							
01/IMS/05	RAMP FROM EB IR 74 TO NORTH BEND RD	0.00	0.22	0.22	0.22	0.22	ļ	386				<u> </u>		386	0.44						30		3	4	4		80	
01/ <b>I</b> MS/05	RAMP FROM NORTH BEND RD SB TO IR 74 EB	0.00	0.14	0.14	0.14	0.14						<u> </u>			0.28												48	
01/IMS/05	RAMP FROM NORTH BEND RD NB TO IR 74 EB	0.00	0.16	0.16	0.16	0.16									0.32												48	
01/IMS/05	RAMP FROM MONTANA AVE TO IR 74 EB	0.00	0.11	0.11	0.11	0.11									0.22													
			<b></b>				L					<u> </u>																
01/IMS/05	HAM-74 WB	11.16	12.38	1.22	1.24	1.24	1.3	550	250			<u> </u>		550	3.78	250	0.15	575	343									
01/IMS/05	HAM-74 WB	12.38	12.70	0.32	0.32	0.32	0.32					<u> </u>			0.96													
01/IMS/05	HAM-74 WB	12.70	13.30	0.60	0.6	0.6	0.6					<u> </u>			1.8													
01/IMS/05	HAM-74 WB	13.30	13.95	0.65	0.65	0.65	0.65		4040		-	<del> </del>			1.95	4040					1							
01/IMS/05	HAM-74 WB	13.95	14.40	0.45	0.45	0.45	0.45	540	1040			1		540	1.35	1040					1				-			
01/IMS/05 01/IMS/05	HAM-74 WB HAM-74 WB	14.40 14.70	14.70	0.30	0.52 0.7	0.52	0.3	510	540			<b>-</b>		510 530	1.34	540			400									
01/IMS/05 01/IMS/05	HAM-74 WB	15.40	15.40	0.70		0.7	1.4	530				1		530	2.8				103		1							
01/IMS/05 01/IMS/05	HAM-74 WB	16.20	16.20 16.50	0.80	0.8	0.8	1.6 0.6		-			<b>-</b>			3.2 1.2		0.08											
01/IMS/05 01/IMS/05	HAM-74 WB	16.50	17.40	0.90	0.9	0.9	1.8				1				3.6		0.12		1		1		1		<del>                                     </del>			
01/IMS/05	HAM-74 WB	17.40	18.00	0.60	0.56	0.56	0.88	1950	1040			<b> </b>		1950	2	1040	0.12		231									
01/IMS/05	RAMP FROM WB IR 74 TO MONTANA RD	0.00	0.05	0.05	0.05	0.05	0.05	1330	1040		<b>+</b>	<b>-</b>		1550	0.1	1040			201		<del> </del>							
01/IMS/05	RAMP FROM WB IR 74 TO NORTH BEND RD	0.00	0.23	0.23	0.23	0.23	0.00								0.46				1				3		1	3		
01/IMS/05	RAMP FROM NORTH BEND RD NB TO IR 74 WB	0.00	0.15	0.15	0.15	0.15	1					1			0.3								† Ť			Ü	36	
01/IMS/05	RAMP FROM NORTH BEND RD SB TO IR 74 WB	0.00	0.14	0.14	0.14	0.14		50				<u> </u>		50	0.28												36	
01/IMS/05	RAMP FROM NB HARRISON RD TO IR 74 WB	0.00	0.28	0.28	0.28	0.34	t	1200						1200						60	50		1	13	7			
01/IMS/05	RAMP FROM IR 74 WB TO HARISON RD	0.00	0.34	0.34	0.34	0.34																						
					İ		İ					İ																
02/IMS/13	HAM-74-1116 L	11.16	11,21	0.05						0.05	0.05	0.05	572															
02/IMS/13	HAM-74-1116 R	11,16	11,21	0.04						0.04	0.04	0.4																
02/IMS/13	HAM-74-1292 L	12.92	12.95	0.03						0.03	0.03	0.03																
02/IMS/13	HAM-74-1292 R	12.92	12.95	0.04						0.04	0.04	0.04																
02/IMS/13	HMA-74-1618 L	16.18	16.20	0.02						0.02	0.02	0.02																
02/IMS/13	HAM-74-1618R	16,18	16.20	0.035						0.035	0.035	0.035																
02/IMS/13	HAM-74-1744 L	17.44	17.47	0.037						0.037	0.037	0.037																
02/IMS/13	HAM-74-1744 R	17.44	17.47	0.037						0.037	0.037	0.037																
	TOTALS CARRIED TO GENERAL SUMMARY				3.	2.74	16.99	9952	4076	С	1.58	0.29	572	9952	48.64	4076	0.53	575	809	60	104	1	7		31		248	


PAVEMENT MARKINGS

NCD REVIEWER JDO 9/20/23

88679

SHEET TOTAL 13 53







DESIGN AGENCY



DESIGNER
JED

REVIEWER
JDO 9/20/223

PROJECT ID

88679

88679
SHEET TOTAL
15 53

## 74-11

#### REFER TO THE FOLLOWING STANDARD DRAWINGS:

1/17/14 FXJ-4-87 7/21/23 BR-1-13 PCB-91 7/17/20 GSD-1-19 1/15/21

#### DESIGN SPECIFICATIONS

THIS STRUCTURE CONFORMS TO "LRFD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 9th ED., AND THE 2020 ODOT BRIDGE DESIGN MANUAL.

#### **DESIGN LOADING**

C.F. 2000 (57) => HAM-74-11.16 L/R, HAM-74-12.92 L/R, HAM-74-16.18 L/R & HAM-74-17.44 L/R

#### **DESIGN STRESSES**

CLASS QC1 CONCRETE - COMPRESSIVE STRENGTH 4.0 KSI (MEDIAN BARRIER)

CLASS QC2 CONCRETE - COMPRESSIVE STRENGTH 4.5 KSI (SUPERSTRUCTURE)

REINFORCING STEEL - MINIMUM YIELD STRENGTH 60 KSI STRUCTURAL STEEL - ASTM A709 GRADE 50, MINIMUM YIELD STRENGTH = 50 KSI

#### PATCHING AND REPAIR OF BRIDGE PARAPETS

PATCHING OF BRIDGE PARAPETS SHALL ADHERE TO ALL REQUIREMENTS OF CMS 519.

FULL DEPTH REPAIR OF BRIDGE PARAPETS SHALL ADHERE TO ALL REQUIREMENTS OF CMS 511 FOR QC2 CONCRETE, SUPERSTRUCTURE.

PARAPET REPAIR DIMENSIONS PROVIDE LENGTH ALONG THE PARAPET BY HEIGHT MEASURED DOWN FROM THE TOP OF PARAPET UNLESS OTHERWISE NOTED.

FOR FULL DEPTH PARPET REPAIRS, ALL EXISTING PARAPET REINFORCING STEEL SHALL REMAIN IN PLACE FOR RE-USE.

#### ITEM 512 - SEALING OF CONCRETE SURFACES (EPOXY-URETHANE

THIS ITEM INCLUDES SEALING THE CONCRETE SUPERSTRUCTURE AND SUBSTRUCTURE SURFACES OF SPECIFIED BRIDGES AS SHOWN ON THE PLANS. THE COLOR OF THE URETHANE COATING SHALL BE FEDERAL COLOR STANDARD NO. 17778 (LIGHT NEUTRAL) FOR THE BRIDGE PARAPETS.

PAYMENT FOR THIS WORK SHALL INCLUDE ALL EQUIPMENT, MATERIAL AND LABOR NECESSARY TO PERFORM THIS TASK. PAYMENT SHALL BE MADE AT THE BID PRICE PER SQUARE YARD.

### PATCHING AND/OR RECONSTRUCTION OF TOP OF ABUTMENT

PATCHING AND/OR RECONSTRUCTION OF TOP OF ABUTMENT BACK WALLS SHALL PROCEED IN ACCORDANCE WITH PROPOSAL NOTE 512. EXISTING REINFORCING STEEL SHALL REMAIN IN PLACE FOR RE-USE. ALL WORK. EQUIPMENT, MATERIALS, ETC. REQUIRED TO COMPLETE THE PROPOSED IMPROVEMENTS SHALL BE PAID FOR UNDER:

ITEM SPECIAL - PATCHING CONCRETE BRIDGE DECKS, TYPE B (SQUARE YARD).

#### ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN

THIS WORK CONSISTS OF THE REMOVAL OF PORTIONS OF THE EXISTING STRUCTURES, ETC. AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER. THE PROVISIONS OF ITEM 202 APPLY EXCEPT AS SPECIFIED BY THE FOLLOWING NOTES. PERFORM WORK CAREFULLY DURING SUPERSTRUCTURE AND SUBSTRUCTURE REMOVALS TO PROTECT PORTIONS OF SUCH SYSTEMS THAT ARE TO BE SALVAGED AND INCORPORATED INTO THE PROPOSED STRUCTURE. THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE RAM TYPE OF EQUIPMENT IS PROHIBITED. SUBMIT CONSTRUCTION AND DEMOLITION PLANS TO THE ENGINEER FOR APPROVAL.

THE CONTRACTOR MUST REVIEW THE STRUCTURE WHEN PREPARING HIS BID. THE CONTRACTOR WILL REVIEW THE CONDITION OF THE STRUCTURE TO DETERMINE WHAT DEBRIS WILL FALL FROM THE STRUCTURE DURING REMOVAL. THE CONTRACTOR WILL DETERMINE THE CORRESPONDING COST TO CLEAN UP ANY AND ALL DEBRIS WHICH FALLS FROM THE STRUCTURE DURING ALL REMOVAL OPERATIONS. THE COST TO CLEAR AND CLEAN UP ALL DEBRIS DURING REMOVAL SHALL BE INCLUDED WITH THE BID FOR THIS ITEM OF WORK. NO ADDITIONAL COST WILL BE RECOGNIZED TO CLEAN DEBRIS RESULTING FROM THE STRUCTURE REMOVAL OPERATION.

CUT LINE CONSTRUCTION JOINT PREPARATION: SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS 1 INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE. LEAVE THE EXISTING REINFORCING STEEL, IF REQUIRED IN THE PLANS, IN PLACE. INSTALL DOWEL BARS IF SPECIFIED. PRIOR TO CONCRETE PLACEMENT ABRASIVELY CLEAN JOINT SURFACES AND EXISTING EXPOSED REINFORCEMENT TO REMOVE LOOSE AND DISINTEGRATED CONCRETE AND LOOSE RUST. THOROUGHLY CLEAN THE JOINT SURFACE AND EXPOSED REINFORCEMENT OF ALL DIRT, DUST, RUST, OR OTHER FOREIGN MATERIAL BY THE USE OF WATER, AIR UNDER PRESSURE, OR OTHER METHODS THAT PRODUCE SATISFACTORY RESULTS. EXISTING REINFORCING STEEL DOES NOT HAVE TO HAVE A BRIGHT STEEL FINISH, BUT REMOVE ALL PACK AND LOOSE RUST. THOROUGHLY DRENCH EXISTING CONCRETE SURFACES WITH CLEAN WATER AND ALLOW TO DRY TO A DAMP CONDITION BEFORE PLACING CONCRETE.

SUBSTRUCTURE CONCRETE REMOVAL: REMOVE CONCRETE BY MEANS OF APPROVED PNEUMATIC HAMMERS EMPLOYING POINTED AND BLUNT CHISEL TOOLS. HYDRAULIC HOE-RAM TYPE HAMMERS WILL NOT BE PERMITTED. THE WEIGHT OF THE HAMMER SHALL NOT BE MORE THAN 35 POUNDS FOR REMOVAL WITHIN 18 INCHES OF PORTIONS TO BE PRESERVED. OUTSIDE THE 18 INCH LIMIT, THE CONTRACTOR MAY USE HAMMERS NOT EXCEEDING 90 POUNDS UPON THE APPROVAL OF THE ENGINEER. DO NOT PLACE PNEUMATIC HAMMERS IN DIRECT CONTACT WITH REINFORCING STEEL THAT IS TO BE RETAINED IN THE REBUILT STRUCTURE.

THE CONTRACTOR SHALL TAKE CARE NOT TO DAMAGE ANY PORTION OF THE STRUCTURE THAT WILL REMAIN IN SERVICE. ANY PORTION OF THE REMAINING STRUCTURE DAMAGED AS A RESULT OF CONTRACTOR ACTIONS SHALL BE REPLACED IN KIND AT THE CONTRACTOR'S EXPENSE.

MEASUREMENT & PAYMENT: THE DEPARTMENT WILL MEASURE THE QUANTITY OF REMOVALS ON A LUMP SUM BASIS. THE DEPARTMENT WILLPAY FOR THE ACCEPTED QUANTITIES OF REMOVALS AT THE CONTRACT PRICE FOR ITEM 202, PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN.

#### ITEM SPECIAL: CONSULTANT FOR CONCRETE QUALITY CONTROL **INCLUDING TESTING AND INSPECTION**

ALL CONCRETE SHALL BE TESTED. ALL TESTING, INSPECTION AND QUALITY CONTROL FOR CONCRETE, NOT INCLUDED UNDER QC/QA PAY ITEMS, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL PROVIDE A CONCRETE TESTING CONSULTANT WITH PREVIOUS EXPERIENCE AND FAMILIARITY IN ODOT PROCEDURES, CONCRETE TESTING REQUIREMENTS AND CONCRETE TESTING DOCUMENTATION. AT LEAST 30 DAYS PRIOR TO CONCRETE PLACEMENT, SUBMIT TO THE ENGINEER FOR APPROVAL, THE PROPOSED CONCRETE TESTING CONSULTANT ALONG WITH THE RESUMES OF THE PROPOSED TESTING PERSONNEL.

TESTING CONCRETE FOR STRUCTURES AND PORTLAND CEMENT CONCRETE PAVEMENT SHALL BE PERFORMED AS OUTLINED IN CONSTRUCTION AND MATERIAL SPECIFICATIONS 455.

THROUGH THE CONTRACTOR, THE CONSULTANT SHALL BE RESPONSIBLE FOR ENSURING THAT ALL CONCRETE PLACED IS IN ACCORDANCE WITH THE SPECIFICATIONS. SUCH WORK SHALL BE IN ACCORDANCE WITH THE APPLICABLE CONSTRUCTION AND MATERIAL SPECIFICATIONS AND THE ODOT CONSTRUCTION INSPECTION MANUAL OF PROCEDURES FOR CONCRETE. THE CONCRETE CONSULTANT SHALL PROVIDE THE NECESSARY TRAINED TECHNICIAN(S) AND EQUIPMENT AND SHALL FURNISH THE PROJECT ENGINEER WITH TWO (2) COPIES OF ALL TEST RESULTS WITHIN 24 HOURS AFTER COMPLETION OF CONCRETE PLACEMENT.

THE TECHNICIANS SHALL BE ACI LEVEL 1 CERTIFIED AND WILL BE REQUIRED TO DEMONSTRATE HIS/HER COMPETENCE AND EXPERIENCE LEVELS TO THE ENGINEER PRIOR TO BEGINNING WORK. THE ENGINEER WILL ORDER THE CONTRACTOR TO REPLACE ANY TECHNICIAN THAT IS NOT VERSED IN THE REQUIRED TESTING PROCEDURE.

THE TECHNICIAN SHALL VERBALLY NOTIFY THE ODOT PROJECT ENGINEER OF ANY FAILING TESTS AND SHALL SUBMIT FOLLOW-UP WRITTEN NOTIFICATION TO THE PROJECT ENGINEER OF REMEDIAL ACTION(S) TAKEN. TESTS SHALL BE TAKEN AS SPECIFIED WITHIN THE CONSTRUCTION AND MATERIAL SPECIFICATIONS, CONCRETE MANUAL OR APPROPRIATE SUPPLEMENTAL SPECIFICATION AS LISTED IN THE PROPOSAL GOVERNING THE PROJECT. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO MAKE IMMEDIATE CORRECTIONS OR ADJUSTMENTS TO THE CONCRETE MIX VIA DIRECT COMMUNICATION WITH THE CONCRETE SUPPLIER'S PLANT PERSONNEL TO MAINTAIN UNINTERRUPTED COMPLIANCE WITH THE SPECIFICATIONS UPON NOTIFICATION OF CONCRETE MIX NON-COMPLIANCE BY THE CONSULTANT TECHNICIAN. THE PROJECT ENGINEER MAY REQUIRE MORE FREQUENT TESTING AS CONDITIONS WARRANT.

UPON COMPLETION OF DAILY CONCRETE PLACEMENT(S), THE CONCRETE CONSULTANT SHALL PROVIDE THE PROJECT ENGINEER WITH DAILY TEST REPORTS, TE-45'S, INSPECTORS DAILY REPORT AND SUPPORTING DOCUMENTATION FOR EACH ITEM OF CONCRETE WORK PERFORMED SEPARATED BY MIX DESIGN. SUBSEQUENTLY, UPON COMPLETION OF AN ENTIRE CONCRETE SPECIFICATION ITEM, THE CONCRETE CONSULTANT SHALL ALSO PROVIDE THE PROJECT ENGINEER WITH TWO (2) COPIES OF AN ADDITIONAL INSPECTION REPORT BY A REGISTERED PROFESSIONAL ENGINEER, STATE OF OHIO. WHICH CONTAINS THE TESTING RESULTS SUMMARY FOR EACH ITEM BY CONTRACT REFERENCE NUMBER AND THE CONSULTANT'S CONCLUSIONS RELATIVE TO SPECIFICATION COMPLIANCE FOR ALL CONCRETE TESTING WORK.

THE ODOT PROJECT ENGINEER RESERVES THE RIGHT TO MAKE UNANNOUNCED QUALITY-CONTROL TESTS TO VERIFY PROCEDURES USED AND RESULTS BEING OBTAINED BY THE CONTRACTOR

THE CONCRETE TECHNICIAN SHALL WORK UNDER THE DIRECTION OF A REGISTERED PROFESSIONAL ENGINEER, STATE OF OHIO, WHO WILL MONITOR THE CONCRETE TEST RESULTS THE FINAL INSPECTION REPORTS FOR EACH COMPLETED ITEM SHALL BE SIGNED BY A REGISTERED PROFESSIONAL ENGINEER. STATE OF OHIO. CERTIFYING THAT ALL CONCRETE TESTS PROVIDED BY THE CONTRACTOR MET APPLICABLE CONTRACT REQUIREMENTS. A FINAL REPORT ISSUED BY THE CONSULTING FIRM SHALL CONTAIN A CERTIFIED STATEMENT OF COMPLIANCE WITH ODOT SPECIFICATIONS AND ANY OTHER CONCLUSIONS REGARDING THE CONCRETE MATERIALS INCORPORATED INTO THE PROJECT. SUCH STATEMENT SHALL BE SIGNED BY A REGISTERED PROFESSIONAL ENGINEER, STATE OF OHIO. AND, THE CONCRETE CONSULTANT SHALL BE REQUIRED TO ATTEND MONTHLY PROGRESS MEETINGS AS REQUIRED BY THE PROJECT ENGINEER.

ADDITIONALLY, THE CONTRACTOR SHALL BE REQUIRED TO KEEP A POSTED LIST OF BEAM AND CYLINDER IDENTIFICATION NUMBERS FOR THE PURPOSE OF IDENTIFYING THE CORRESPONDING PLACEMENT LOCATION AND CONCRETE SPECIFICATION ITEM.

PAYMENT SHALL BE BID AS LUMP SUM FOR ITEM SPECIAL STRUCTURES: CONSULTANT FOR CONCRETE QUALITY CONTROL INCLUDING TESTING AND INSPECTION. THE ITEM WILL BE PAID FOR AS FOLLOWS:

UPON APPROVAL OF CONSULTANT ...... 20% PROGRESSIVE EQUIVALENT PAYMENTS ...... 50% UPON SUBMISSION OF FINAL REPORT ...... 30%

THE TECHNICIAN SHALL HAVE THE FULL EFFECT AND AUTHORITY OF AN ODOT PROJECT INSPECTOR IN DETERMINING ACCEPTABILITY OF MATERIAL AND CONCRETE PLACEMENT PRACTICES.

#### EXISTING STRUCTURE VERIFICATION

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05, 105.02 AND 513.04.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS WHICH HAVE BEEN VERIFIED IN THE FIELD.

#### ITEM 513 - STRUCTURAL STEEL, MISC.: FATIGUE RETROFIT, ULTRASONIC IMPACT TREATMENT (UIT)

THIS ITEM CONSISTS OF NDT (MAG PARTICLE) INSPECTION OF THE EXISTING WELDS AT THE GIRDER TIE PLATE CONNECTIONS TO THE PIER CAP WEBS, PERFORMING ANY NEEDED WELD REPAIRS AND PERFORMING ULTRASONIC IMPACT TREATMENT IN ACCORDANCE WITH THE SPECIAL PROVISION AT THE LOCATIONS SHOWN IN THE PLANS.

#### STRUCTURE CLEANING

ONCE THE BIRD NESTS AND DROPPINGS ARE REMOVED, USE 1,500 PSI MAXIMUM PRESSURE WATER TO REMOVE ANY REMAINING DEBRIS FROM THE STRUCTURAL STEEL AND PROVIDE A CLEAN WORK SURFACE PRIOR TO THE START OF ULTRA SONIC TESTING AND INSPECTION (UTI), CONCRETE BARRIER REHABILITATION AND/OR PAINTING OF STRUCTURAL STEEL. AVOID SKIN CONTACT OR INHALING NEAR DISTURBED NESTS OR DROPPINGS.



CAH | GTF AMS 9/20/23 88679

# HAM-IR 74-11.16

#### PROPOSED WORK

HAM-74-11.16 L/RI-74 OVER HARRISON RD.

SFN's 3108430 + 3108465

- 1. PATCH THE TOP OF BACKWALLS WITH CONCRETE PER PROPOSAL NOTE 512, TYPE B.
- PATCH THE SUBSTRUCTURE WITH 519 PATCHING AND REPLACE DETERIORATED PORTIONS OF THE BARRIER FULL THICKNESS WHERE UNSOUND ON BOTH SIDES. REPAIR/REPLACE ASPHALT OVERLAY ON THE APPROACH SLABS SEE ROADWAY PLANS).
- TREAT ALL WELDS ON/TO THE STEEL PIER CAPS WITH ULTRASONIC IMPACT TREATMENT (UIT).
- PAINT THE STRUCTURAL STEEL PER 514 (OZEU) SPECIFICATIONS, FEDERAL COLOR 14277 (GREEN). THIS INCLUDES ALL STEEL PORTIONS OF THE PIER.
- SEAL THE CONCRETE SURFACES OF THE BARRIERS, ABUTMENTS, AND PIERS WITH EPOXY URETHANE SEALER, FEDERAL COLOR 17778. REMOVE LOOSE AREAS ALONG THE DECK EDGE, UNDER THE BARRIER PRIOR TO SEALING.
- SEAL THE WEARING SURFACE OF THE DECK WITH GRAVITY FED RESIN
- 7. INCREASE THE MEDIAN BARRIER TO 54" PER LRFD REQUIREMENTS FOR NON-REDUNDANT SUBSTRUCTURES. REPAIR THE EROSION BEHIND THE SOUTH/WEST CURB OF HARRISON AVE.

#### HAM-74-1292L/R OVER HAFT RD.

SEN's 3108589 + 3108619

- REPLACE THE EXPANSION JOINT, TOP OF BACKWALL DOWN TO THE APPROACH SLAB SEAT, AND THE ADJACENT 2 FEET OF
- 2. PATCH THE SUBSTRUCTURE WITH 519 PATCHING AND REPLACE DETERIORATED PORTIONS OF THE BARRIER FULL THICKNESS WHERE UNSOUND AS SHOWN IN THE PLANS. REPAIR/REPLACE ASPHALT OVERLAY ON THE APPROACH SLABS SEE ROADWAY PLANS).
- SEAL THE CONCRETE SURFACES OF THE BARRIERS, ABUTMENTS, AND PIERS WITH EPOXY URETHANE SEALER, FEDERAL COLOR 17778
- SEAL THE WEARING SURFACE OF THE DECK WITH GRAVITY FED RESIN.

HAM-74-1618 L/R OVER CR 151 SHEPHERD CREEK RD. SFN's 3108767 + 3108732

- 1. REPLACE THE EXPANSION JOINT, TOP OF BACKWALL DOWN TO THE APPROACH SLAB SEAT, AND THE ADJACENT 2 FEET OF
- PATCH THE SUBSTRUCTURE WITH 519 PATCHING AND 2. REPAIR/REPLACE ASPHALT OVERLAY ON THE APPROACH SLABS (SEE ROADWAY PLANS).
- REPAIR THE SEALER ON THE PATCHED AREAS WITH NEW EPOXY URETHANE SEALER, FEDERAL COLOR 17778.
- SEAL THE WEARING SURFACE OF THE DECK WITH GRAVITY FED RESIN.
- INSTALL NEW CONCRETE BARRIER IN FRONT OF THE PIERS ALONG SHEPHERD CREEK RD.

#### HAM-74-1744 L/R OVER MONTANA AVE.

SFN's: 3115437 + 3115429

- 1. PATCH THE TOP OF BACKWALLS AND CONCRETE AREA OF APPROACH SLAB WITH CONCRETE PER PROPOSAL NOTE 512, TYPE B.
- 2. PATCH THE SUBSTRUCTURE WITH 519 PATCHING. REPAIR/REPLACE ASPHALT OVERLAY ON THE APPROACH SLABS (SEE ROADWAY PLANS).
- SEAL THE WEARING SURFACE OF THE DECK WITH GRAVITY FED RESIN.

#### **ITEM 516 - STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL. AS PER PLAN**

THE CONTRACTOR SHALL FIELD VERIFY THE TOE OF THE EXISTING BARRIERS AT THE EXISTING EXPANSION JOINT AND PROVIDE ELEVATIONS TO THE JOINT FABRICATOR TO CONFIRM THE EXISTING DECK CROSS SLOPE AT EACH JOINT. THE CONTRACTOR SHALL ALSO FIELD VERIFY THE PLAN DIMENSIONS PRIOR TO JOINT FABRICATION. THE CONTRACTOR SHALL ALSO FIELD VERIFY THE EXISTING END CROSS FRAMES AND PROVIDE GUSSET PLATES (AND FILL PLATES AS NEEDED) TO ENSURE PROPER FIT-UP BETWEEN THE NEW EXPANSION JOINT AND EXISTING END CROSS FRAMES. IF UPON FIELD VERIFICATION, THE DIMENSIONS VARY FROM WHAT IS SHOWN. THE JOINT SHALL MATCH THE INFORMATION FOUND IN THE FIELD. ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO FIELD VERIFY THE EXISTING EXPANSION JOINT AND END CROSS FRAMES SHALL BE INCLUDED IN PAY ITEM 516 - STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN FOR PAYMENT

ITEM 510 - DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN

INSTALL ADHESIVE ANCHORS ACCORDING TO THE MANUFACTURER'S INSTALLATION INSTRUCTIONS PUBLISHED IN THE ICC-ES REPORTS LISTED BELOW.

#### WWW.ICC-ES.ORG/EVALUATION REPORTS/

THE HOLES FOR THE ADHESIVE ANCHORS SHALL BE DRILLED WITH A HAMMER DRILL AND CARBIDE BIT. PRIOR TO THE INSTALLATION OF THE ANCHORS, THE HOLES SHALL BE CLEANED AND DRIED IN A MANNER CONSISTENT WITH THE MANUFACTURER'S REQUIREMENTS FOR DRY CONCRETE.

SELECT FROM ONE OF THE FOLLOWING APPROVED PRODUCTS:

HILTI HIT-HY 200 ADHESIVE ANCHORS ICC-ES REPORT ESR-3187)

DEWALT PURE110+ EPOXY ADHESIVE ANCHOR SYSTEM (ICC-ES REPORT ESR-3298)


SIMPSON STRONG-TIE SET-3G EPOXY ADHESIVE ANCHORS ICC-ES REPORT ESR-4057)

ATC ULTRABOND HS-1CC ADHESIVE ANCHOR SYSTEM (ICC-ES REPORT ESR-4094)





AMS 9/20/23 88679



				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1116L		(100%	% 02/IMS/13 FUNDING	)	
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14
509	26000	5051	LB	GALVANIZED STEEL REINFORCMENT				5051	
511	53010	109	CY	CLASS QC1 CONCRETE, MISC.: CONCRETE MEDIAN BARRIER				109	20
512	10100	1353	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	152	465	349	387	
512	10600	8	FT	CONCRETE REPAIR BY EPOXY INJECTION	8				
512	73500	1788	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			1788		
512	74000	5.5	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	5.5				
513	95020	LS	LUMP	STRUCTURAL STEEL, MISC.: ULTRASONIC IMPACT TREATMENT (UIT)		LUMP			14
513	95020	LS	LUMP	STRUCTURAL STEEL, MISC.: STEEL RETROFIT		LUMP			
514	00050	31694	SF	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL		1404	30290		
514	00056	31694	SF	FIELD PAINTING EXISTING STRUCTURAL STEEL, PRIME COAT		1404	30290		
514	00060	31694	SF	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT		1404	30290		
514	00066	31694	SF	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT		1404	30290		
514	00504	51	MNHR	GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL		11	40		
514	10000	27	EACH	FINAL INSPECTION REPAIR		1	26		
516	13200	184	SF	PREFORMED EXPANSION JOINT FILLER				184	
519	11100	25	SF	PATCHING CONCRETE STRUCTURE	25				
519	12300	24	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	24				
530	00200	LS	LUMP	STRUCTURE CLEANING			LUMP		
530	00200	LS	LUMP	SPECIAL - STRUCTURES: CONSULTANT FOR CONCRETE QUALTY CONTROL INCLUDING TESTING AND INSPECTION			LUMP		14

				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1116R	(100% 02/IMS/13 FUNDING)				
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14
511	34410	1	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE			1		
512	10100	652	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	102	280	270		
512	73500	842	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			842		
513	95020	LS	LUMP	STRUCTURAL STEEL, MISC.: ULTRASONIC IMPACT TREATMENT (UIT)				LUMP	14
514	00050	15618	SF	SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL		1014	14604		
514	00056	15618	SF	FIELD PAINTING EXISTING STRUCTURAL STEEL, PRIME COAT		1014	14604		
514	00060	15618	SF	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT		1014	14604		
514	00066	15618	SF	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT		1014	14604		
514	00504	27	MNHR	GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL		4	23		
514	10000	14	EACH	FINAL INSPECTION REPAIR		1	13		
519	11100	34	SF	PATCHING CONCRETE STRUCTURE			34		
519	12300	14	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	14				
530	00200	LS	LUMP	STRUCTURE CLEANING			LUMP		
530	00200	LS	LUMP	SPECIAL - STRUCTURES: CONSULTANT FOR CONCRETE QUALTY CONTROL INCLUDING TESTING AND INSPECTION			LUMP		14

				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1292L		(100%	02/IMS/13 FUNDING	)	
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14
509	26000	2167	LB	GALVANIZED STEEL REINFORCMENT	1078		1089		
511	34410	19	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	13		6		
512	10100	34	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	19		15		
512	73500	698	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			698		
512	74000	5	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES			5		
516	11210	92	FT	STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN			92		
519	11100	1.5	SF	PATCHING CONCRETE STRUCTURE	1.5				

•			•	ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1292R	(100% 02/IMS/13 FUNDING)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF				
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14				
509	26000	2167	LB	GALVANIZED STEEL REINFORCMENT	1078		1089						
511	34410	33	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	13		20						
512	10100	34	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	19		15						
512	73500	812	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			812						
512	74000	5	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES			5						
516	11210	92	FT	STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN			92						

# STRUCTURE QUANTITIES - 1 BRIDGE No.: VARIES

VARIES DESIGN AGENCY



DESIGNER CHECKER
CAH GTF
REVIEWER
AMS 9/20/23
PROJECT ID
88679
SUBSET TOTAL
1 2
SHEET TOTAL
19 53

	9670\400 Engineers
PM USER jdavis4	Olastication Hondie
4 TIME: 1:34:25	Od Aptino Brainotti
	-and-03/Documents
L: Sheet PAPERSIZE: 17x11 (in.)	Popular man value
EL: Sheet	hodot nur

				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1618L	ES - STRUCTURE No.: HAM-74-1618L (100% 02/IMS/13 FUNDING)						
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.		
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14		
509	26000	2693	LB	GALVANIZED STEEL REINFORCMENT	1329		1364				
511	34410	24	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	16		8				
512	10100	37	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	22		15				
512	73500	1038	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			1,038				
512	74000	5	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES			5				
516	11210	117	FT	STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN			117				
519	11100	30	SF	PATCHING CONCRETE STRUCTURE	30						
519	12300	16	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	16						


				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1618R	(100% 02/IMS/13 FUNDING)						
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.		
202	11203	LS	LUMP	PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LUMP	LUMP	LUMP		14		
509	26000	2129	LB	GALVANIZED STEEL REINFORCMENT	1072		1057				
511	34410	18	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	12		6				
512	10100	34	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	19		15				
512	73500	583	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			583				
512	74000	5	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES			5				
516	11210	92	FT	STRUCTURAL EXPANSION JOINT INCLUDING ELASTOMERIC STRIP SEAL, AS PER PLAN			92				
519	11100	6	SF	PATCHING CONCRETE STRUCTURE	6						
519	12300	12	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	12						


		•		ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1744L		(100% 02/IMS/13 FUNDING)						
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.			
512	10100	5	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	4	1						
512	73500	876	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			876					
519	11100	13	SF	PATCHING CONCRETE STRUCTURE	12	1						
519	12300	13	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	13							

				ESTIMATED QUANTITIES - STRUCTURE No.: HAM-74-1744R	(100% 02/IMS/13 FUNDING)							
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENT	PIERS	SUPERSTRUCTURE	GENERAL	SHT. REF.			
512	10100	7	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	7							
512	73500	864	SY	TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RESIN			864					
519	11100	21	SF	PATCHING CONCRETE STRUCTURE	21							
519	12300	13	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B	13							




DESIGNER CAH	CHECKER GTF
REVIE	WER
AMS 9	9/20/23
88679	
SUBSET 2	TOTAL 2
SHEET 20	TOTAL 53





MICROFILMEL

FEB 2 6 1988



PATCH CONCRETE PER CMS 519 TOTAL PATCH QTY = 2 SF \* 1.50 = 3 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

A544

K- 4537

- PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. REPAIR LEFT BRIDGE TOP OF BACK WALLS TO ESTABLISH A UNIFORM 1'-3" WIDTH.
- TOTAL REPAIR AREA AT TOP OF LEFT BRIDGE REAR ABUTMENT BACK WALL = 85.6 FT x 1.25 FT = 107 SF/9 = 12 SY TOTAL REPAIR AREA AT TOP OF LEFT BRIDGE FORWARD ABUTMENT BACK WALL = 83.4 FT \* 1.25 FT = 104 SF/9 = 12 SY

4. REPAIR RIGHT BRIDGE TOP OF BACK WALLS IN A SIMILAR MANNER (NOT SHOWN) TOTAL REPAIR AREA AT TOP OF RIGHT BRIDGE REAR ABUTMENT BACK WALL = 46.9 FT \* 1.25 FT = 59 SF/9 = 7 SY TOTAL REPAIR AREA AT TOP OF RIGHT BRIDGE FORWARD ABUTMENT BACK WALL = 46.9 FT \* 1.25 FT = 59 SF/9 = 7 SY REAR ABUTMENT REHAB DETAILS BRIDGE No.: HAM-74-11.16L IR 74 OVER HARRISON AVE.

FED. RD. DIVISION

STATE


2 OHIO

353

3108430



CAH GTF AMS 9/20/23 88679 3 10 TOTAL 53 23



PATCH CONCRETE PER CMS 519
TOTAL PATCH QTY = 25 SF \* 1.50 = 37.5 SF
QUANTITY HAS BEEN INCREASED BY 50%
TO ACCOUNT FOR ADDITIONAL DETERIORATION
PRIOR TO CONSTRUCTION.

- 2. PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. SEE SHEET 21 FOR ADDITIONAL NOTES.

FORWARD ABUTMENT PLAN BRIDGE No: HAM-74-11.16L IR 74 OVER HARRISON AVE.

3108430



CAH GTF AMS 9/20/23 88679 4 10 TOTAL 53 24


PIER REHAB DETAILS - 1 BRIDGE No.: HAM-74-11.16L IR 74 OVER HARRISON AVE.


3108430



CAH GTF AMS 9/20/23 88679 SHEET 25


- 3. PERFORM ULTRASONIC TESTING AND INSPECTION (UTI) ON ALL STEEL PIER CAP WELDS INCLUDING STIFFENERS, BEARINGS, MOMENT PLATES, BEAM TO PIER CAP CONNECTIONS, ETC.
- 4. THE CONTRACTOR SHALL BE AWARE OF BIRDS NESTS AND DROPPINGS LOCATED IN CONFINED SPACES OF THE PIER CAP. THE CONTRACTOR SHALL REMOVE INACTIVE BIRDS NESTS AND DROPPINGS AND CLEAN AFFECTED STEEL SURFACES WITH WATER (1,500 PSI MINIMUM WATER PRESSURE) PRIOR TO PERFORMING UTI AND STRUCTURE PAINTING.





SECTION A-A

RETROFIT DETAIL



#### NOTES:

- 1. DETAILS ON THIS SHEET ARE TAKEN FROM EXISTING PLANS AND SHOULD BE USED FOR INFORMATION PURPOSES ONLY.
- 2. PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3, PERFORM ULTRASONIC TESTING AN INSPECTION (UTI) ON ALL STEEL PIER CAP WELDS INCLUDING STIFFENERS, BEARINGS, MOMENT PLATES, BEAM TO PIER CAP CONNECTIONS, ETC.
- 4. THE CONTRACTOR SHALL BE AWARE OF BIRDS NESTS AND DROPPINGS LOCATED IN CONFINED SPACES OF THE PIER CAP. THE CONTRACTOR SHALL REMOVE INACTIVE BIRDS NESTS AND DROPPINGS AND CLEAN AFFECTED STEEL SURFACES WITH WATER (1,500 PSI MINIMUM WATER PRESSURE) PRIOR TO PERFORMING UTI AND STRUCTURE PAINTING.
- 5. FOR RETROFIT, CUT STRINGER WEBS WITH GRINDING WHEEL OR AIR ARC CUTTER. DO NOT USE A TORCH OR PLASMA CUTTER. PROVIDE CUTTING METHOD AND TOOLS TO BE USED TO THE ENGINEER FOR APPROVAL PRIOR TO STARTING WORK. TOP FLANGE OF THE PIER CAP AND CUT SURFACES OF THE STINGER WEBS SHALL BE GROUND SMOOTH.
- 6. BEAM RETROFIT, GRINDING AND WELD REMOVAL SHALL BE INCLUDED WITH ITEM 513 STRUCTURAL STEEL, MISC.; STEEL RETROFIT FOR PAYMENT.
- 7. REMOVAL OF CONSTRUCTION DEBRIS, BIRD NESTS AND DROPPINGS SHALL BE INCLUDED WITH ITEM 202 PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN FOR PAYMENT.

3108430 DESIGN AGENCY

PIER REHAB DETAILS - 2 BRIDGE No.: HAM-74-11.16L IR 74 OVER HARRISON AVE.



DESIGNER CHECKER
CAH GTF

REVIEWER
AMS 9/20/23
PROJECT ID
88679
SUBSET TOTAL
6 10
SHEET TOTAL
26 53

HAM-IR 74-11.16


HAM-IR 74-11.16

- DETAILS ON THIS SHEET ARE TAKEN FROM EXISTING PLANS AND SHOULD BE USED FOR INFORMATION PURPOSES ONLY.
- 2. PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3.PAINT THE STRUCTURAL STEEL PER 5144OZEU), FEDERAL COLOR 14277 (GREEN). THIS INCLUDES ALL STEEL PORTIONS OF THE PIER

FRAMING PLAN BRIDGE No.: HAM-74-11.16R IR 74 OVER HARRISON AVE.

3108465





4242

MICROPILMEL

74-11 16

HAM-IR


- 1. DETAILS ON THIS SHEET ARE TAKEN FROM EXISTING PLANS AND SHOULD BE USED FOR INFORMATION PURPOSES ONLY.
- 2. PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. PAINT ALL STRUCTURAL STEEL INCLUDING BEARINGS AND PIERS PER CMS 514, FEDERAL COLOR 14277 (GREEN).

BRIDGE No.: HAM-74-11.16L IR 74 OVER HARRISON AVE **FRAMING PLAN** 

3108430



CAH GTF AMS 9/20/23 88679 8 10 53 28




- 1. DETAILS ON THIS SHEET ARE TAKEN FROM EXISTING PLANS AND SHOULD BE USED FOR INFORMATION PURPOSES ONLY.
- 2. PERFORM ONLY THE WORK INDTCATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- BEARINGS, MOMENT PLATES, BEAM TO PIER CAP CONNECTIONS, ETC.
- 4. THE CONTRACTOR SHALL BE AWARE OF BIRDS NESTS AND DROPPINGS LOCATED IN CONFINED SPACES OF THE PIER CAP THE CONTRACTOR SHALL REMOVE INACTIVE BIRDS NESTS AND DROPPINGS AND CLEAN AFFECTED STEEL SURFACES WITH WATER (1,500 PSI MINIMUM WATER PRESSURE) PRIOR TO PERFORMING UTI AND STRUCTURE PAINTING.

PIER REHAB DETAILS - 3 BRIDGE No.: HAM-74-11.16R IR 74 OVER HARRISON AVE.

3108465



CAH GTF AMS 9/20/23 88679 TOTAL 53 SHEET 29




PARAPET REPAIR DETAILS BRIDGE No.: HAM-74-11.16R IIR 74 OVER HARRISON AVE.

3108465





30



PHASE CONSTRUCTION BRIDGE No.: HAM-74-12.92 L/R I-74 OVER HAFT RD.


- 1. REMOVE 2'-0" OF DECK/PARAPETS AND ABUTMENT BACKWALLS AT EACH END OF BRIDGE TO ACCOMMODATE REPLACEMENT OF THE EXPANSION JOINTS.
- 2. SEAL DECK IN EACH PHASE WITH GRAVITY FED RESIN.
- 3. EXISTING STRUCTURAL STEEL SHALL REMAIN IN SERVICE.
- 4. RIGHT BRIDGE SHOWN. LEFT BRIDGE SYMMETRIC ABOUT € 1-74.
- 5. PCB MOVED FROM SHOULDER INTO THE LANE AND BACK TO THE SHOULDER DURING THE WEEKEND LANE CLOSURE IS INCIDENTAL TO LUMP SUM MOT.
- 6. CONTRACTOR MAY USE DRUMS OR PCB DURING WEEKEND LANE CLOSURE.
- 7. PROVIDE TEMPORARY SHORING AS NEEDED FOR DECK. COST FOR BOND BREAKER AND SHORING SHALL BE INCIDENTAL TO THE 511 CONCRETE.

3108589 SFN 3108619 DESIGN AGENCY



DESIGNER CHECKER
CAH GTF

REVIEWER
AMS 9/20/23
PROJECT ID
88679
SUBSET TOTAL
2 8
SHEET TOTAL
32 53



- INFORMATION PURPOSES ONLY.
- 2. PERFORM ONLY THE WORK INDICATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. TOTAL CONCRETE PATCHING QUANTITY = 1 SF \* 1.50 = 1.5 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

HAM-IR 74-11.16

#### **LEGEND**

PATCHING STRUCTURE CONCRETE PER CMS 519

3108589

BRIDGE REAR ABUTMENT BRIDGE No.: HAM-74-12.92 I I-74 OVER HAFT RD.




AMS 9/20/23 88679 3 SHEET 1




4 TOTAL 53 34


5. INCORPORATE EXISTING WING WALL REBAR INTO NEW CONCRETE. DO NOT CUT.









REAR ABUTMENT SHOWN FORWARD ABUTMENT SIMILAR





ARMOR SPLICE DETAIL

#### STRIP SEAL EXPANSION JOINT SPLICE DETAIL




VIEW X-X DECK SLAB SUPPORT ARMOR SPLICE DETAIL

# **EXPANSION JOINT GLAND DIMENSION 'A'**

	LT REAR	LT FWD	RT REAR	RT FWD
30°	2.30"	2.37"	2.31"	2.39"
40°	2.27"	2.29"	2.27"	2.30"
50°	2.23"	2.21"	2.23"	2.20"
60°	2.20"	2.13"	2.19"	2.11"
70°	2.17"	2.05"	2.15"	2.02"
80°	2.14"	1.97"	2.11"	1.93"
90°	2.10"	1.89"	2.07"	1.84"

MINIMUM JOINT OPENING (DIMENSION 'A') AT THE TIME OF 3" SEAL GLAND INSTALLATION SHALL NOT BE LESS THAN 1 5/8". IF THE JOINT OPENING IS LESS, INSTALLATION SHALL BE POSTPONED UNTIL THE TEMPERATURE DROPS A SUFFICIENT AMOUNT TO ALLOW THE




## **ELASTOMERIC STRIP SEAL JOINT SECTION**

TYPICAL THRU DECK SLAB

FROM STANDARD DRAWING EXJ-4-87

## **LEGEND**

CP = COMPLETE PENETRATION FIELD WELD, GRIND SMOOTH



# STRIP SEAL EXPANSION JOINT DETAILS

▲ - 0" MIN. TO ½" MAX. AT BREAKPOINT IN RETAINER FOR SQUARE BRIDGES. ON SKEWED BRIDGES THIS DIMENSION WILL ONLY APPLY TO THE SIDE OF JOINT ASSEMBLY WHICH IS NEAREST TO THE CURB LINE (SEE SHEET 2 OF 5 ON STD. DWG. EXJ-4-87).


#### NOTES:

1. DUE TO THE CLOSE PROXIMITY OF THE PHASE ONE CONCRETE POUR TO THE EXISTING PHASE 2 DECK, THE CONTRACTOR SHALL TAKE STEPS AS NEEDED (i.e. EXTRA CONCRETE REMOVAL/PLACEMENT, ETC.) TO ACCOMMODATE THE PLACEMENT AND PROTECTION OF THE BOLTED 6"x6"x3/8" EXPANSION JOINT PLATE. COST FOR THIS ADDITIONAL WORK SHALL BE INCIDENTAL TO THE EXPANSION JOINT.

3108589 3108619



DESIGNER	CHECKE
CAH	GTF
REVI	EWER
AS MI	M-DD-Y
PROJECT ID	
886	379
SUBSET	TOTAL
6	8
SHEET	TOTAL



3. TOTAL 511 CONCRETE = 153' x 1'x1'x(1/27) = 5.7 CY


BRIDGE SUPERSTRUCTURE DETAILS BRIDGE No.: HAM-74-12.92 L/R I-74 OVER HAFT RD.

37 TOTAL 53

DATE: 2/1/2024 TIME: 1:35:45 PM USER: jdav	\Documents\01 Active Projects\District 08\Hamil
MODEL: Sheet PAPERSIZE: 17x11 (in.) I	pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\D

MARK	NUMBER	LENGTH	WEIGHT	TYPE	DIMENSIONS									
	TOTAL			r	Α	В	С	D	E	R	INC			
	LEFT	BRIDGE	E - SUPE	RST	RUCT	JRE RE	INFOR	CING S	TEEL LI	ST				
S501	32	3'-7"	120	1	3'-1"	0'-8"								
S502	188	2'-7"	507	STR										
S601	6	20'-7"	185	STR										
S602	6	24'-11"	225	STR										
S701	6	20'-7"	252	STR										
S702	6	24'-11"	306	STR										
	S	UB-TOTAL	1,595											
	RIGH <sup>*</sup>	T BRIDG	E - SUPI	ERS	TRUCT	URE RE	EINFOR	CING S	TEEL L	IST				
S501	32	3'-7"	120	1	3'-1"	0'-8"								
S502	188	2'-7"	507	STR										
S601	6	20'-7"	185	STR										
S602	6	24'-11"	225	STR										
S701	6	20'-7"	252	STR										
S702	6	24'-11"	306	STR										
	S	UB-TOTAL	1,595											

	NUMBER					ш			DIMENSIONS					
MARK	REAR ABUT.	FWD. ABUT.	TOTAL	LENGTH	WEIGHT	TYPE	Α	В	С	D	E	R	INC	
			FFT BR	IDGE - A	BUTMEN	JT R	FINFO	RCING	STEFL	IST				
A501	2	2	4	7'-11"	33	STR								
A502	2	2	4	12'-10"	54	STR								
A503	2	2	4	21'-5"	89	STR								
A504	2	2	4	25'-10"	108	STR								
A505	8	8	16	4'-0"	67	1	3'-6"	0'-8"						
A506	16	16	32	1'-5"	47	STR								
A507	1	1	2	21'-9"	45	STR								
A508	1	1	2	25'-6"	53	STR								
, 1000			<u>-</u>											
A601	32	32	64	2'-2"	208	STR								
A602	15	15	30	4'-3"	192	2	1'-0"	1'-5"	2'-2"					
A603	17	17	34	3'-9"	192	2	1'-0"	0'-11"	2'-2"					
	1		S	UB-TOTAL	1,088	<u> </u>			ı		1	1	-	
		F	RIGHT BE	RIDGE - /	ABUTME	NT F	RFINEC	RCING	STFFI	LIST				
A501	2	2	4	7'-11"	33	STR			<u> </u>					
A502	2	2	4	12'-10"	54	STR								
A503	2	2	4	21'-5"	89	STR								
A504	2	2	4	25'-10"	108	STR								
A505	8	8	16	4'-0"	67	1	3'-6"	0'-8"						
A506	16	16	32	1'-5"	47	STR								
A507	1	1	2	21'-9"	45	STR								
A508	1	1	2	25'-6"	53	STR								
A601	32	32	64	2'-2"	208	STR								
A602	15	15	30	4'-3"	192	2	1'-0"	1'-5"	2'-2"					
A603	17	17	34	3'-9"	192	2	1'-0"	0'-11"	2'-2"					
	1		S	UB-TOTAL	1,088						1	1		



# REBAR BEND DIAGRAMS

## NOTES:

- 1. ALL DIMENSIONS ARE OUT TO OUT OF BAR
- 2. DIMENSIONS ON HOOKS TO BE SHOWN ONLY WHERE NECESSARY TO RESTRICT HOOK SIZE. OTHERWISE STANDARD HOOKS ARE TO BE USED. REFERENCE CMS 509.
- 3. ALL REINFORCING STEEL CLEARANCES ARE 2" UNLESS OTHERWISE NOTED.


- ALL REBAR SHALL BE BLACK BARS UNLESS NOTED
- 5. BLACK REBAR DOWELS SHALL BE USED TO OBTAIN PROPER BOND WHEN USING CMS 510 GROUT WITH SHALLOW EMBEDMENT DECK DOWELS.
- 6. PROVIDE THREADED "FORM SAVER" TYPE MECHANICAL CONNECTORS. CONTRACTOR SHALL ADJUST THE PROVIDED REBAR LENGTHS AS REQUIRED FOR MECANICAL CONNECTOR USAGE.




3108589 3108619



DESIGNER CHECKER
CAH GTF AMS 9/20/23 88679 SHEET TOTAL 38 53





PHASE CONSTRUCTION - 2 BRIDGE No: HAM-74-16.18R I-74 OVER SHEPHERD CREEK RD.

SFN 3108732 SFN 3108767

DESIGN AGENCY



DESIGNER CHECKER
CAH GTF
REVIEWER
AMS 9/20/23
PROJECT ID
88679
SUBSET TOTAL

HEET TOTAL 53

HAM-IR 74-11.16

RD

BRIDGE REAR ABUTMENT BRIDGE No. HAM-74-16.18L OVER SHEPHERD CREEK

**I-74** 

3108732 DESIGN AGENCY



DESIGNER CHECKER
CAH GTF

REVIEWER
AMS 9/20/23


PROJECT ID
88679

SUBSET TOTAL
4 11

SHEET TOTAL
42 53

PATCHING STRUCTURE CONCRETE PER CMS 519

- 2. PERFORM ONLY THE WORK INDICATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. TOTAL CONCRETE PATCHING QUANTITY = 24 SF \* 1.50 = 36 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.



DESCRIBED IN THE GENERAL NOTES.

3. TOTAL CONCRETE PATCHING QUANTITY = 6 SF \* 1.50 = 9 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR

ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

HAM-IR 74-11.16

BRIDGE FORWARD ABUTMENT BRIDGE No: HAM-74-16.18L I-74 OVER SHEPHERD CREEK RI

3108732 DESIGN AGENCY



DESIGNER CHECKER
CAH GTF


REVIEWER
AMS 9/20/23

PROJECT ID
88679

SUBSET TOTAL
5 11

SHEET TOTAL
43 53

PATCHING STRUCTURE CONCRETE PER CMS 519



BRIDGE FORWARD ABUTMENT BRIDGE No: HAM-74-16.18R I-74 OVER SHEPHERD CREEK RD


3108767





CAH GTF AMS 9/20/23 88679 6 SHEET TOTAL 44 53


PATCHING STRUCTURE CONCRETE PER CMS 519

- 2. PERFORM ONLY THE WORK INDICATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. TOTAL CONCRETE PATCHING QUANTITY = 6 SF \* 1.50 = 9 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.











₽ %"x6"x6" L7"x4"x1/2" ⊈ SPLICE -**6**+6 1½" 6" 45<sup>33</sup>/<sub>64</sub> VIEW Y-Y



ABUTMENT SIDE SUPPORT

#### STRIP SEAL EXPANSION JOINT SPLICE DETAIL




# VIEW X-X

DECK SLAB SUPPORT ARMOR SPLICE DETAIL

EXF		N JOINT NSION		)							
	LT   RT   RT   RT   RT   RT   RT   RT										
30°	2.38"	2.31"	2.35"	2.29"							
40°	2.29"	2.27"	2.28"	2.26"							
50°	2.21"	2.23"	2.22"	2.24"							
60°	2.12"	2.19"	2.15"	2.21"							
70°	2.03"	2.15"	2.08"	2.18"							
80°	1.95"	2.12"	2.02"	2.15"							
90°	1.86"	2.08"	1.95"	2.12"							

MINIMUM JOINT OPENING (DIMENSION 'A') AT THE TIME OF 3" SEAL GLAND INSTALLATION SHALL NOT BE LESS THAN 2". IF THE JOINT OPENING IS LESS, INSTALLATION SHALL BE POSTPONED UNTIL THE TEMPERATURE DROPS A SUFFICIENT AMOUNT TO ALLOW THE 2" OPENING.




## **ELASTOMERIC STRIP SEAL JOINT SECTION**

TYPICAL THRU DECK SLAB

## **LEGEND**

CP = COMPLETE PENETRATION FIELD WELD, GRIND SMOOTH



## STRIP SEAL EXPANSION JOINT DETAILS

▲ - 0" MIN. TO ½" MAX. AT BREAKPOINT IN RETAINER FOR SQUARE BRIDGES. ON SKEWED BRIDGES THIS DIMENSION WILL ONLY APPLY TO THE SIDE OF JOINT ASSEMBLY WHICH IS NEAREST TO THE CURB LINE (SEE SHEET 2 OF 5 ON STD. DWG. EXJ-4-87).

## NOTES:

1. DUE TO THE CLOSE PROXIMITY OF THE PHASE ONE CONCRETE POUR TO THE EXISTING PHASE 2 DECK, THE CONTRACTOR SHALL TAKE STEPS AS NEEDED (i.e. EXTRA CONCRETE REMOVAL/PLACEMENT, ETC.) TO ACCOMMODATE THE PLACEMENT AND PROTECTION OF THE BOLTED 6"x6"x3/8" EXPANSION JOINT PLATE. COST FOR THIS ADDITIONAL WORK SHALL BE INCIDENTAL TO THE EXPANSION JOINT.

3108589 3108619

EXPANSION JOINT DETAILS BRIDGE No.: HAM-74-16.88 L/R I-74 OVER SHEPHERD CREEK RD.




CHECKE
GTF
WER
И-DD-Y
679
TOTAL
11
TOTAL
53

	DIMENSIONS					
) E	F					
S STEEL	LIST					
G STEEL	LIST					

INC

	NUMBER					ш	DIMENSIONS						
MARK	REAR ABUT.	FWD. ABUT.	TOTAL	LENGTH	WEIGHT	TYPE	Α	В	С	D	E	R	INC
			LEFT BR	IDGE - A	BUTMEN	NT R	EINFO	RCING :	STEEL	LIST			
A501	2	2	4	7'-11"	33	STR							
A502	2	2	4	12'-9"	53	STR							
A503	2	2	4	21'-3"	89	STR							
A504	2	2	4	38'-9"	162	STR							
A505	8	8	16	4'-0"	67	1	3'-6"	0'-8"					
A506	16	16	32	1'-5"	47	STR							
A507	1	1	2	21'-7"	45	STR							
A508	1	1	2	58'-5"	122	STR							
A601	41	41	82	2'-2"	267	STR							
A602	15	15	30	4'-3"	192	2	1'-0"	1'-5"	2'-2"				
A603	26	26	52	3'-9"	293	STR							
			5	UB-TOTAL	1,370			1	l.			-	
		F	RIGHT BI	RIDGE - /	ABUTME	NT F	REINEC	RCING	STEFL	LIST			
A501	2	2	4	11'-9"	49	STR	<u></u>		<u> </u>				
A502	2	2	4	8'-0"	33	STR							
A503	2	2	4	24'-9"	103	STR							
A504	2	2	4	20'-8"	86	STR							
A505	8	8	16	4'-0"	67	1	3'-6"	0'-8"					
A506	16	16	32	1'-5"	47	STR							
A507	1	1	2	25'-0"	52	STR							
A508	1	1	2	20'-5"	43	STR							
A601	31	31	62	2'-2"	202	STR							
A602	14	14	28	4'-3"	179	2	1'-0"	1'-5"	2'-2"				
A603	17	17	34	3'-9"	192	2	1'-0"	0'-11"	2'-2"				
			·	UB-TOTAL	1.053	Ι '							-



# REBAR BEND DIAGRAMS

## NOTES:

- 1. ALL DIMENSIONS ARE OUT TO OUT OF BAR
- 2. DIMENSIONS ON HOOKS TO BE SHOWN ONLY WHERE NECESSARY TO RESTRICT HOOK SIZE. OTHERWISE STANDARD HOOKS ARE TO BE USED. REFERENCE CMS 509.
- 3. ALL REINFORCING STEEL CLEARANCES ARE 2" UNLESS OTHERWISE NOTED.

- 4. ALL REBAR SHALL BE BLACK BARS UNLESS NOTED OTHERWISE.
- 5. BLACK REBAR DOWELS SHALL BE USED TO OBTAIN PROPER BOND WHEN USING CMS 510 GROUT WITH SHALLOW EMBEDMENT DECK DOWELS.
- 6. PROVIDE THREADED "FORM SAVER" TYPE MECHANICAL CONNECTORS. CONTRACTOR SHALL ADJUST THE PROVIDED REBAR LENGTHS AS REQUIRED FOR MECANICAL CONNECTOR USAGE.



SFN 3108732 SFN 3108767



DESIGNER CHECKER
CAH GTF

REVIEWER
AMS 9/20/23
PROJECT ID
88679
SUBSET TOTAL
11 11
SHEET TOTAL
49 53

QUANTITIES.

431 Wout to our

LONGITUDE W84°34'05.0"

50 53

5. PN 512, TYPE 'B' CONC. PATCHING = 26.2' \* 1.25'\*(1/9) \* 1.50 = 5.5 SY

QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR

ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

DESCRIBED IN THE GENERAL NOTES.

3. TOTAL CONCRETE PATCHING QUANTITY = 12 SF \* 1.50 = 18 SF

QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR

ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

BRIDGE FORWARD ABUTMENT BRIDGE No.: HAM-74-17.44L I-74 OVER MONTANA AVE.

3115429



AMS 9/20/23 88679 2 HEET TOTAL 53

PATCHING STRUCTURE CONCRETE PER PN 512 TYPE 'B'.

BRIDGE PIERS BRIDGE No.: HAM-74-17.44L I-74 OVER MONTANA AVE.

P503

P/104-

P501-1 P507-

5" 9" 4" 1"9" 5"

-P501-

P602 -

SECTION G-G

VOGT, IVERS, & ASSOCIATES 7/10

TRACED CHECKED REVIEWED DATE

RK. H.D.J. 10-17-69

**DIER 1 \$ 2** 

BRIDGE NO. HAM-74-1755 L

PATCHING STRUCTURE CONCRETE PER CMS 519

W.B. I -74

9" 6" 6" 9

SECTION C-C SECTION D-D

- P1104

-2501

-P507

01104

9" 6" 6" 9"

3115429




CAH GTF AMS 9/20/23 88679 3 4

52 TOTAL 53

TOTAL SEALING AREA = 1 SY TOTAL SEALING REMOVAL AREA (BEYOND PATCH AREA) = 1 SY

- 2. PERFORM ONLY THE WORK INDICATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. TOTAL CONCRETE PATCHING QUANTITY = 1 SF \* 1.50 = 1.5 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.



HAM-IR 74-11.16

- 2. PERFORM ONLY THE WORK INDICATED IN THE FRAMED TEXT AND/OR DESCRIBED IN THE GENERAL NOTES.
- 3. TOTAL 519 CONCRETE PATCHING QUANTITY = 21 SF \* 1.50 = 32 SF QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.

- TOTAL SEALING REMOVAL AREA = 5 SY
- 5. PN 512, TYPE 'B' CONC. PATCHING = 26.2' \* 1.25'\*(1/9) \* 1.50 = 5.5 SY QUANTITY HAS BEEN INCREASED BY 50% TO ACCOUNT FOR ADDITIONAL DETERIORATION PRIOR TO CONSTRUCTION.



PATCHING STRUCTURE CONCRETE PER CMS 519



PATCHING STRUCTURE CONCRETE PER PN 512, TYPE 'B'.

CAH GTF AMS 9/20/23 88679 4 4 HEET TOTAL 53

3115437

BRIDGE FORWARD ABUTMENT BRIDGE No.: HAM-74-17.44R I-74 OVER MONTANA AVE.