

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 1

Floor Beam Spacing 23.91

Comments:

Member I. D. B01 Symmetry:

Span Length:	Span 1	Span 2	Span 3	Span 4	Span 5
	38.833	0.000	0.000	0.000	0.000

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	1.22	HS 24.37	43.9
1.474	OPER.	5C1T	2.62	0.00	209.4
-1.000	POST.		999.00	0.00	0.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
-1.000	INV.	HS20	999.00	999.00	HS 0.00	0.00
-1.000	OPER.	5C1T	999.00	999.00	0.00	0.00
-1.000	POST.		999.00	999.00	0.00	0.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	1.27	HS 25.51	45.9
1.474	OPER.	5C1T	2.74	0.00	219.1
-1.000	POST.		999.00	0.00	0.0

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 1

Floor Beam Spacing 23.91

Comments:

Member I. D. B02 Symmetry:

Span Length:	Span 1	Span 2	Span 3	Span 4	Span 5
	38.833	0.000	0.000	0.000	0.000

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	1.09	HS 21.83	39.3
1.474	OPER.	5C1T	2.34	0.00	187.5
-1.000	POST.		999.00	0.00	0.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
-1.000	INV.	HS20	999.00	999.00	HS 0.00	0.00
-1.000	OPER.	5C1T	999.00	999.00	0.00	0.00
-1.000	POST.		999.00	999.00	0.00	0.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	1.15	HS 23.06	41.5
1.474	OPER.	5C1T	2.48	0.00	198.1
-1.000	POST.		999.00	0.00	0.0

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 1

Floor Beam Spacing 23.91

Comments:

Member I. D. B03 Symmetry:

Span Length:	Span 1	Span 2	Span 3	Span 4	Span 5
	38.833	0.000	0.000	0.000	0.000

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	0.96	HS 19.13	34.4
1.474	OPER.	5C1T	2.09	0.00	166.8
-1.000	POST.		999.00	0.00	0.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
-1.000	INV.	HS20	999.00	999.00	HS 0.00	0.00
-1.000	OPER.	5C1T	999.00	999.00	0.00	0.00
-1.000	POST.		999.00	999.00	0.00	0.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.474	INV.	HS20	1.01	HS 20.19	36.3
1.474	OPER.	5C1T	2.20	0.00	176.1
-1.000	POST.		999.00	0.00	0.0

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 8

Live Load Distribution Factor 1.143

Second Live Load Dist. Factor 1.143

Comments:

Member I. D.	S01	Symmetry:				
Span Length:	Span 1 23.917	Span 2 23.917	Span 3 23.917	Span 4 23.917	Span 5 23.917	
	Span 6 23.917	Span 7 23.917	Span 8 23.917	Span 9 0.000	Span 10 0.000	

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.18	HS 23.58	42.4
1.400	OPER.	5C1T	2.19	0.00	174.9
1.000	POST.		999.00	0.00	999.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
2.000	INV.	HS20	135.55	1.73	HS 34.61	62.30
2.000	OPER.	5C1T	262.51	3.85	0.00	307.70
1.000	POST.		999.00	999.00	0.00	999.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.23	HS 24.68	44.4
1.400	OPER.	5C1T	2.29	0.00	183.0
1.000	POST.		999.00	0.00	999.0

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 8

Live Load Distribution Factor 1.143

Second Live Load Dist. Factor 1.143

Comments:

Member I. D. S02 Symmetry:

Span Length:	Span 1 23.917	Span 2 23.917	Span 3 23.917	Span 4 23.917	Span 5 23.917
	Span 6 23.917	Span 7 23.917	Span 8 23.917	Span 9 0.000	Span 10 0.000

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.21	HS 24.24	43.6
1.400	OPER.	5C1T	2.25	0.00	179.8
1.000	POST.		999.00	0.00	999.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
2.000	INV.	HS20	133.30	1.77	HS 35.31	63.60
2.000	OPER.	5C1T	258.16	3.92	0.00	314.00
1.000	POST.		999.00	999.00	0.00	999.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.27	HS 25.34	45.6
1.400	OPER.	5C1T	2.35	0.00	187.9
1.000	POST.		999.00	0.00	999.0

BRIDGE / MEMBER DATA

SUMMARY REPORT

Structure I. D. HAM500

Material of Construction SS
 Year of Construction 1959
 Roadway Width 32.000
 Number of Spans 8

Live Load Distribution Factor 1.143

Second Live Load Dist. Factor 1.143

Comments:

Member I. D.	S03					Symmetry:
Span Length:	Span 1 23.917	Span 2 23.917	Span 3 23.917	Span 4 23.917	Span 5 23.917	
	Span 6 23.917	Span 7 23.917	Span 8 23.917	Span 9 0.000	Span 10 0.000	

Moment

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.20	HS 23.91	43.0
1.400	OPER.	5C1T	2.22	0.00	177.3
1.000	POST.		999.00	0.00	999.0

Shear

C.P.			Rating Factor (-)	Rating Factor (+)	Rating Value	Load Capacity
2.000	INV.	HS20	134.42	1.75	HS 34.96	62.90
2.000	OPER.	5C1T	260.32	3.89	0.00	310.90
1.000	POST.		999.00	999.00	0.00	999.00

Serviceability

C.P.			Rating Factor	Rating Value	Load Capacity (tons)
1.400	INV.	HS20	1.25	HS 25.01	45.0
1.400	OPER.	5C1T	2.32	0.00	185.4
1.000	POST.		999.00	0.00	999.0