




ms consultants, inc.
msconsultants.com

msconsultants.com

DEL - US 23-13.17
160054 PID - 94527
Dist 6 1/28/2016


Contract Proposal Available @ www.
contracts.dot.state.oh.us/home



LOCATION MAP

LATITUDE: 40° 18' 56" LONGITUDE: 83° 04' 01"

SCALE IN MILES



PORTION TO BE IMPROVED
INTERSTATE & DIVIDED HIGHWAY
UNDIVIDED STATE & FEDERAL ROUTES
OTHER ROADS

DESIGN DESIGNATION	US 23
CURRENT ADT (2012)	32,400
DESIGN YEAR ADT (2035)	43,700
DESIGN HOURLY VOLUME (2035)	5,200
DIRECTIONAL DISTRIBUTION	53.7%
TRUCKS (24 HOUR B&C)	13%
DESIGN SPEED	45 MPH
LEGAL SPEED	45 MPH
DESIGN FUNCTIONAL CLASSIFICATION	PRINCIPAL ARTERIAL
NHS PROJECT	YES


DESIGN EXCEPTIONS	APPROVAL DATE	SHEET NUMBERS
HORIZONTAL ALIGNMENT - DEGREE OF CURVE	04/01/2014	2, 11

SUPERELEVATION RATE	04/01/2014	2
---------------------	------------	---

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES
CALL TWO WORKING DAYS
BEFORE YOU DIG
CALL 1-800-362-2764
(TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY
OIL & GAS PRODUCERS PROTECTIVE
SERVICE CALL: 1-800-925-0988

SANDUSKY STREET EXTENSION

CURRENT ADT (2012)	2,610
DESIGN YEAR ADT (2035)	10,600
DESIGN HOURLY VOLUME (2035)	950
DIRECTIONAL DISTRIBUTION	70.3%
TRUCKS (24 HOUR B&C)	2%
DESIGN SPEED	35 MPH
LEGAL SPEED	35 MPH
DESIGN FUNCTIONAL CLASSIFICATION	MINOR ARTERIAL



PLAN PREPARED BY:

ms consultants, inc.

engineers, architects & planners
2221 Schrock Road
Columbus, Ohio 43229-1547
Tel 614.898.7100 Fax 614.898.7570
www.msconsultants.com

STATE OF OHIO DEPARTMENT OF TRANSPORTATION **DEL-23-13.17** CITY OF DELAWARE DELAWARE TOWNSHIP DELAWARE COUNTY

INDEX OF SHEETS:

TITLE SHEET	1
SCHEMATIC PLAN	2
TYPICAL SECTIONS	3-5
GENERAL NOTES	6-7
MAINTENANCE OF TRAFFIC	8-10, 10A, 11-21
GENERAL SUMMARY	22-24
SUBSUMMARIES	25-28
PROJECT SITE PLAN	29
PLAN & PROFILE - US 23	30
PLAN & PROFILE - SANDUSKY STREET	31-33
CROSS SECTIONS - US 23	34-41
CROSS SECTIONS - SANDUSKY STREET	42-48
SUPERELEVATION TABLE - SANDUSKY STREET	49
INTERSECTION DETAILS	50-51
DRIVE DETAILS	52-53
WATER WORK	54-60
MISCELLANEOUS DETAILS	61-62
TRAFFIC CONTROL	63-69, 69A, 69B, 70-80
LIGHTING	81-88
LANDSCAPING	89-94
RIGHT OF WAY	95-103
SOIL PROFILES	

STANDARD CONSTRUCTION DRAWINGS

NO.	DATE	DESCRIPTION	DATE	DESCRIPTION	DATE	DESCRIPTION	SUPPLEMENTAL SPECIFICATIONS
BP-1.1	7/28/00	DM-2.1	1/18/13	TC-41.20	10/18/13		800 10/18/13
BP-3.1	7/18/14	DM-4.3	7/18/13	TC-81.21	7/17/13		809 1/18/13
BP-4.1	7/19/13	DM-4.4	7/20/12	TC-83.10	1/17/14		832 1/17/14
BP-5.1	7/19/13			TC-83.20	7/17/13		902 12/31/12
BP-7.1	7/18/14	NO-1.1	1/18/13	TC-85.20	1/18/13		839 7/17/13
		NO-1.2	1/18/13				878 10/18/13
CB-1.1	1/18/13						
CB-1.2	1/18/13	RM-1.1	7/18/14				
CB-1.3	1/18/13	RM-4.4	7/18/14				
CB-2.1	1/18/13	RM-4.6	7/19/13				
CB-2.2	1/17/14						
LA-1.1	1/18/13	LA-1.2	10/15/10				
DM-1.1	1/18/13	MT-101.70	1/17/14				
DM-1.2	1/18/13	MT-101.90	7/17/13				

SPECIAL PROVISIONS
SP-OLEHTANGY..
NPDES-06-02-14

PROJECT DESCRIPTION

REMOVE THE SOUTHBOUND US-23 EXIT AND EXTEND SANDUSKY STREET TO A SIGNALIZED INTERSECTION AT US-23, ADD A SOUTHBOUND RIGHT TURN LANE AND A NORTHBOUND LEFT TURN LANE AT THE PROPOSED US-23 / SANDUSKY STREET INTERSECTION.

PROJECT EARTH DISTURBED AREA:	4.66 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	0.25 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	4.91 ACRES

LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY, EXCEPT FOR THE SIDE ROADS AS DESCRIBED ON SHEET 11, AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED *[Signature]*
DATE 10/13/15 DEPUTY CITY ENGINEER,
CITY OF DELAWARE

APPROVED *[Signature]*
DATE 10-15-15 DISTRICT DEPUTY DIRECTOR

APPROVED *[Signature]*
DATE 11-10-15 DIRECTOR, DEPARTMENT OF
TRANSPORTATION

FEDERAL PROJECT NO.
E130 (216)

PID NO.
94527

CONSTRUCTION PROJECT NO.

RAILROAD INVOLVEMENT
NONE

DEL-23-13.17

1
103

C1 US 23
P.I.Sta. 693+80.16
 $\Delta = 4^\circ 40' 32''$ (LT)
 $Dc = 0^\circ 28' 00''$
 $R = 12,277.67'$
 $T = 501.23'$
 $L = 1,001.91'$
 $E = 10.23'$
 $C = 1,001.63'$
C.B. = N $23^\circ 43' 35''$ W
 $\theta_{max} = \text{MATCH EXISTING}$

C3 SANDUSKY ST.
P.I.Sta. 311+33.35
 $\Delta = 97^\circ 06' 30''$ (RT)
 $Dc = 49^\circ 49' 21''$ (NDC= $15^\circ 30'$)
 $R = 115.00'$
 $T = 130.23'$
 $L = 194.91'$
 $E = 58.74'$
 $C = 172.40'$
C.B. = N $17^\circ 04' 24''$ E
 $\theta_{max} = R.C.$ (NDC= 0.040)


C2 SANDUSKY ST.
P.I.Sta. 305+90.87
 $\Delta = 35^\circ 12' 45''$ (LT)
 $Dc = 11^\circ 00' 00''$
 $R = 520.87'$
 $T = 165.29'$
 $L = 320.11'$
 $E = 25.60'$
 $C = 315.10'$
C.B. = N $13^\circ 52' 29''$ W
 $\theta_{max} = N.C.$

SCS1 US 23 RAMP
P.I.Sta. 106+62.29
 $\Delta = 111^\circ 59' 44''$ (LT)
 $Dc = 22^\circ 00' 00''$
 $R = 260.44'$
 $Ls = 200.00'$
 $\theta s = 22^\circ 00' 00''$
 $LT = 134.38'$
 $ST = 67.62'$
 $x = 197.07'$
 $y = 25.33'$
 $k = 99.51'$
 $p = 6.37'$
 $\Delta c = 67^\circ 59' 44''$ (LT)
 $Lc = 309.07'$
 $Ts = 495.03'$
 $Es = 216.66'$
 $C = 291.25'$
 $C1 = C2 = 198.69'$
C.B.1 = N $61^\circ 18' 13''$ E
C.B. = N $12^\circ 37' 48''$ E
C.B.2 = S $36^\circ 02' 37''$ E


C4 US 23 RAMP
P.I.Sta. 111+95.38
 $\Delta = 16^\circ 11' 00''$ (RT)
 $Dc = 5^\circ 00' 00''$
 $R = 1,145.92'$
 $T = 162.92'$
 $L = 323.67'$
 $E = 11.52'$
 $C = 322.59'$
C.B. = N $35^\circ 16' 34''$ W






PRIMARY PROJECT CONTROL INFORMATION

POINT	NORTHING	EASTING	FEATURE	ELEVATION	DESCRIPTION
BM 1	236996.859	1810301.397	BM	873.41	TBM 1
BM 2	235929.350	1810578.617	BM	889.29	TBM 2
CP 1	236660.362	1810583.585	--	875.15	CONTROL POINT 1
CP 2	235713.893	1810945.535	--	868.99	CONTROL POINT 2



END PROJECT
STA 700+23.86
S.L.M. = 13.27



**LEGEND:****PROPOSED**

- ① ITEM 442 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5mm, TYPE A (446)
- ② ITEM 442 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (446)
- ③ ITEM 301 - 9" ASPHALT CONCRETE BASE, PG64-22
- ④ ITEM 304 - 8" AGGREGATE BASE
- ⑤ ITEM 407 - TACK COAT FOR INTERMEDIATE COURSE @ 0.04 GAL/SY
- ⑥ ITEM 301 - 7" ASPHALT CONCRETE BASE, PG64-22
- ⑦ ITEM 407 - TACK COAT @ 0.075 GAL/SY
- ⑧ ITEM 204 - SUBGRADE COMPACTION
- ⑨ ITEM 605 - 4" BASE PIPE UNDERDRAINS
- ⑩ ITEM 608 - 4" CONCRETE WALK
- ⑪ ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2
- ⑫ ITEM 620 - DELINEATOR MISC.: REBOUNDABLE TUBULAR PYLON
- ⑬ ITEM 659 - SEEDING AND MULCHING, CLASS 1
- ⑭ ITEM 605 - 4" SHALLOW PIPE UNDERDRAINS
- ⑮ ITEM 204 - GRANULAR MATERIAL TYPE B, 703.16
- ⑯ ITEM 204 - GEOTEXTILE FABRIC, 712.09, TYPE D
- ⑰ ITEM 622 - BARRIER, MISC.: NEW JERSEY STYLE, TYPE A, AS PER PLAN
- ⑱ ITEM 622 - BARRIER TRANSITION, AS PER PLAN
- ⑲ ITEM 606 - IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL)
- ⑳ ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE
- ㉑ ITEM 448 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22
- ㉒ ITEM 448 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22
- ㉓ ITEM 442 - ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (448) VARIABLE DEPTH (0" MIN., 1 1/4" MAX.)

EXISTING

- Ⓐ 6"± ASPHALT CONCRETE
- Ⓑ 9 1/2"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- Ⓒ 4 1/2" ASPHALT CONCRETE
- Ⓕ 32" JERSEY BARRIER
- Ⓖ GUARDRAIL

- Ⓐ REMOVE EXISTING BARRIER FROM STA 688+54.95 TO STA 690+81.17
- Ⓑ STA 689+00.00 TO STA 689+10.00 = 6.0'
STA 689+10.00 TO STA 689+60.00 = 6.0' - 4.0'
STA 689+60.00 TO STA 695+02.42 = 4.0'
- Ⓕ EXTEND AND END 1.2' UNDERCUT TO STA 695+00.00

NOTE "A"
PAVEMENT PLANING SHALL BE A CONSTANT DEPTH OF 1 1/4" ON US 23, INCLUDING PAVED SHOULDERS, AND EXCLUDING RAMP AND GORE AREAS ON NORTHBOUND US 23. FOR THE OUTSIDE LANE ON SOUTHBOUND US 23, FROM STA 694+03.73 TO STA 700+20.00, PAVEMENT PLANING SHALL BE A VARIABLE DEPTH WITH 1 1/4" BEING PLANED AT THE LANE LINE AND DECREASING IN DEPTH AS PLANING APPROACHES THE SAW CUT LINE. THIS IS TO ESTABLISH A MAXIMUM PAVEMENT CROSS SLOPE OF 0.020.

**LEGEND:****PROPOSED**

- ① ITEM 442 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5mm, TYPE A (446)
- ② ITEM 442 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (446)
- ③ ITEM 301 - 9" ASPHALT CONCRETE BASE, PG64-22
- ④ ITEM 304 - 8" AGGREGATE BASE
- ⑤ ITEM 407 - TACK COAT FOR INTERMEDIATE COURSE @ 0.04 GAL/SY
- ⑥ ITEM 301 - 7" ASPHALT CONCRETE BASE, PG64-22
- ⑦ ITEM 407 - TACK COAT @ 0.075 GAL/SY
- ⑧ ITEM 204 - SUBGRADE COMPACTION
- ⑨ ITEM 605 - 4" BASE PIPE UNDERDRAINS
- ⑩ ITEM 608 - 4" CONCRETE WALK
- ⑪ ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2
- ⑫ ITEM 620 - DELINEATOR MISC.: REBOUNDABLE TUBULAR PYLON
- ⑬ ITEM 659 - SEEDING AND MULCHING, CLASS 1
- ⑭ ITEM 605 - 4" SHALLOW PIPE UNDERDRAINS
- ⑮ ITEM 204 - GRANULAR MATERIAL TYPE B, 703.16
- ⑯ ITEM 204 - GEOTEXTILE FABRIC, 712.09, TYPE D
- ⑰ ITEM 622 - BARRIER, MISC.: NEW JERSEY STYLE, TYPE A, AS PER PLAN
- ⑱ ITEM 622 - BARRIER TRANSITION, AS PER PLAN
- ⑲ ITEM 606 - IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL)
- ⑳ ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE
- ㉑ ITEM 448 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22
- ㉒ ITEM 448 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22
- ㉓ ITEM 442 - ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (448) VARIABLE DEPTH (0" MIN., 1 1/4" MAX.)

EXISTING

- (A) 6"± ASPHALT CONCRETE
- (B) 9 1/2"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- (C) 4 1/2" ASPHALT CONCRETE
- (F) 32" JERSEY BARRIER
- (G) GUARDRAIL


FOR ADDITIONAL INFORMATION
STA. 694+03.73 TO STA. 696+28.80
SEE INTERSECTION DETAIL, SHEET 51.

SEE NOTE "A"

US 23 - NORMAL SECTION

SECTION APPLIES:
STA 694+03.73 TO STA 700+20.00

- [G] BEGIN SHOULDER AT STA 695+87.23
- [H] BEGIN TURN LANE AT STA 695+50.00
STA 695+50.00 TO STA 699+70.00 = 11.0'
699+70.00 TO STA 700+20.00 = 11.0' - 0.0'
- [J] DELINEATOR FROM STA 695+00.00 TO STA 695+50.00


**US 23 - ADJOINING SECTION**


SECTION APPLIES: STA 700+20.00

NOTE "A"

PAVEMENT PLANING SHALL BE A CONSTANT DEPTH OF 1 1/4" ON US 23, INCLUDING PAVED SHOULDERS, AND EXCLUDING RAMP AND GORE AREAS ON NORTHBOUND US 23. FOR THE OUTSIDE LANE ON SOUTHBOUND US 23, FROM STA 694+03.73 TO STA 700+20.00, PAVEMENT PLANING SHALL BE A VARIABLE DEPTH WITH 1 1/4" BEING PLANED AT THE LANE LINE AND DECREASING IN DEPTH AS PLANING APPROACHES THE SAW CUT LINE. THIS IS TO ESTABLISH A MAXIMUM PAVEMENT CROSS SLOPE OF 0.020.

DELINEATOR: REBOUNDABLE TUBULAR PYLONS
NOT TO SCALE





SANDUSKY STREET - NORMAL SECTION
SECTION APPLIES:
STA 302+28.30 TO STA 309+38.97

- [K]** END SIDEWALK AT STA 310+55.12, 35.5' LT.
- [L]** STA 302+28.30 TO STA 306+32.21 = 6.0'
STA 306+32.21 TO STA 307+45.69 = 6.0' - 0.0'
STA 307+45.69 TO STA 309+38.97 = 0.0'
- [M]** STA 302+28.30 TO STA 306+32.21 = 6.0'
STA 306+32.21 TO STA 307+45.69 = 6.0' - 0.0'
STA 307+45.69 TO STA 309+38.97 = 0.0'
- [N]** STA 302+28.30 TO STA 302+63.32 = 57.8' - 20.0'
- [P]** STA 302+30.09 TO STA 302+50.09 = 38.0' - 18.0'
- [R]** USE CURB, TYPE 6 WITHIN RADIUS RETURN
STA 302+28.30 TO STA 302+63.32, LT.

BEGIN CURB AND GUTTER, TYPE 2
STA 302+31.20, 31.4' RT.

LEGEND:

PROPOSED

- ① ITEM 442 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5mm, TYPE A (446)
- ② ITEM 442 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (446)
- ③ ITEM 301 - 9" ASPHALT CONCRETE BASE, PG64-22
- ④ ITEM 304 - 8" AGGREGATE BASE
- ⑤ ITEM 407 - TACK COAT FOR INTERMEDIATE COURSE @ 0.04 GAL/SY
- ⑥ ITEM 301 - 7" ASPHALT CONCRETE BASE, PG64-22
- ⑦ ITEM 407 - TACK COAT @ 0.075 GAL/SY
- ⑧ ITEM 204 - SUBGRADE COMPACTION
- ⑨ ITEM 605 - 4" BASE PIPE UNDERDRAINS
- ⑩ ITEM 608 - 4" CONCRETE WALK
- ⑪ ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2
- ⑫ ITEM 620 - DELINEATOR MISC.: REBOUNDABLE TUBULAR PYLON
- ⑬ ITEM 659 - SEEDING AND MULCHING, CLASS 1
- ⑭ ITEM 605 - 4" SHALLOW PIPE UNDERDRAINS
- ⑮ ITEM 204 - GRANULAR MATERIAL TYPE B, 703.16
- ⑯ ITEM 204 - GEOTEXTILE FABRIC, 712.09, TYPE D
- ⑰ ITEM 622 - BARRIER, MISC.: NEW JERSEY STYLE, TYPE A, AS PER PLAN
- ⑱ ITEM 622 - BARRIER TRANSITION, AS PER PLAN
- ⑲ ITEM 606 - IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL)
- ⑳ ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE

FOR ADDITIONAL INFORMATION
STA. 311+60.63 TO STA. 312+51.32
SEE INTERSECTION DETAIL, SHEET 51.

SANDUSKY STREET - SUPERELEVATED SECTION [V]
SECTION APPLIES:
STA 309+38.97 TO STA 312+51.32

- [21]** ITEM 448 - 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22
- [22]** ITEM 448 - 1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22
- [23]** ITEM 442 - ASPHALT CONCRETE INTERMEDIATE COURSE, 19mm, TYPE A (448) VARIABLE DEPTH (0" MIN., 1 1/4" MAX.)

EXISTING

- [A]** 6"± ASPHALT CONCRETE
- [B]** 9 1/2"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- [C]** 4 1/2" ASPHALT CONCRETE
- [F]** 32" JERSEY BARRIER
- [G]** GUARDRAIL

FOR ADDITIONAL INFORMATION
STA. 311+18.52 TO STA. 312+51.32
SEE INTERSECTION DETAIL, SHEET 51.

- [S]** STA 309+38.97 TO STA 311+60.63 = 18.0'
STA 311+60.63 TO STA 312+39.84 = 18.0' - 129.5'
- [T]** STA 309+38.97 TO STA 311+18.52 = 18.0'
STA 311+18.52 TO STA 312+51.32 = 18.0' - 94.9'
- [U]** END COMBINATION CURB AND GUTTER, TYPE 2
STA 312+34.07, 87.0' LT.
STA 312+40.80, 58.1' RT.
- [V]** FOR SUPERELEVATION TRANSITIONS
SEE SUPERELEVATION TABLE, SHEET 49.

SEQUENCE OF CONSTRUCTION

PHASE 1

N. SANDUSKY ST.
THIS PHASE INCLUDES A SUB-PHASE FOR HALF-WIDTH CONSTRUCTION ALONG N. SANDUSKY ST. PHASE 1 AND PHASE 1A ARE INDEPENDENT OF THE TRAFFIC CONTROL FOR US-23 IN PHASE 1.

CLOSE N. SANDUSKY ST. AS INDICATED IN THE PLANS. MAINTAIN BI-DIRECTIONAL LOCAL TRAFFIC ON THE WESTERN HALF OF THE ROADWAY WHILE PERFORMING CONSTRUCTION ACTIVITIES ON THE EASTERN HALF OF THE ROADWAY. MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS TO THE EXISTING PROPERTIES AND DRIVEWAYS AS SHOWN ON THE PLANS AT ALL TIMES.

US-23
CLOSE THE TWO-WAY LEFT-TURN LANE AS INDICATED IN THE PLANS. SHIFT SOUTHBOUND US-23 TRAVEL LANES TO THE EAST AS INDICATED IN THE PLANS. CLOSE THE N. SANDUSKY ST. EXIT RAMP WITH PORTABLE BARRIER AND IMPLEMENT THE DETOUR AS SHOWN IN THE PLANS. MAINTAIN NORTHBOUND US-23 AND RAMP TRAFFIC IN THE EXISTING LANES. MAINTAIN RIGHT-IN, RIGHT-OUT ACCESS TO ALL DRIVEWAYS ALONG US-23 UNLESS INDICATED IN THE PLANS TO BE CLOSED WITH PORTABLE BARRIER.

CONSTRUCT US-23 SOUTHBOUND WIDENING AND THE EXTENSION OF N. SANDUSKY ST. AS SHOWN IN THE ROADWAY PLANS. PERFORM ALL NECESSARY GRADING, LIGHTING, UTILITY, SIGNAL AND ANY OTHER REQUIRED OFF-ALIGNMENT WORK ACCORDING TO THE APPLICABLE PLANS DURING THIS PHASE. INSTALL THE TRAFFIC SIGNAL EQUIPMENT AND SUPPORTS LOCATED EAST OF THE ON-RAMP UTILIZING SHOULDER CLOSURES AND LANE REDUCTIONS IN ACCORDANCE WITH THE LANE CLOSURE/REDUCTION REQUIREMENTS LISTED ABOVE.

PHASE 1A

N. SANDUSKY ST.
CLOSE N. SANDUSKY ST. AS INDICATED IN THE PLANS. MAINTAIN BI-DIRECTIONAL LOCAL TRAFFIC ON THE NEWLY CONSTRUCTED EASTERN HALF OF THE ROADWAY WHILE PERFORMING CONSTRUCTION ACTIVITIES ON THE WESTERN HALF OF THE ROADWAY. MAINTAIN VEHICULAR AND PEDESTRIAN ACCESS TO THE EXISTING PROPERTIES AND DRIVEWAYS AS SHOWN ON THE PLANS AT ALL TIMES. NOTIFY LOCAL PROPERTY OWNERS 48 HOURS BEFORE BEGINNING ANY WORK THAT WILL AFFECT THE PROPERTY OWNER'S DRIVEWAY OR WALKWAY. UTILIZE HALF-WIDTH CONSTRUCTION AND TRAFFIC COMPACTED SURFACES TO MAINTAIN DRIVEWAY ACCESS AT ALL TIMES.

PHASE 2

N. SANDUSKY ST.
MAINTAIN THE CLOSURE OF THE N. SANDUSKY ST. EXTENSION. MAINTAIN LOCAL TRAFFIC TO THE LIMITS SHOWN ON THE PLANS AT ALL TIMES.

US-23
MAINTAIN THE N. SANDUSKY ST. DETOUR THAT WAS ESTABLISHED IN PHASE 1. CLOSE THE TWO-WAY LEFT-TURN LANE AS INDICATED IN THE PLANS. SHIFT NORTHBOUND AND SOUTHBOUND TRAFFIC TO THE OUTSIDE OF THE ROADWAY AS SHOWN IN THE PLANS BY UTILIZING THE NEW PAVEMENT CONSTRUCTED IN PHASE 1 FOR SOUTHBOUND TRAFFIC AND THE EXISTING SHOULDER FOR NORTHBOUND TRAFFIC. ESTABLISH THE WORK ZONE IN THE CENTER OF US-23 WITH PORTABLE BARRIER AS INDICATED IN THE PLANS.

PERFORM TRENCH DRAIN, MEDIAN BARRIER AND IMPACT ATTENUATOR CONSTRUCTION ACTIVITIES AS INDICATED IN THE ROADWAY PLANS. INSTALL THE LANE SEPARATOR WITH REBOUNDABLE POSTS AS SHOWN IN THE SIGNING AND MARKING PLANS.

PHASE 3 (NO SHEETS PROVIDED)

REMOVE ALL TRAFFIC CONTROL FROM THE PREVIOUS PHASES, INCLUDING THE N. SANDUSKY ST. DETOUR, AND INSTALL PERMANENT PAVEMENT MARKINGS. PLACE THE NEW TRAFFIC SIGNAL INTO OPERATION AND OPEN N. SANDUSKY ST. TO TRAFFIC.

METHOD OF PAYMENT

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OMUTCD.

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

ITEM 614 MAINTAINING TRAFFIC LUMP SUM

MAINTAINING TRAFFIC (ESTIMATED QUANTITIES)

ACCESS TO ALL DRIVEWAYS WITHIN THE WORK AREA SHALL BE MAINTAINED USING ITEM 410, TRAFFIC COMPACTED SURFACE, TYPE A OR B, AS DIRECTED BY THE ENGINEER.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC.

ITEM 410, TRAFFIC COMPACTED SURFACE, TYPE A OR B - 50 CU. YD.

ITEM 616, WATER - 1 M. GAL.

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER - 60 M. GAL.

MAINTENANCE OF TRAFFIC SIGNAL/FLASHER INSTALLATION

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRAFFIC SIGNAL/FLASHER INSTALLATIONS WITHIN THE PROJECT UNDER THE FOLLOWING CONDITIONS:

1. EXISTING SIGNAL/FLASHER INSTALLATIONS WHICH THE PLANS REQUIRE THE CONTRACTOR TO ADJUST, MODIFY, ADD ONTO OR REMOVE, OR WHICH THE CONTRACTOR ACTUALLY ADJUSTS, MODIFIES OR OTHERWISE DISTURBS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ENTIRE INSTALLATION (AT AN INTERSECTION) FROM THE TIME HIS OPERATIONS FIRST DISTURB THE INSTALLATION UNTIL THE INSTALLATION HAS BEEN SUBSEQUENTLY REMOVED OR MODIFIED AND THE WORK IS ACCEPTED.

2. NEW OR REUSED SIGNAL/FLASHER INSTALLATIONS OR DEVICES, INSTALLED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF THESE FROM THE TIME OF INSTALLATION UNTIL THE WORK IS ACCEPTED.

THE CONTRACTOR SHALL CORRECT AS QUICKLY AS POSSIBLE ALL OUTAGES OR MALFUNCTIONS. HE SHALL PROVIDE THE MAINTAINING AGENCY AND THE ENGINEER SUCH ADDRESSES AND PHONE NUMBERS WHERE HIS MAINTENANCE FORCES CAN BE CONTACTED. THE CONTRACTOR SHALL PROVIDE ONE OR MORE PERSONS TO RECEIVE ALL CALLS AND DISPATCH THE NECESSARY MAINTENANCE FORCES TO CORRECT OUTAGES. SUCH A PERSON OR PERSONS MAY BE USED TO PERFORM OTHER DUTIES AS LONG AS PROMPT ATTENTION IS GIVEN TO THESE CALLS AND A PERSON IS READILY AVAILABLE CONTINUOUSLY 24 HOURS A DAY, 7 DAYS A WEEK. ALL LAMP OUTAGES, CABLE OUTAGES, ELECTRICAL FAILURES, EQUIPMENT MALFUNCTIONS AND MISALIGNED SIGNAL HEADS SHALL BE CORRECTED TO THE SATISFACTION OF THE ENGINEER WITH THE SIGNAL BACK TO SERVICE WITHIN FOUR HOURS AFTER THE CONTRACTOR HAS BEEN NOTIFIED OF THE OUTAGE.

IN THE EVENT NEW SIGNALS ARE DAMAGED PRIOR TO ACCEPTANCE, ALL DAMAGED EQUIPMENT EXCEPT POLES AND CONTROL EQUIPMENT SHALL BE REPLACED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER WITH THE SIGNAL BACK IN SERVICE WITHIN 8 HOURS AFTER THE CONTRACTOR'S NOTIFICATION OF THE OUTAGE. THE CONTRACTOR SHALL ARRANGE FOR FULL TRAFFIC CONTROL UNTIL THE SIGNAL IS BACK IN OPERATION.

IF POLES AND/OR CONTROL EQUIPMENT ARE DAMAGED AND MUST BE REPLACED, THE CONTRACTOR SHALL MAKE TEMPORARY REPAIRS AS NECESSARY TO BRING THE SIGNAL BACK INTO FULL OPERATION WITHIN THE ALLOWED 8-HOUR PERIOD, AND SHALL MAKE PERMANENT REPAIRS OR REPLACEMENT AS SOON THEREAFTER AS POSSIBLE.

NONE OF THE ABOVE SHALL BE CONSTRUED AS COLLECTIVE OR CONSECUTIVE OUTAGE TIME PERIODS AT ANY ONE LOCATION. THAT IS, WHERE MORE THAN ONE OUTAGE OCCURS AT ANY ONE LOCATION THEN THE ALLOTTED TIME LIMIT SHALL BE FOR THE WORST SINGLE OUTAGE.

WHERE OUTAGES ARE THE DIRECT RESULT OF A VEHICLE ACCIDENT THE RESPONSE OF THE CONTRACTOR SHALL BE AS OUTLINED ABOVE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COLLECTION OF ANY COMPENSATION FOR THIS WORK FROM THOSE PARTIES RESPONSIBLE FOR THE DAMAGE.

WHERE THE CONTRACTOR HAS FAILED TO, OR CANNOT RESPOND TO, AN OUTAGE OR SIGNAL EQUIPMENT MALFUNCTION, AT THESE LOCATIONS WITHIN HIS RESPONSIBILITY, WITHIN PERIODS AS SPECIFIED ABOVE, THE ENGINEER MAY INVOKE THE PROVISIONS OF SECTION 105.15 AND ANY SUBSEQUENT BILLINGS TO THE STATE OR THE CITY OF DELAWARE FOR POLICE SERVICES AND MAINTENANCE SERVICES BY CITY FORCES SHALL BE DEDUCTED FROM MONIES DUE OR TO BECOME DUE THE CONTRACTOR IN ACCORDANCE WITH PROVISIONS OF SECTION 105.15.

THE CONTRACTOR SHALL PROVIDE THE MAINTENANCE SERVICE ENTIRELY WITH HIS FORCES OR HE MAY CHOOSE TO ENTER INTO A COOPERATIVE UNDERSTANDING WITH THE LOCAL MAINTAINING AGENCY TO PROVIDE THE MAINTENANCE. THE CONTRACTOR SHALL INFORM THE ENGINEER, IN WRITING, OF THE MAINTENANCE METHOD SELECTED.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ANY TRAFFIC SIGNAL COMPONENTS REQUIRED TO BE HANDLED DURING THE RELOCATION OF POLES AND REVISIONS TO THE SIGNAL SYSTEM. WHEN A TRAFFIC SIGNAL MUST BE TAKEN OUT OF SERVICE BY THE CONTRACTOR, DUE TO CONSTRUCTION PROCEDURES, THIS OUTAGE SHALL NOT EXCEED 4 HOURS AND SHALL NOT INCLUDE THE HOURS OF 6:00 AM TO 9:00 AM AND 3:00 PM TO 6:00 PM. ANY SIGNALIZED INTERSECTION, WHERE THE SIGNAL IS OUT OF SERVICE DUE TO CONSTRUCTION PROCEDURES, OR DUE TO AN OUTAGE OR MALFUNCTION OF EQUIPMENT AS DESCRIBED ABOVE, SHALL BE PROTECTED, BY THE CONTRACTOR, BY THE INSTALLATION OF TEMPORARY "STOP" SIGNS.

ANY VEHICULAR TRAFFIC SIGNAL HEAD, EITHER NEW OR EXISTING WHICH WILL BE OUT OF OPERATION SHALL BE COVERED IN THE MANNER DESCRIBED IN 632.25.

THE CONTRACTOR SHALL MAINTAIN COMPLETE RECORDS OF MALFUNCTIONS INCLUDING:

1. TIME OF NOTIFICATION OF MALFUNCTION;
2. TIME OF WORK CREWS ARRIVAL TO CORRECT THE MALFUNCTION;
3. ACTIONS TAKEN TO CORRECT THE MALFUNCTION, INCLUDING A LIST OF PARTS REPAIRED OR REPLACED;
4. A DIAGNOSIS OF REASON FOR THE MALFUNCTION AND PROBABILITY OF REOCCURRENCE;
5. TIME OF COMPLETION OF THE REPAIR AND SYSTEM RESTORED TO FULL SERVICE.

A COPY OF THESE RECORDS SHALL BE PROVIDED TO THE ENGINEER WITHIN THREE (3) WORKING DAYS FOLLOWING COMPLETION OF EACH REPAIR.

ALL COSTS RESULTING FROM THE ABOVE REQUIREMENTS SHALL BE CONSIDERED TO BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING TRAFFIC.

LEGEND



WORK AREA



TRAFFIC SIGNAL



VEHICLE DETOUR




DETOUR SIGN

NOTE:

1. TEMPORARY SIGNAL TIMING ADJUSTMENTS MAY BE REQUIRED AT US-23 SB OFF-RAMP AND E. CENTRAL AVENUE AND E. CENTRAL AVENUE AND SANDUSKY STREET. CITY OF DELAWARE WILL MONITOR AND PERFORM ANY REQUIRED TIMING ADJUSTMENTS.



①	②	③	④	⑤	⑥
D3-1 48" X 12" BLACK/ORANGE	D3-1 48" X 12" BLACK/ORANGE	D3-1 48" X 12" BLACK/ORANGE	D3-1 48" X 12" BLACK/ORANGE	D3-1 48" X 12" BLACK/ORANGE	D3-1 48" X 12" BLACK/ORANGE
N. Sandusky St	N. Sandusky St	N. Sandusky St	N. Sandusky St	N. Sandusky St	N. Sandusky St
END DETOUR	DETOUR →	DETOUR ↗	DETOUR ↗	DETOUR ↗	DETOUR ↑
M4-8A-24	M4-9R-30	M4-9(MOD)-30	M4-9(MOD)-30	M4-9(MOD)-30	M4-9-30



DRUM SPACING TABLE

TANGENT = 80'

TAPER = 45'


INTERSECTION RADII = 5'



MAINTENANCE OF TRAFFIC - PHASE 1
U.S. 23 - STA. 683+00 TO STA. 694+00

DEL-23-13.17

13
103




- NOTES:
- SEE DETOUR PLAN SHEET 11 FOR ADDITIONAL SIGNS.
 - NOTIFY AFFECTED PROPERTY OWNERS OF RIGHT IN, RIGHT OUT ACCESS RESTRICTIONS AT LEAST 48 HOURS BEFORE IMPLEMENTING TEMPORARY TRAFFIC CONTROL THAT LIMITS LEFT TURNS.


DRUM SPACING TABLE	
TANGENT = 80'	
TAPER = 45'	
INTERSECTION RADII = 5'	

FOR LEGEND SEE SHEET 12






NOTES:
1. DURING STAGED CONSTRUCTION OF N. SANDUSKY ST., MAINTAIN ACCESS TO HOMES, BUSINESSES AND DRIVEWAYS AT ALL TIMES. CONTRACTOR TO NOTIFY PROPERTY OWNERS 48 HOURS BEFORE PERFORMING ANY DRIVEWAY OR WALKWAY WORK.



FOR LEGEND SEE SHEET 12

DRUM SPACING TABLE	
TANGENT = 35'	
TAPER = 45'	
INTERSECTION RADII = 5'	



DRUM SPACING TABLE
TANGENT = 80'
TAPER = 45'
INTERSECTION RADII = 5'




CALCULATED
CHECKED

MAINTENANCE OF TRAFFIC - PHASE 2
U.S. 23 - BEGIN PROJECT TO STA. 683+00

DEL-23-13.17


FOR LEGEND SEE SHEET 12



--	--

[illegible]


ms consultants, inc



1. SEE DETOUR PLAN SHEET 11 FOR ADDITIONAL SIGNS.

2. NOTIFY AFFECTED PROPERTY OWNERS OF RIGHT IN, RIGHT OUT ACCESS RESTRICTIONS AT LEAST 48 HOURS BEFORE IMPLEMENTING TEMPORARY TRAFFIC CONTROL THAT LIMITS LEFT TURNS.

DRUM SPACING TABLE
TANGENT = 80'
TAPER = 45'
INTERSECTION RADII = 5'




MAINTENANCE OF TRAFFIC - PHASE 2
U.S. 23 - STA. 694+00 TO STA. 704+00

DEL-23-13.17

20
103

FOR LEGEND SEE SHEET 12



- NOTES:**
1. NOTIFY AFFECTED PROPERTY OWNERS OF RIGHT IN, RIGHT OUT ACCESS RESTRICTIONS AT LEAST 48 HOURS BEFORE IMPLEMENTING TEMPORARY TRAFFIC CONTROL THAT LIMITS LEFT TURNS.

DRUM SPACING TABLE	
TANGENT = 80'	
TAPER = 45'	
INTERSECTION RADII = 5'	



MAINTENANCE OF TRAFFIC - PHASE 2
U.S. 23 - STA. 704+00 TO END PROJECT

DEL-23-13.17

FOR LEGEND SEE SHEET 12

[illegible]

REF. NO.	SHEET NO.	STATION		SIDE	202	202	202	202	202	202	202	202	202	252	606	608	609	609		622	622	638		
					WALK REMOVED	CONCRETE MEDIAN REMOVED	CONCRETE BARRIER REMOVED	CURB REMOVED	PIPE REMOVED, 24" AND UNDER	GUARDRAIL REMOVED	IMPACT ATTENUATOR REMOVED	CATCH BASIN REMOVED		REMOVAL MISC.: CITY OF DELAWARE SIGN REMOVED AND STORED	FULL DEPTH PAVEMENT SAWING		IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL)	4" CONCRETE WALK	CURB, TYPE 6	COMBINATION CURB AND GUTTER, TYPE 2		BARRIER, MISC.: NEW JERSEY STYLE, TYPE A, AS PER PLAN	BARRIER TRANSITION, AS PER PLAN	FIRE HYDRANT REMOVED
		FROM	TO		SQ FT	SQ YD	FT	FT	FT	FT	EACH	EACH		EACH	FT	EACH	SQ FT	FT	FT		FT	EACH	EACH	
R1	30	688+54.95 (US23)	690+53.17 (US23)	L/R			198																	
R2	30	689+00.00 (US23)	690+81.21 (US23)	L/R										372										
R3	30	690+54.18 (US23)	690+79.86 (US23)	L/R							1													
R4	30	689+00.00 (US23)	700+20.00 (US23)	LT										1142										
R5	30	694+61.38 (US23)	696+47.30 (US23)	LT					189		1													
R6	30	698+83.32 (US23)	699+21.67 (US23)	LT			38																	
R7	30	699+22.96 (US23)	700+30.51 (US23)	LT						111														
R8	31	302+28.30 (SAND)	303+07.71 (SAND)	LT				97																
R9	31	302+29.36 (SAND)	302+40.95 (SAND)	RT				15																
R10	31-32	302+39.02 (SAND)	305+66.32 (SAND)	LT	1581																			
R11	31	302+55.50 (SAND)	303+83.59 (SAND)	RT		184																		
R12	31	303+00.28 (SAND)	303+74.08 (SAND)	LT					75		1													
R13	31-32	303+74.08 (SAND)	305+03.27 (SAND)	LT					124		1													
R13A	32	305+03.27 (SAND)	305+52.33 (SAND)	LT					46		1													
R14	31-32	303+81.30 (SAND)	305+49.71 (SAND)	RT						176														
R15	31-32	304+23.55 (SAND)	305+23.47 (SAND)	L/R		149																		
R16	32	305+38.19 (SAND)	305+64.31 (SAND)	RT				35																
R17	32	306+07.52 (SAND)	308+24.05 (SAND)	L/R	972																			
R18	32	306+23.64 (SAND)	306+31.84 (SAND)	LT										1										
R19	32	308+25.75 (SAND)	309+45.88 (SAND)	RT					132		2													
R20	33	309+45.88 (SAND)	312+19.92 (SAND)	RT					139		1													
R21	32	306+09.30 (SAND)		LT																		1		
G1	30	688+85.71(US23)	688+99.96 (US23)	L/R											1									
SW1	31	302+39.04(SAND)	304+06.86 (SAND)	LT												1044								
SW2	31-32	304+24.52 (SAND)	305+28.72 (SAND)	LT												830								
SW3	32	305+40.54 (SAND)	305+66.78 (SAND)	LT												123								
SW4	32-33	305+84.60 (SAND)	310+55.12 (SAND)	LT												2374								
C1	31	302+28.30 (SAND)	302+63.32 (SAND)	LT													58							
C2	31-33	302+63.32 (SAND)	312+30.23 (SAND)	LT														1025						
C3	31-33	302+33.09 (SAND)	312+39.09 (SAND)	RT														1000						
B1	30	688+54.95 (US23)	688+61.45 (US23)	L/R																7				
B2	30	688+61.45 (US23)	688+85.71(US23)	L/R																	1			
TOTALS CARRIED TO GENERAL SUMMARY					2553	333	236	147	705	287	1	7		1	1514		1	4371	58	2025		7	1	1


REF. NO.	SHEET NO.	STATION		SIDE	204	605	611	611	611	611	611	611	611	611	611	611		611	611	611	839	670	659	
					GRANULAR MATERIAL, TYPE C	6" BASE PIPE UNDERDRAINS WITH FABRIC WRAP	4" CONDUIT, TYPE F	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	12" CONDUIT, TYPE B	12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	18" CONDUIT, TYPE B	21" CONDUIT, TYPE C	CATCH BASIN, NO. 3	CATCH BASIN, NO. 3A	CATCH BASIN, NO. 6		CATCH BASIN, NO. 2-2B	MANHOLE, NO. 3	MANHOLE ADJUSTED TO GRADE	TRENCH DRAIN WITH STANDARD GRATE	DITCH EROSION PROTECTION, AS PER PLAN	TOPSOIL
		CU YD	FT		FT	FT	FT	FT	FT	FT	FT	FT	FT	EACH	EACH	EACH		EACH	EACH	EACH	FT	SQ YD	CU YD	
		FROM	TO																					
D1	30	688+49.97 (US23)	689+05.00 (US23)	R/L				55																
D2	30	689+05.00 (US23)	689+50.00 (US23)	R/L			47								1									
D3	30	689+50.00 (US23)	696+54.71 (US23)	LT																705				
D4	30	696+54.71 (US23)	700+20.00 (US23)	LT			7													366				
D5	30	694+30.00 (US23)	694+60.72 (US23)	LT						31							1							
D6	30	694+60.72 (US23)	695+70.32 (US23)	LT								109		1										
D7	30	695+70.32 (US23)	696+55.48 (US23)	LT									84	1										
D8	32	305+00.00 (SAND)	305+00.00 (SAND)	R/L				40							1									
D9	32	305+00.00 (SAND)	305+20.00 (SAND)	LT					33						1									
D10	32	305+20.00 (SAND)	305+52.33 (SAND)	LT					30								1							
D11	32	305+68.87 (SAND)		LT															1					
D12	32	306+50.00 (SAND)	307+10.00 (SAND)	LT				58						1										
D13	32	307+10.00 (SAND)	307+62.50 (SAND)	LT				51						1										
D14	32	307+62.50 (SAND)	308+25.00 (SAND)	LT				63						1										
D15	32	307+62.50 (SAND)	307+62.50 (SAND)	L/R					40					1										
D16	32-33	307+62.50 (SAND)	310+00.00 (SAND)	RT					239					1										
D17	33	310+00.00 (SAND)	312+24.44 (SAND)	RT						110								1						
D18	33	310+54.33 (SAND)	310+73.24 (SAND)	LT			3													20				
D19	33	310+75.95 (SAND)	310+87.00 (SAND)	LT					25								1							
D20	33	310+87.00 (SAND)	311+25.00 (SAND)	LT				45							1									
D21	33	311+25.00 (SAND)	311+80.00 (SAND)	LT				66										1						
D22	33	311+80.00 (SAND)	312+26.44 (SAND)	LT				70							1									
D23	33	312+14.56 (SAND)		LT															1					
E1	30	689+00.00 (US23)	694+32.00 (US23)	LT																	1457	100		
E2	33	310+73.84 (SAND)	310+75.71 (SAND)	LT	3	23		6																

TOTALS CARRIED TO GENERAL SUMMARY

DROPPED CURB DETAIL

ms consultants, inc.

PLOT.CEL
ms consultants, inc.
msconsultants.com
Ohio DOT Worksheet
DEL-23
UCF: ohioVBI
PCF: 60-06655.Columbus
Batchplot Spec: \\0330share\in\60\06655\standards\plotdrv\batchplot.spc
Pen Table: S:\std\plotting\usin\VB\pen\VB\ms_std.tbl
Plot Driver: S:\std\plotting\usin\VB\PDF\plc1g
Model: Sheet
Printed: 10/8/2015 @ 4:25:56 PM By: hrendlinger
File: \\0330share\in\60\06655\drainage\sheet\066550001.dgn
View: FENCE - VIEW1
34" x 22"



SEDIMENT BASINS							
BASIN	UPSTREAM LOCATION	SURFACE DIMENSIONS	DEPTH	CONTRIBUTING AREA* TOTAL	CONTRIBUTING AREA* FROM EDA	TREATMENT REQUIRED	TREATMENT PROVIDED
SB-1	STA. 689+56 LT, US-23	18' x 56'	4'	0.57 AC.	0.57 AC.	1596 CF	1632 CF
SB-2	STA. 691+76 LT, US-23	16' x 52'	3'	0.87 AC.	0.87 AC.	2436 CF	1218 CF
SB-3	STA. 692+99 LT, US-23	16' x 52'	3'				1218 CF
SB-4	STA. 303+79 LT, SANDUSKY	13' x 28'	2'	0.18 AC.	0.04 AC.	364 CF	368 CF
SB-5	STA. 306+55 LT, SANDUSKY	16' x 42'	3'	0.45 AC.	0.08 AC.	890 CF	918 CF
SB-6	STA. 308+08 LT, SANDUSKY	15' x 39'	3'	0.34 AC.	0.13 AC.	742 CF	747 CF
SB-7	STA. 308+67 LT, SANDUSKY	13' x 42'	2'				620 CF
SB-8	STA. 309+52 LT, SANDUSKY	13' x 42'	2'	0.47 AC.	0.38 AC.	1226 CF	620 CF

* TOTAL CONTRIBUTING AREA DETERMINES THE DEWATERING ZONE VOLUME WHILE THE SEDIMENT STORAGE ZONE SIZING IS DETERMINED BY FLOWS FROM WITHIN THE EARTH DISTURBED AREA (EDA).


PROJECT DATA	
Total Area (Right-of-Way) -----	13.93 Acres
Runoff Coefficient for Pre-Construction Site -----	0.46
Project Earth Disturbed Area ---	4.60 Acres
Runoff Coefficient for Post Construction Site -----	0.50
Estimated Contractor Earth Disturbed Area -----	0.25 Acres
Post Construction BMP: Vegetated biofilters shown on this sheet were provided to meet NPDES post-construction requirements. See cross section sheets for additional details.	
Notice of Intent Earth Disturbed Area -----	4.90 Acres
Impervious (Paved) Area for Pre-Construction Site -----	3.82 Acres
Immediate Receiving Waters -----	Olentangy River
Impervious (Paved) Area for Post Construction Site -----	4.61 Acres
Subsequent Receiving Water -----	Scioto River

VEGETATED BIOFILTERS					
BMP	LOCATION		WIDTH	EDA CREDIT (ACRES)	
	BEGIN LAT./LONG.	END LAT./LONG.			
VBF 1	40.313730 83.066349	40.314908 83.067013	7'	1.43	
VBF 2	40.314908 83.067013	40.315063 83.067105	7'	0.22	
	REQ'D TREATMENT (4.60Ac x 0.24)			1.10	
	TREATMENT PROVIDED			1.65	

PROJECT DESCRIPTION
Remove the southbound US-23 exit and extend Sandusky Street to a signalized intersection at US-23, add a southbound right turn lane and a northbound left turn lane at the proposed US-23/Sandusky Street intersection.

USGS Quadrant: T5N R19W
OHIO-DELAWARE CO.
Longitude: 83°04' 01" *
Latitude: 40°18' 56" *
* Latitude and Longitude to Approx. Center of Project

- LEGEND
- Catch Basin, CB-2-2A
 - Catch Basin, CB-2-2B
 - Catch Basin, CB-3A
 - Catch Basin, CB-3
 - Catch Basin, CB-6
 - Manhole, MH-3
 - Post Construction BMP Vegetated Biofilter Bottom of Ditch Width = 7.0'




P.I. Sta. 693+80.16
 $\Delta = 4^\circ 40' 32''$ (LT)
 $Dc = 0^\circ 28' 00''$
 $R = 12,277.67'$
 $T = 501.23'$
 $L = 1,001.91'$
 $E = 10.23'$
 $C = 1,001.63'$
 $C.B. = N 23^\circ 43' 35'' W$
 $\theta_{max} = \text{MATCH EXISTING}$

FOR ESTIMATED QUANTITIES SEE SHEETS 25-28.
FOR INTERSECTION DETAILS SEE SHEET 51.
FOR WATERLINE DETAILS SEE SHEETS 54-60.
FOR LIGHTING DETAILS SEE SHEETS 81-88.
FOR LANDSCAPING DETAILS SEE SHEETS 89-94.
FOR SIGNAL/TRAFFIC CONTROL DETAILS
SEE SHEETS 63-80.



CALCULATED
CHECKED

PLAN AND PROFILE - US 23
STA 687+00 TO STA 702+00



STA 688+49.52, 79.15' LT
EX. MH, GRATE ELEV 871.35
EX. 48" RCP NW 864.85
EX. 48" RCP E 863.25

STA 688+49.97, 1.52' RT
EX. MEDIAN INLET, GRATE ELEV 870.73
EX. 15" RCP S 865.65
EX. 6" CMP N 866.40
EX. 12" (N) 865.65

BEGIN PROJECT
STA 688+49.97
S.L.M. = 13.04
ELEV = 870.91

STA 689+05.00, @
CB-6, GRATE ELEV 871.63
4" (NW) 868.96
12" (SE) 865.98

STA 689+50.00, 1.50' LT
BEGIN TRENCH DRAIN, GRATE ELEV 872.15
ELEV 871.23

STA 694+30.00, 57.58' LT - US 23
STA 312+24.44, 68.46' RT - SANDUSKY ST
CB-2-2B, GRATE ELEV 871.40
15" (SW) 867.90
15" (NW) 867.90

STA 694+60.72, 63.32' LT - US 23
STA 312+18.89, 37.86' RT - SANDUSKY ST.
CB-3, GRATE ELEV 872.83
4" (W) 869.80
18" (N) 867.34
15" (SE) 867.59

STA 695+70.32, 55.79' LT - US 23
STA 312+26.44, 71.21' LT - SANDUSKY ST
CB-3, GRATE ELEV 873.39
18" (S) 866.25
12" (SW) 866.75
21" (NW) 866.00

STA 696+48.31, 78.30' LT
EX. CB, GRATE ELEV 871.31
EX. 36" RCP WSW 865.71
EX. 30" CPP ENE 864.93

STA 696+55.48, 59.80' LT
EX. CB, GRATE ELEV 871.02
EX. 12" VCP N 865.12
EX. 30" CPP WSW 864.52
EX. 12" VCP S 864.42
EX. 18" VCP S 864.42
EX. 65"x40" RCP E 864.42
6" (NE) 869.76
21" (S) 865.16


STA 696+54.71
E 4" (VERT.) 873.27


STA 700+20.00, 1.50' LT
END TRENCH DRAIN, GRATE ELEV 876.52
ELEV 875.58

END PROJECT
STA 700+23.86
S.L.M. = 13.27
ELEV = 876.57


DEL-23-13.17

30
103






C2 P.I. Sta. 305+90.87
 $\Delta = 35^\circ 12' 45''$ (LT)
 $Dc = 11^\circ 00' 00''$
 $R = 520.87'$
 $T = 165.29'$
 $L = 320.11'$
 $E = 25.60'$
 $C = 315.10'$
 $C.B. = N 13^\circ 52' 29'' W$
 $e_{max} = N.C.$



FOR ESTIMATED QUANTITIES SEE SHEETS 25-28.
FOR DRIVE DETAILS SEE SHEET 52.
FOR WATERLINE DETAILS SEE SHEETS 54-60.
FOR LIGHTING DETAILS SEE SHEETS 81-88.
FOR LANDSCAPING DETAILS SEE SHEETS 89-94.
FOR SIGNALS/TRAFFIC CONTROL DETAILS
SEE SHEETS 63-80.




CALCULATED

CHECKED

PLAN AND PROFILE - SANDUSKY STREET
STA 304+50 TO STA 309+50

DEL-23-13.17

32
103




SEEDING		END AREA		VOLUME		CALCULATED	CHECKED
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	DWH	RDW
24	133	38	3	68	5		
23	89	35	2	62	2		
9	0	32	0	0	0		
0	0	0	0	0	0		
0	0	0	0	0	0		
222				130	7		


CROSS SECTIONS - US 23
STA. 688+50.00 TO STA. 690+00.00

DEL-23-13.17

34
103



END AREA		VOLUME		CALCULATED	DWH CHECKED	RDW
CUT	FILL	CUT	FILL			
77	21	130	41	CROSS SECTIONS - US 23 STA. 690+50.00 TO STA. 691+50.00		
63	23	98	22			
43	1	75	4			
		303	67	DEL-23-13.17		
				35 103		




SEEDING		END AREA		VOLUME		CALCULATED DWH	CHECKED RDW
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL		
928				463	108		

CROSS SECTIONS - US 23
STA. 692+00.00 TO STA. 693+00.00

DEL-23-13.17

36
103

ms consultants, inc.




SEEDING		END AREA		VOLUME		CALCULATED	CHECKED
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	DWH	RDW
22		28	1	43	1		
0		18	0	35	0		
0		19	0	38	0		
0				116	1		

CROSS SECTIONS - US 23
STA. 695+00.00 TO STA. 696+00.00

DEL-23-13.17


38
103



SEEDING		END AREA		VOLUME		CALCULATED DWH	CHECKED RDW
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL		
17		31	1				
89				56	2		
15		29	1				
67				50	2		
8		24	1				
44				48	2		
200				154	6		

CROSS SECTIONS - US 23
STA. 696+50.00 TO STA. 697+50.00

39
103





SEEDING		END AREA		VOLUME		CALCULATED	CHECKED
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	DWH	RDW
19		33	0				
128			80	0			
26		53	0				
139			86	2			
23		40	2				
111			66	3			
378			232	5			

CROSS SECTIONS - US 23
STA. 698+00.00 TO STA. 699+00.00

40
103

DEL-23-13.17






SEEDING		END AREA		VOLUME		CALCULATED	CHECKED	RDW
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL			
32		136	2	230	17			
194								
38		112	16	184	21			
150								
14		86	6	72	5			
35		86	6					
14								
379				486	43			

CROSS SECTIONS - SANDUSKY STREET
STA. 302+50.00 TO STA. 303+50.00

DEL-23-13.17


42
103



SEEDING		END AREA		VOLUME		CALCULATED DWH	CHECKED RDW
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL		
59		188	11				
234				353	10		
25		193	0				
222				331	6		
55		165	6				
244				277	6		
700				961	22		


CROSS SECTIONS - SANDUSKY STREET
STA. 304+00.00 TO STA. 305+00.00

43
103



CROSS SECTIONS - SANDUSKY STREET
STA. 305+50.00 TO STA. 306+50.00


DEL-23-13.17



CROSS SECTIONS - SANDUSKY STREET
STA. 307+00.00 TO STA. 308+00.00


DEL-23-13.17





CROSS SECTIONS - SANDUSKY STREET
STA. 310+00.00 TO STA. 310+50.00

DEL-23-13.17



SUPERELEVATION TABLE

P.I. Station 311+33.35

$$D_C = 49^\circ 49' 21''$$
[illegible]

SUPERELEVATION TABLE

[illegible]


SUPERELEVATION TABLE
SANDUSKY STREET

DEL-23-13.17

$$\frac{49}{103}$$

Calculated	Observed
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100


CHECKED



CURVE DATA FOR RADIUS RETURNS

EDGE OF PAVEMENT

- (R1) RAD. PT.: SANDUSKY ST. STA. 302+63.32, 55.00' LT. = PENNSYLVANIA AVE. STA. 203+33.12, 50.32' LT.
 $\Delta = 89^\circ 38' 10''$
 $R = 35.00'$
 $L = 54.76'$
- (R2) RAD. PT.: SANDUSKY ST. STA. 302+50.09, 38.00' RT. = US 23 RAMP STA. 100+59.41, 39.60' LT.
 $\Delta = 110^\circ 20' 33''$
 $R = 20.00'$
 $L = 38.52'$



LEGEND

(XXX.XX) EXISTING ELEVATIONS

<XXX.XX> PROPOSED ELEVATIONS (NON-TYPICAL)

[XXX.XX] PROPOSED ELEVATIONS (PER PROFILE GRADE AND TYPICAL CROSS SLOPE)

NOTE: FOR TOP OF TYPE 2 CURB ELEVATIONS, ADD 0.33' TO EOP ELEVATION SHOWN.


FOR TOP OF TYPE 6 CURB ELEVATIONS, ADD 0.50' TO EOP ELEVATION SHOWN.

LEGEND

(XXX.XX) EXISTING ELEVATIONS
<XXX.XX> PROPOSED ELEVATIONS (NON-TYPICAL)
[XXX.XX] PROPOSED ELEVATIONS (PER PROFILE GRADE AND TYPICAL CROSS SLOPE)

NOTE: FOR TOP OF TYPE 2 CURB ELEVATIONS, ADD 0.33' TO EOP ELEVATION SHOWN.

[Symbol] POST CONSTRUCTION BMP
[Symbol] VEGETATED BIOFILTER
[Symbol] BOTTOM OF DITCH WIDTH = 7.0'



CURVE DATA (ALIGNMENT)

US 23
P.I. Sta. 693+80.16
 $\Delta = 4^\circ 40' 32''$ (LT)
 $D_c = 0^\circ 28' 00''$
 $R = 12,277.67'$
 $T = 501.23'$
 $L = 1,001.91'$
 $E = 10.23'$
 $C = 1,001.63'$
C.B. = N $23^\circ 43' 35''$ W
 $e_{max} = \text{MATCH EXISTING}$

SANDUSKY STREET
P.I. Sta. 311+33.35
 $\Delta = 97^\circ 06' 30''$ (RT)
 $D_c = 49^\circ 49' 21''$ (NDC = $15^\circ 30'$)
 $R = 115.00'$
 $T = 130.23'$
 $L = 194.91'$
 $E = 58.74'$
 $C = 172.40'$
C.B. = N $17^\circ 04' 24''$ E
 $e_{max} = 0.0160$ (NDC = 0.040)

CURVE DATA FOR RADIUS RETURNS


EDGE OF PAVEMENT


[R1] RAD. PT.: US 23 STA. 694+03.73, 101.00' LT.= SANDUSKY ST. STA. 311+18.52, 88.00' RT.
 $\Delta = 130^\circ 08' 39''$
 $R = 70.00'$
 $L = 159.00'$

[R2] RAD. PT.: US 23 STA. 696+53.97, 173.98' LT.= SANDUSKY ST. STA. 311+60.63, 168.00' LT.
 $\Delta = 27^\circ 07' 36''$
 $R = 150.00'$
 $L = 71.02'$


[R3] RAD. PT.: US 23 STA. 695+82.82, 102.91' LT.= SANDUSKY ST. STA. 311+87.18, 84.29' LT.
 $\Delta = 17^\circ 37' 57''$
 $R = 50.00'$
 $L = 15.39'$

[R4] RAD. PT.: US 23 STA. 696+28.80, 192.00' LT.= SANDUSKY ST. STA. 311+49.89, 151.17' LT.
 $\Delta = 27^\circ 07' 36''$
 $R = 150.00'$
 $L = 71.02'$









RESIDENTIAL DRIVE
STA 304+15.75






RESIDENTIAL DRIVE
STA 305+34.49



RESIDENTIAL DRIVE
STA 305+75.30







FLANGE SIZE	A	B	C	D	E	F
3	12	5	4-1/32	3-1/2	6	3/4
4	12	5	5-1/32	4-1/2	6	3/4
6	12	5	7-1/32	6-1/2	6	3/4
8	16	5-1/8	9-1/32	8-1/8	8	3/4
10	20	5-1/2	11-1/16	10-1/4	10	3/4
12	24	5-3/4	13-1/16	12-1/4	12	3/4

FOR OUTLETS 14" AND LARGER THE MANUFACTURER OF THE TAPPING VALVE MUST BE SPECIFIED TO ASSURE PROPER ALIGNMENT RECESS DIMENSION.
SIZE ON SIZE TAPPING SLEEVE REQUIRES 1/2" UNDERSIZE CUTTER TO ASSURE PROPER CUTTER CLEARANCE AND COMPLETE SEVERANCE OF THE COUPON ON NOMINAL PIPE SIZE 7.45 AND SMALLER DIMENSION D IS 6-1/8"





STANDARD DETAIL

SIZE OF PIPE	DEGREE OF BEND											
	11 1/4°				22 1/2°				45°			
	L	W	H	V c.f.	L	W	H	V c.f.	L	W	H	V c.f.
3"	12	18	12	1.5	13	25	16	3.0	18	30	19	5.9
4"	12	24	16	2.6	16	30	18	5.0	22	36	24	11.0
6"	12	48	18	6.0	15	43	36	13.4	30	55	24	22.9
8"	12	63	24	10.5	18	57	34	20.2	36	57	33	39.2
12"	20	54	36	22.6	37	62	37	49.0	48	62	51	87.9
16"	31	65	38	44.3	60	65	39	88.1	65	65	65	159.2
20"	45	70	40	72.8	56	70	60	136.2	72	76	78	247.0
24"	41	72	54	92.3	67	74	69	198.0	88	84	84	359.1


NOTES:

- BACKER TO BE CENTERED HORIZONTALLY IN BEND.
- A LAYER OF POLYETHYLENE SHEETING REQUIRED BETWEEN CONCRETE AND WATERLINE, VALVES, ETC.



SECTION A-A

PLAN VIEW



NOTES:


- DIMENSIONS SHALL BE VARIED AS DIRECTED TO SUIT MAKE OF VALVE FURNISHED.
- WIDTH SHALL BE AS REQUIRED TO ALLOW ACCESS TO BOLTS. (6" MIN.)
- T = 6" MINIMUM
- A LAYER OF POLYETHYLENE SHEETING REQUIRED BETWEEN CONCRETE AND WATERLINE, VALVES, ETC.



STANDARD DETAIL

SIZE OF PIPE	DEGREE OF BEND											
	11 1/4°			22 1/2°			45°			90°		
	L	D	V c.f.	L	D	V c.f.	L	D	V c.f.	L	D	V c.f.
3"	4	3	0.1	6	4	0.2	10	4	0.3	10	4	0.3
4"	5	4	0.2	9	5	0.4	14	5	0.6	14	5	0.6
6"	8	6	0.5	12	7	0.7	20	8	1.4	18	9	1.7
8"	9	8	0.7	16	9	1.4	24	12	2.7	25	11	4.0
12"	14	12	1.8	24	14	3.6	36	18	6.8	32	18	10.7
16"	18	16	3.4	32	18	6.7	36	32	13.4	41	26	25.4
20"	25	20	6.4	30	30	11.5	49	36	20.5	50	32	46.5
24"	27	24	9.0	39	34	18.4	60	42	35.0	58	40	77.7

STEEL WILL BE USED AS REQUIRED BY ENGINEER




NOTES:

- BACKER DESIGNED FOR 3000 PSF SOIL BEARING.
- CONCRETE TO BE PLACED AGAINST UNDISTURBED EARTH.
- A LAYER OF POLYETHYLENE SHEETING REQUIRED BETWEEN CONCRETE AND WATERLINE, VALVES, ETC.



STANDARD DETAIL




MAIN LINE	DIMENSION "L" (MINIMUM)
6"	35"
8"	36"
12"	39"
16"	42"

NOTES:

- FIRE HYDRANT SHALL HAVE A MAXIMUM BURY DEPTH OF 7'-0".
- MODIFICATION OF THE HYDRANT LEAD TO MEET THIS REQUIREMENT SHALL BE MADE IN THAT SECTION DETAIL THE VALVE TO THE HYDRANT AS PER STANDARD DETAIL WTRD-10.
- FIRE HYDRANTS SHALL BE SET A MINIMUM OF 6'-0" FROM ALL DRIVEWAY OPENINGS.
- A LAYER OF POLYETHYLENE SHEETING REQUIRED BETWEEN CONCRETE AND WATERLINE, VALVES, ETC.



STANDARD DETAIL




STANDARD DETAIL


WATER LINE NOTES



- 1 ALL WATER LINES, FITTINGS AND APPURTENANCES SHALL BE INSTALLED IN ACCORDANCE WITH THE SPECIFICATIONS CONTAINED WITHIN THE ODOT CMS 2013 VERSION, EXCEPT AS MODIFIED WITHIN THE CITY OF DELAWARE GENERAL NOTES, STANDARD DRAWINGS AND INFRASTRUCTURE DESIGN MANUAL.
- 2 ANY ACTIVITY RELATED TO THE MODIFYING, UPGRADING, OR EXPANDING THE PUBLIC WATER SYSTEM MUST HAVE PRE-APPROVAL OF THE DEPARTMENT OF ENGINEERING SERVICES AND UTILITY DEPARTMENT. WORK REQUIRING THE SHUTDOWN OF EXISTING WATER MAINS IS TO BE COORDINATED WITH THESE TWO DEPARTMENTS FORTY-EIGHT HOURS PRIOR TO THE SCHEDULED WORK BEING PERFORMED. ALL EFFECTED CUSTOMERS SHALL BE NOTIFIED, IN WRITING, BY THE CONTRACTOR AT LEAST TWENTY-FOUR HOURS PRIOR TO SHUT DOWN. CITY APPROVAL OF ALL CUSTOMER NOTIFICATIONS IS REQUIRED IN ADVANCE OF DISTRIBUTION.
- 3 WATER MAINS SHALL BE DUCTILE IRON PIPE, CLASS 53 FOR SIZES 3" TO 10" AND CLASS 54 FOR SIZES 12" TO 48" (AWWA C151) WITH CEMENT MORTAR LINING AND SEAL COATING (AWWA C104) IN ACCORDANCE WITH CITY SPECIFICATIONS, UNLESS CALLED OUT OTHERWISE BY THESE PLANS. JOINTS MUST BE RUBBER GASKET PUSH-ON MECHANICAL (AWWA C111). WATER MAIN FITTINGS MUST BE DUCTILE IRON WITH CEMENT MORTAR LINING AND SEAL COATING WITH MECHANICAL JOINTS AND MUST CONFORM TO AWWA C153, UNLESS SPECIFIED OTHERWISE BY THESE PLANS. JOINT RESTRAINTS MUST BE PER THE APPROVED PLANS.
- 4 ALL PIPING 2" OR LESS IN DIAMETER BETWEEN THE WATER MAIN AND THE CONTROL VALVE OR METER PIT SHALL BE TYPE K, SOFT TEMPERED COPPER TUBING CONFORMING IN ALL RESPECTS TO ASTM B88. FITTINGS SHALL BE FORD OR MUELLER HIGH QUALITY COPPER BRASS WITH AWWA APPROVED COMPRESSION TYPE JOINTS. THERE WILL BE NO FITTINGS PERMITTED BETWEEN THE WATER MAIN CONNECTION AND THE CONTROL VALVE.
- 5 DEAD-END WATER LINES SHALL TERMINATE WITH A FIRE HYDRANT AND WATCH VALVE FOLLOWED BY A MAIN LINE VALVE AND AN ADDITIONAL SECTION OF WATER LINE PLUGGED AND BLOCKED PER THE STANDARD DRAWINGS.
- 6 WATER LINES SHALL BE INSTALLED WITH A MINIMUM OF 4'-0" OF COVER MEASURED FROM THE FINISHED GRADE TO THE TOP OF THE WATER MAIN, OR AS INDICATED ON THE APPROVED CONSTRUCTION PLANS.
- 7 ALL MAIN LINE VALVES, HYDRANT WATCH VALVES, CURB BOXES, AND DEAD END LINES ARE TO BE MARKED WITH A 4"X 4"X 10'-0" PRESSURE TREATED WOOD WYE-POLE PROJECTING 4'-0" ABOVE THE FINISHED GRADE AND WITH THE TOP 1'-0" PAINTED BLUE ON FOUR SIDES. POSTS ARE TO BE MAINTAINED UNTIL THE AREA IS HAS UNDERGONE FINAL GRADING AND SEEDING. THE COST SHALL BE INCLUDED IN THE VARIOUS WATER ITEMS.
- 8 IF THERE ARE ANY CONFLICTS IN GRADE BETWEEN WATER LINE AND SEWERS, THE WATER LINES SHALL BE LOWERED DURING CONSTRUCTION.
- 9 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE HORIZONTAL AND VERTICAL DEFLECTIONS OR BEND IN THE WATER LINE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. WATER LINES ARE TO MAINTAIN 1'-6" VERTICAL, AND 10'-0" HORIZONTAL CLEARANCE FROM SANITARY SEWERS AND STORM SEWERS.
- 10 PRIOR TO MAKING A CONNECTION TO THE PUBLIC WATER SYSTEM, THE CONTRACTOR SHALL COORDINATE ANY NECESSARY OPERATION OF THE PUBLIC WATERLINE VALVES DIRECTLY WITH THE DEPARTMENT OF PUBLIC UTILITIES.
- 11 THE WATER SERVICE TAPS SHALL CONSIST OF ALL PIPE, VALVES, FITTINGS, AND APPURTENANCES NECESSARY TO CONNECT TO THE PUBLIC WATER MAIN AND COMPLETE THE INSTALLATION ACCORDING TO THE STANDARDS SET FORTH IN THE APPROVED CONSTRUCTION PLANS.
- 12 THE VALVE COVERS AND INSIDE OF ALL MAINLINE WATER VALVE BOXES SHALL BE PAINTED BLUE, AND THE VALVE COVERS AND INSIDE OF ALL FIRE HYDRANT WATCH VALVE BOXES SHALL BE PAINTED RED WITH 2 COATS OF RUST INHIBITIVE PAINT. PUBLIC FIRE HYDRANTS ARE TO BE PAINTED WITH TWO COATS OF FEDERAL SAFETY YELLOW. PRIVATE FIRE HYDRANTS ARE TO BE PAINTED FEDERAL SAFETY RED, WITH WHITE BONNETS AND NOZZLE COVERS.
- 13 ALL MECHANICAL FASTENERS, BOLTS, ALL THREAD ROD, ETC. ARE TO RECEIVE ONE COAT OF RUST INHIBITIVE PAINT OR COATING.
- 14 IF THE TOP OF THE VALVE OPERATING NUT IS MORE THAN 36" BELOW FINISHED GRADE, AN EXTENSION STEM SHALL BE FURNISHED TO BRING THE TOP OF THE OPERATING NUT TO WITHIN 24" OF FINISHED GRADE ELEVATION. ALL VALVE STEM EXTENSIONS ARE TO BE INSTALLED WITH THE EXTENSION SECURED DIRECTLY TO THE VALVE OPERATING NUT WITH GALVANIZED BOLTS.
- 15 WATER LINE SHALL NOT BE INSTALLED IN ANY TRENCH FILLED WITH WATER. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF DEWATERING OPERATIONS REQUIRED FOR THE CONSTRUCTION OF THE WATER LINE.
- 16 ALL FITTINGS SHALL BE ADEQUATELY RESTRAINED WITH SOLID OR POURED IN PLACE CONCRETE BLOCKING PER THE CITY STANDARD DRAWINGS. ALL FITTINGS TO BE BACKED MUST BE THOROUGHLY WRAPPED IN PLASTIC SHEETING PRIOR TO PLACING CONCRETE.
- 17 FIRE HYDRANTS SHALL MEET AWWA STANDARDS AND ARE TO BE MUELLER "SUPER CENTURION 250" A-423 OR "CLOW MEDALLION" ON TYPE "A" SETTING WITH NATIONAL STANDARD THREADS FOR THE 2-1/2" HOSE NOZZLES AND WATCH VALVE DIRECTLY MOUNTED TO ANCHOR TEE. TYPE "B" SETTINGS SHALL NOT BE USED UNLESS APPROVED BY THE CITY. ALL PIPING BETWEEN THE WATCH VALVE AND HYDRANT SHALL BE MECHANICAL JOINT FITTINGS. THE CONNECTION TO THE HYDRANT SHALL BE A 5" STORTZ FITTING WITH A QUICK RELEASE LOCKING COUPLING. ALL SAFETY CHAINS ARE TO BE REMOVED FROM HYDRANTS.
- 18 ALL FIRE DEPARTMENT CONNECTIONS (STANDPIPES) SHALL HAVE A 45° DOWNTURN FITTING TO REDUCE KINKING IN THE FIRE HOSE. THE CONNECTION TO THE STANDPIPE SHALL BE A 5" STORTZ FITTING WITH A LOCKING COUPLING.
- 19 ALL NEW MAIN LINE AND HYDRANT WATCH VALVES ARE TO BE DIRECTLY BOLTED TO THE ANCHOR TEE WITH ANCHOR TYPE FITTINGS.
- 20 THE INSTALLATION OF 3/4" AND 1" WATER TAPS SHALL BE MADE BY DIRECT TAP ONLY. DIRECT TAPS ARE NOT PERMITTED TO ANY ASBESTOS MAINS. 1 1/2" AND 2" WATER TAPS SHALL BE MADE WITH A FORD STYLE FC-202. 3" AND 4" WATER TAPS SHALL BE MADE WITH A FORD STYLE FS-202. 6" WATER TAPS AND LARGER SHALL BE MADE WITH A FORD FTSS TAPPING SLEEVE. A JCM 432 IS AN APPROVED EQUAL.



- 22 VALVE BOXES ARE TO BE TYLER 6850 SERIES CAST IRON 2-PIECE SCREW TYPE FOR MAIN AND WATCH VALVES AND TYLER 6500 SERIES CAST IRON 2-PIECE SCREW TYPE SERVICE BOXES FOR CURB VALVES. STAR PIPE PRODUCTS 2-PIECE SCREW TYPE VALVE BOX ITEM CODE VB5645 39-50 APPROVED.
- 23 FOR WATER SERVICE TAPS; THE WATER MAIN CONNECTION SHALL BE MADE USING A MUELLER 300 BALL TYPE B-25008 OR FORD FB1000-Q BALL CORP CORPORATION STOP. CONTROL VALVES SHALL BE MUELLER 300 BALL CURB VALVE B-25209 OR FORD B44-Q BALL VALVE CURB STOPS (QUARTER TURN ONLY).
- 24 WATER SERVICE BOXES ARE TO BE INSTALLED IN PAIRS ALONG PROPERTY LINES, SET 8'-0 APART AND 2'-0 OUTSIDE OF THE RIGHT OF WAY LINE. A MINIMUM BURY DEPTH OF 48" BELOW TOP OF CURB MUST BE MAINTAINED FOR ALL WATER SERVICES IN THE RIGHT OF WAY.
- 25 ALL WATER LINES SHALL BE TESTED (AWWA 600) AND STERILIZED (AWWA C651) BY THE CONTRACTOR AT HIS EXPENSE IN ACCORDANCE WITH THE CITY AND AWWA SPECIFICATIONS. TESTING SHALL BE DONE UNDER THE SUPERVISION OF THE DEPARTMENT OF ENGINEERING SERVICES.
- 26 ALL METERS (OTHER THAN STANDARD 5/8" X 3/4" RESIDENTIAL METER) AND ALL BACKFLOW DEVICES SPECIFIED FOR THIS PROJECT MUST BE DELIVERED TO THE CITY DEPARTMENT OF PUBLIC UTILITIES FOR INSPECTIONS AND APPROVAL PRIOR TO INSTALLATION.
- 27 METER PITS, INCLUDING ALL PIPING, FITTINGS, EQUIPMENT, AND APPURTENANCES, MUST BE APPROVED BY THE CITY THROUGH A SCHEDULED FIELD INSPECTION DURING THE INSTALLATION. THE DEPARTMENT OF PUBLIC UTILITIES IS RESPONSIBLE FOR INSPECTING THE DOMESTIC WATER METER PIT, DOMESTIC WATER LINE, AND ASSOCIATED APPURTENANCES. THE DEPARTMENT OF PLANNING AND COMMUNITY DEVELOPMENT IS RESPONSIBLE FOR THE INSPECTION OF: THE FIRE LINE, THRUST BLOCKS FOR THE FIRE LINE, METER PIT-FIRE LINE CONNECTION, FIRE DEPARTMENT CONNECTION, AND VALVE MONITORING. PRIOR TO BURYING THE WATER SERVICE, THE APPROPRIATE DEPARTMENT REPRESENTATIVE SHALL BE CONTACTED BY THE CONTRACTOR TO ARRANGE FOR THE REQUIRED INSPECTION OF EACH PORTION OF THE SERVICE. FAILURE TO HAVING THE INSPECTION PERFORMED WILL RESULT IN HAVING TO UNCOVER THE SERVICE FOR INSPECTIONS AT CONTRACTOR EXPENSE.
- 28 THE PRESSURE REQUIRED TO PERFORM HYDROSTATIC TESTING ON WATER LINES IS 150 PSI FOR DOMESTIC LINES AND 200 PSI FOR FIRE SUPPRESSION LINES (PER NFPA 13).
- 29 THE CONTRACTOR AT HIS EXPENSE, SHALL CLEAN ALL WATER MAINS 12" AND LARGER BY PASSING A PROPERLY SIZED POLY PIG THROUGH THE PIPE.
- 30 ALL MECHANICAL JOINTS WITHIN THE METER VAULT SHALL INCLUDE FACTORY MANUFACTURED FLANGES. NO UNI-FLANGES ARE PERMITTED. ALL JOINTS AND FITTINGS LOCATED ON THE SUPPLY SIDE WITHIN 20-FEET OF THE METER VAULT SHALL BE RESTRAINED USING APPROVED MECHANICAL JOINT RESTRAINTS.

WATER SERVICE TAP TRANSFERRED











PLOT.CEL
ms consultants, inc.
msconsultants.com
Ohio DOT Worksheet
DEL 23
UCF: ohioVBI
PCF: 60-06655-Columbus
Batchplot Spec: \\0330share\in\60\06655\standards\plotdrv\batchplot.spc
Pen Table: S:\std\plotting\usn\VB\pen\VB\ms_std.tbl
Plot Driver: S:\std\plotting\usn\VB\PDF\pdfcrg
View: FENCE - VIEW1
Printed: 10/8/2015 @ 4:26:26 PM By: hrendlinger
File: \\0330share\in\60\06655\roadway\Sheets\06655\06001.dgn
Model: Sheet
34" x 22"




NORMAL SECTIONS



50" BARRIERS - TYPICAL SECTIONS

- LEGEND
- 1 1" Radius or 3/4" chamfer.
 - 2 Permissible 10" radius.
 - 3 Permissible 1" radius.
 - 4 No. 8 epoxy coated deformed steel bars, 12" long, spaced 4' between successive bars on a staggered (except Type D) pattern. Omit dowels when top is constructed integral with the base.



BARRIER ELEVATIONS

NOTES

JOINTS: Unsealed contraction joints spaced at 20' max. shall be constructed throughout the run of Concrete Barrier except that expansion joints shall be used at the center line of and around each bridge pier column and on either side of overhead sign supports, inlets and light pole foundations. If inlet top is slip formed, the expansion joints adjacent to it may be omitted.

Contraction joints may be constructed with metal inserts inside the forms, preformed full width joint filler, a grooving tool, or by sawing. Inserts, tooled or sawed joints shall have a 3" minimum depth. All joints shall be constructed for the full height of the barrier including the base. Sawing shall be done as soon as curing will allow, to prevent spalling.

BASE JOINTS: The vertical walls between the barrier base and a concrete pavement or concrete base shall be provided with a sealed, grooved joint as shown on Std. Const. Dwg. BP-2.1. Sealing material shall conform with CMS 705.04.

P.C.J. = Permissible Construction Joint

MEASUREMENT: 622 Concrete Barrier, including transitions and pier sections as per Standard Const. Drawing MC-9.4, is paid for in linear feet as one of the four types (A, B, C or D) or as Type A50 and B50, (for 50" high barrier), with appropriate deductions for other items such as:

604 I-3 Median Inlet	20 Lin. Ft.
625 Light pole foundation or pullbox	2.5 Lin. Ft.
630 Overhead sign support foundation	10 Lin. Ft.
630 Barrier wall assembly	10 Lin. Ft.

50 INCH HIGH BARRIER shall be built in locations specified in the plans. Construct the lower 32" of the barrier and the barrier base using the same dimensions as shown in the corresponding Normal Section. The upper 18" may be constructed integral with the bottom, or separately with No. 4 rebar dowels at 4' foot maximum spacing. Start and end dowels 6" from barrier contraction joints.

RACEWAY: The contractor shall insure that the electrical raceway is clear of internal obstructions. Cost of the 4 inch polyvinyl chloride raceway and No. 10 AWG copper-clad, or aluminum-clad wire if needed for future installation of circuits shall be included in the unit cost per linear foot for item 622, Concrete Barrier.

STATION MARKING shall be impressed in the "green" concrete on both sides at the top of the barrier if specified in the plans, which cost shall be incidental to the unit cost per linear foot bid for item 622, Concrete Barrier.



ITEM 632 - COMBINATION SIGNAL SUPPORT, TYPE
TC-81.21, (BY DESIGN), AS PER PLAN

THIS ITEM SHALL BE AS PER 632 AND 730 EXCEPT THE POLE AND MAST ARM SHALL BE POWDER COATED BLACK BY THE MANUFACTURER. A PAINT CHIP SHALL BE SUBMITTED TO THE DEPARTMENT OF ENGINEERING SERVICES FOR FINAL APPROVAL.

PAYMENT WILL BE MADE AT THE CONTRACT UNIT PRICE AND WILL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND OTHER INCIDENTALS NECESSARY FOR SIGNAL SUPPORT FURNISHED, IN PLACE, COMPLETE AND ACCEPTED.

ITEM 632 - SIGNAL SUPPORT, MECHANICAL DAMPER FOR
TC-81.21 MAST ARM (GREATER THAN 59' IN LENGTH), AS
PER PLAN

THIS ITEM SHALL CONSIST OF THE CONTRACTOR INSTALLING A TUNED MECHANICAL STOCKBRIDGE OR MASSSPRING TYPE DAMPER ON A TC-81.21 MAST ARM SIGNAL SUPPORT TO REDUCE THE POSSIBILITY OF HARMONIC VIBRATIONS CAUSED BY WIND LOADS. A MECHANICAL DAMPER SHALL BE APPLIED TO ALL MAST ARMS OVER 59 FEET IN LENGTH. THE INSTALLED DAMPER SHALL BE CAPABLE OF REDUCING THE LOADED MAXIMUM VERTICAL MOVEMENT AT THE TIP OF THE ARM TO 8 INCHES MEASURED FROM THE HIGHEST TO THE LOWEST POINT OF DEFLECTION AT WIND SPEEDS OF 5-20 MPH.

ALL ATTACHMENT HARDWARE CONNECTIONS SHALL BE STAINLESS STEEL. STOCKBRIDGE-TYPE DAMPERS SHALL HAVE A STAINLESS STEEL SAFETY CHAIN ANCHORED TO THE MAST ARM TO PREVENT WEIGHTS FROM FALLING SHOULD THEY BECOME SEPARATED FROM THE REST OF THE ASSEMBLY. THE DAMPER SHALL BE ATTACHED TO THE ARM WITHIN 8 FEET OF MAST ARM TIP. INSTALLATION SHALL BE PER THE MANUFACTURER'S GUIDELINES. STATIC DAMPERS SUCH AS HORIZONTAL FLAT SIGN MOUNTINGS SHALL NOT BE USED. ACCEPTABLE DEVICES INCLUDE THE FOLLOWING OR APPROVED EQUAL:

1. UNION METAL ALCOA DAMPER DEVICE DWG. NO.
2G-1817-C1
2. VALMONT STRUCTURES ALCOA DEVICE DWG. NO.
OHIO4242P1
3. FLORIDA DOT SPRING-MASS DAMPER DRAWING INDEX
NO. 17749

PAYMENT FOR IEM 632 "SIGNAL SUPPORT, MECHANICAL DAMPER FOR TC-81.21 MAST ARM (GREATER THAN 59' IN LENGTH), AS PER PLAN" SHALL BE MADE AT THE CONTRACT UNIT PRICE PER EACH COMPLETE AND IN PLACE, AND SHALL INCLUDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO COMPLETE THE WORK.

ITEM 633 - CONTROLLER UNIT, TYPE TS2/A2, WITH
CABINET TYPE TS2, AS PER PLAN

THE ELECTRICAL CONTROL EQUIPMENT PROVIDED SHALL MEET THE FOLLOWING SPECIFICATION AND BE MANUFACTURED BY EAGLE TRAFFIC CONTROL SYSTEMS. THE EQUIPMENT PROVIDED AS PART OF THIS CONTRACT SHALL BE THE LATEST MODEL CURRENTLY UNDER PRODUCTION AND NEW. THE CONTROLLER CABINET AND ACCESSORIES SHALL MEET THE NEMA TS2 STANDARD FOR ACTUATED CONTROLLER UNITS. THE CABINET SHALL BE A 36-INCH WIDE "M" CABINET. THE CABINET SHALL BE ALUMINUM, WITH THE NATURAL ALUMINUM FINISH INSIDE AND THE OUTSIDE SHALL BE POWDER COATED BLACK TO MATCH THE COLOR OF THE SIGNAL SUPPORTS. A PAINT CHIP SHALL BE SUBMITTED TO THE DEPARTMENT OF ENGINEERING SERVICES FOR FINAL APPROVAL. THE LOAD BAY SHALL BE THE TF5012 OR NEWER, WITH 12 LOAD SWITCH POSITIONS AND 12 LOAD SWITCHES PROVIDED (UNUSED LOAD SWITCHES SHALL BE IN A SEPARATE BOX IN THE CABINET). EACH LOAD SWITCH SHALL HAVE LIGHT EMITTING DIODES (LEDs) FOR THE CONTROLLER OUTPUT AND LOAD SWITCH OUTPUT, 8 FLASH RELAY POSITIONS (UNUSED FLASH RELAY SHALL BE IN A SEPARATE BOX IN THE CABINET), ONE NEMA 2-CIRCUIT FLASHER AND A MALFUNCTION MANAGEMENT UNIT (EBERLY DESIGN MMU16LE).

THERE SHALL BE NO LAG LEFT OPERATION. PHASE OMIT SHALL BE ACHIEVED THROUGH OMITTED CALL PROGRAMMING TO PREVENT A LAG LEFT SIGNAL OPERATION.

A POWER BACK/BC 100 UPS BATTERY BACKUP CABINET
PBM-2000ITS UPS MODULE IS TO BE INSTALLED PER ODOT
SPECIFICATIONS. THE BATTERY BACKUP SHALL BE PAID FOR
SEPARATELY.

A GENERATOR POWER PANEL AND ENCLOSURE SHALL BE MOUNTED ON THE OUTSIDE OF THE UPPER SECTION OF THE CONTROLLER CABINET, ON THE SAME SIDE AS THE CIRCUIT BREAKERS. THE STANDARD DRAWING FOR THE GENERATOR POWER PANEL IS INCLUDED IN THIS PLAN AND SHALL MEET THOSE SPECIFICATIONS.

THE POLICE PANEL ON THE INSIDE OF THE CABINET DOOR SHALL HAVE VEHICLE DETECTOR AND PEDESTRIAN DETECTOR PUSH BUTTONS TO CALL PHASES 1 TO 8 INDIVIDUAL, A STOP TIMING SWITCH, CABINET LIGHT SWITCH, AND AN AUTO FLASH SWITCH SHALL ALSO BE SUPPLIED ON THE POLICE PANEL ON THE OUTSIDE OF THE CABINET DOOR.

A CABINET DOOR OPEN SWITCH AND A CABINET LIGHT ON/OFF SWITCH SHALL ALSO BE SUPPLIED.

THE CONTROLLER SHALL HAVE A LIQUID CRYSTAL DISPLAY WITH ADJUSTABLE BACKLIGHT. THE DISPLAY SHALL BE OF SUFFICIENT SIZE TO DISPLAY A MINIMUM OF FOUR (3) LINES OF TEXT WITH A MINIMUM OF 20 CHARACTERS PER LINE. THE DISPLAY SHALL BE READABLE IN DIRECT LIGHT OR DARKNESS.

THE FOLLOWING INFORMATION SHALL BE ON ALL LABELS IN THE CONTROLLER CABINET TO IDENTIFY THE WIRING FUNCTIONS:

LOOP DETECTOR LEAD-IN CABLE: PHASE NUMBER SERVICED,
DIRECTION, MOVEMENT TYPE, AND LOOP PLAN NUMBER.
SIGNAL HEAD FIELD WIRING: PHASE NUMBER SERVICED,
DIRECTION, MOVEMENT TYPE AND COLOR (RED YELLOW,
GREEN YELLOW ARROW, GREEN ARROW) OR PEDESTRIAN
MOVEMENT.

THE CONTROLLER TIMER SHALL BE SIEMENS MODEL EPAC M52 WITH INTEGRAL LATEST VERSION SEPAC LOCAL CONTROLLER SOFTWARE AND LATEST VERSION SEMARC MASTER CONTROLLER SOFTWARE AND SHALL HAVE A BUILT-IN EXTERNAL 10 BASE-T ETHERNET PORT WITH CONFIGURABLE IP. EACH CONTROLLER TIMER SHALL HAVE 6 MODES OF COORDINATION, ADAPTIVE TRAFFIC CONTROL, REPORTS, PREEMPTION/PRIORITY, DIAGNOSTICS AND INTERNAL TIME BASE CONTROL.

EACH CONDUIT ENTRANCE TO THE CABINET SHALL BE SEALED WITH A RUBBER PIPE/CONDUIT SEAL GASKET. THE SEAL SHALL BE OF A MATERIAL AND TYPE TIGHTLY FITTING AND ABLE TO SEAL OUT WATER, INSECTS, RODENTS, AND DIRT. THE SEAL SHALL BE EASILY REMOVED FOR SERVICE INSTALLATIONS OR CABLE REPLACEMENTS.

PAYMENT FOR ITEM 633 - CONTROLLER UNIT TYPE TSA/A2, WITH CABINET TYPE TS2 TYPE 1, AS PER PLAN, WILL BE AT THE CONTRACT BID PRICE COMPLETE AND IN PLACE INCLUDING ALL CONNECTIONS TESTED AND ACCEPTED.

ITEM 633 - UNINTERRUPTIBLE POWER SUPPLY (UPS). AS PER PLAN

IT IS THE INTENT OF THESE PLANS THAT A BATTERY
BACKUP SYSTEM BE PROVIDED AND SHALL MEET THE
FOLLOWING:

THE UNIT SHALL BE AN ALPHA TECHNOLOGIES BRAND ALPHA FXM UNINTERRUPTIBLE POWER SUPPLY MODULE FXM 1100, A MEYERS BRAND POWER BACK/BC 100 UPS BATTERY BACKUP CABINET PBM-2000ITS UPS MODULE OR APPROVED EQUAL, IN ALL CASES, THIS ITEM SHALL MEET ODOT SPECIFICATIONS.

A MANUAL BY-PASS/DISCONNECT SWITCH INTERNAL TO THE CABINET SHALL BE INCLUDED.

THE BATTERY BACKUP CABINET SHALL BE ATTACHED TO THE LEFT SIDE OF THE CONTROLLER CABINET (TO THE LEFT OF THE CABINET DOOR), AND THE EXTERIOR OF THE CABINET SHALL MATCH THE COLOR OF THE CONTROLLER CABINET. ALL HOOKUPS, CABLE, ATTACHMENT HARDWARE, AND MISCELLANEOUS MATERIALS FOR BOTH ATTACHING THE CABINETS AND FOR FULL OPERATION OF THE BATTERY BACKUP SYSTEM SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THIS ITEM.

THE BACKUP CABINET SHALL BE MOUNTED ON A FOUNDATION PAD TO MATCH THE HEIGHT ABOVE GRADE OF THE ADJACENT CONTROLLER CABINET. THE WORK PAD IN FRONT OF THE FOUNDATION SHALL MATCH THE 35-INCH DIMENSION FOR THE CONTROLLER WORK PAD. THE FOUNDATION AND WORK PADS SHALL BE PAID SEPARATELY.

PAYMENT SHALL BE MADE AT THE UNIT PRICE BID FOR EACH, COMPLETE AND IN PLACE, ALL CONNECTIONS TESTED AND ACCEPTED.

ITEM 633 - UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN, ALPHA TECHNOLOGIES - ALTERNATE BID

THIS ITEM REPLACES THE ITEM 633 UNINTERRUPTIBLE POWER SUPPLY, AS PER PLAN PER THE ALPHA TECHNOLOGIES SPECIFICATION LISTED BELOW.

THE UNINTERRUPTABLE POWER SUPPLY SHALL MEET ALL
REQUIREMENTS IN THE ALPHA TECHNOLOGIES SPECIFICATION
FOR ALPHA FXM UNINTERRUPTIBLE POWER SUPPLY MODULE
FXM 1100, DOCUMENT 0480013-00 REV D.

PAYMENT FOR ITEM 633 UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN, ALPHA TECHNOLOGIES ALTERNATE BID SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH UNIT, COMPLETE AND IN PLACE INCLUDING ALL REQUIRED CABINET HARDWARE, MOUNTING HARDWARE, PROCESSOR CARD(S), CABLES, CONDUIT, AND CONNECTIONS TESTED AND ACCEPTED, SETUP SUPPORT AND SYSTEM TRAINING.

ITEM 809 - STOP-BAR DETECTION

THIS ITEM OF WORK SHALL CONSIST OF FURNISHING AND INSTALLING A STOP-BAR DETECTION UNIT CAPABLE OF INTERSECTION DETECTION CONTROL UTILIZING ABOVE GROUND DIGITAL WAVE RADAR TECHNIQUES. THE UNIT SHALL BE NONINTRUSIVE AND SHALL DETECT VEHICLES FROM 6 FT. (1.8 M) UP TO 140 FT. (42.7 M) FOR A 90 DEGREE FIELD OF VIEW FROM THE UNIT. THE UNIT SHALL PROVIDE REAL-TIME PRESENCE DATA FOR AT LEAST 10 LANES. THE UNIT SHALL PROVIDE AT LEAST SIXTEEN DETECTION ZONES SIMULTANEOUSLY FOR INTERSECTION CONTROL. ONE UNIT SHALL BE PROVIDED PER APPROACH, WHERE SPECIFIED IN THE PLANS, COVERING MULTIPLE LANES WHERE STOP-BAR DETECTION IS REQUIRED. THE DETECTION UNIT SHALL INCLUDE THE FOLLOWING LIST OF FEATURES AND CAPABILITIES:

- THE UNIT SHALL PROVIDE ACCURATE PRESENCE-DETECTION OF BOTH MOVING AND STOPPED VEHICLES. THE UNIT SHALL BE MOUNTED IN A FORWARD-FIRE OR SIDE-FIRE POSITION, LOOKING AT EITHER APPROACHING OR DEPARTING TRAFFIC AND SHALL ONLY DETECT VEHICLES IN ONE DIRECTION OF TRAVEL.
- THE UNIT SHALL BE TESTED TO MEET NEMA TS2 ENVIRONMENTAL STANDARDS AND MAINTAIN ACCURATE PERFORMANCE IN THE FOLLOWING OPERATING CONDITIONS:
 - * RAIN UP TO 1 IN. (2.5 CM) PER HOUR
 - * FREEZING RAIN
 - * SNOW
 - * WIND
 - * DUST
 - * FOG
 - * CHANGING TEMPERATURE
 - * CHANGING LIGHTING
- THE RADAR DESIGN FOR EACH UNIT SHALL CONFORM TO THE FOLLOWING:
 - * OPERATING FREQUENCY: 24.024.25 GHZ (K-BAND)
 - * MATRIX OF 16 RADARS
 - * NO MANUAL TUNING TO CIRCUITRY
 - * TRANSMITS MODULATED SIGNALS GENERATED DIGITALLY
 - * NO TEMPERATURE-BASED COMPENSATION NECESSARY
 - * BANDWIDTH STABLE WITHIN 1%
 - * PRINTED CIRCUIT BOARD ANTENNAS
 - * ANTENNA VERTICAL 6 DB BEAM WIDTH (TWO-WAY PATTERN): 65 DEGREES
 - * HORIZONTAL FIELD OF VIEW: 90 DEGREES
 - * ANTENNA TWO-WAY SIDELOBES: -40 DB
 - * TRANSMIT BANDWIDTH: 245 MHZ
 - * UN-WINDOWED RESOLUTION: 2 FT. (0.6 M)
 - * RF CHANNELS: 8
 - * SELF-TEST FOR VERIFYING HARDWARE FUNCTIONALITY
 - * DIAGNOSTICS MODE FOR VERIFYING SYSTEM FUNCTIONALITY
- THE UNIT SHALL INCLUDE A SIMPLE SETUP ROUTINE THAT SHALL AUTOMATICALLY CONFIGURE AND CALIBRATE THE UNIT FOR PROPER OPERATION DURING INSTALLATION. THE UNIT SHALL ALSO BE CAPABLE OF BEING PROGRAMMED AND UPDATED FROM A LAPTOP COMPUTER OR OTHER PORTABLE PROGRAMMING DEVICE, SUCH AS A POCKET PC, VIA A LOCAL OR REMOTE ETHERNET CONNECTION USING VENDOR SUPPLIED SOFTWARE. THE SOFTWARE SHALL SUPPORT TCP/IP CONNECTIVITY, UNIT CONFIGURATION BACK-UP AND RESTORE, AND REAL-TIME TRAFFIC VISUALIZATION FOR PERFORMANCE VERIFICATION AND TRAFFIC DISPLAY. THE GRAPHICAL USER INTERFACE SHALL OPERATE ON A WINDOWS PLATFORM.

- THE UNIT SHALL HAVE TWO HALF-DUPLEX RS-485 COMMUNICATION PORTS AND SHALL HAVE THE ABILITY TO UPGRADE FIRMWARE OVER ANY COMMUNICATION PORT.
- THE UNIT SHALL BE CAPABLE OF ETHERNET COMMUNICATION.
- THE UNIT SHALL BE MOUNTED DIRECTLY TO A POLE OR SMALL ARM, AS RECOMMENDED BY THE MANUFACTURER. CABLE(S) SHALL BE PROVIDED AS REQUIRED AND RECOMMENDED BY THE MANUFACTURER.
- SURGE PROTECTION DEVICES, AS RECOMMENDED BY THE MANUFACTURER, SHALL BE INCLUDED BOTH AT THE POLE WHERE THE UNIT IS LOCATED TO PROTECT THE UNIT AND IN THE TRAFFIC CABINET TO PROTECT THE CABINET ELECTRONICS.
- POWER SHALL BE PROVIDED FROM THE TRAFFIC CABINET. THE UNIT SHALL CONSUME LESS THAN 10 WATTS AND OPERATE FROM A DC INPUT BETWEEN 9 VDC AND 28 VDC. COMPLETE AND AUTOMATIC RECOVERY FROM A POWER FAILURE SHALL BE WITHIN 15 SECONDS AFTER RESUMPTION OF NORMAL POWER.
- ALL REQUIRED INPUTS CARDS SHALL BE INCLUDED IN THE TRAFFIC CABINET AND SHALL BE COMPATIBLE WITH CALTRANS, NEMA TS1 AND NEMA TS2 DETECTOR RACKS. THE CARDS SHALL PROVIDE TRUE PRESENCE DETECTOR CALLS OR CONTACT CLOSURE TO THE TRAFFIC CONTROLLER.
- THE MANUFACTURER'S REPRESENTATIVE SHALL BE ON SITE DURING INSTALLATION AND TESTING AND SHALL PROVIDE ONSITE TRAINING ON THE SETUP, OPERATION, AND MAINTENANCE OF THE UNIT.
- THE UNIT SHALL COME WITH A 2-YEAR MANUFACTURER SUPPLIED WARRANTY.
- PRIOR TO PROGRAMMING, THE CONTRACTOR SHALL CONTACT THE CITY OF DELAWARE PROJECT ENGINEER AT 740-203-1700. A CITY ENGINEERING DEPARTMENT REPRESENTATIVE SHALL BE PRESENT DURING THE PROGRAMMING OF THE SYSTEM.

PAYMENT FOR ITEM 809 STOP-BAR DETECTION SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR EACH UNIT, COMPLETE AND IN PLACE INCLUDING ALL REQUIRED CABINET HARDWARE, MOUNTING BRACKETS, CABLES, CONDUIT, AND CONNECTIONS TESTED AND ACCEPTED.

ITEM 633 - CONTROLLER WORK PAD, AS PER PLAN

WORK PADS FOR THE UNINTERRUPTIBLE POWER SUPPLY (UPS) AND CONTROLLER CABINETS SHALL BE AS SHOWN ON THIS SHEET. EXCAVATE A MINIMUM OF 9" BELOW GRADE. PLACE AND COMPACT 6" OF MATERIAL CONFORMING TO 304.02. INSTALL A CAST-IN-PLACE WORK PAD THAT IS A MINIMUM OF 4" THICK.

ITEM 633 - CABINET FOUNDATION. AS PER PLAN

THIS ITEM SHALL PROVIDE A FOUNDATION FOR THE CONTROLLER AND UNINTERRUPTIBLE POWER SUPPLY (UPS) AS SHOWN ON THIS SHEET. THE FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH NEMA CABINET FOUNDATIONS SHOWN ON TC-83.20.

PAYMENT FOR ITEM 633 "CABINET FOUNDATION, AS PER PLAN" SHALL INCLUDE ALL EQUIPMENT, LABOR AND MATERIALS TO INSTALL THE FOUNDATION, INCLUDING CONDUIT ELLS AND ANCHOR BOLTS, RESTORATION OF DISTURBED AREA AND DISPOSAL OF SURPLUS MATERIAL AS POWER CMS 104.04.

ITEM 625 - LUMINAIRE, CONVENTIONAL, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF ODOT'S
CONSTRUCTION AND MATERIAL SPECIFICATIONS, LUMINAIRES
FOR CONVENTIONAL LIGHTING UNITS SHALL BE AS FOLLOWS:


LUMINAIRES FOR CONVENTIONAL LIGHTING UNITS WITH ANIES III-MC DISTRIBUTION AND 250 WATT METAL HALIDE LAMPS SHALL BE AMERICAN ELECTRIC "SERIES 125" COOPER "OVF" (FLAT GLASS), GENERAL ELECTRIC "M-400" (CUTOFF), OR EQUAL AS APPROVED BY THE ENGINEER AND SHALL HAVE A BLACK HOUSING FROM THE MANUFACTURER. THE LUMINAIRE SHALL INCLUDE INDIVIDUAL PHOTOELECTRIC CONTROL.

PAYMENT WILL BE MADE AT THE UNIT BID PRICE FOR EACH CMS ITEM 625, "LUMINAIRE, CONVENTIONAL, AS PER PLAN (250 W MH, 120 VOLT, TYPE III, WITH PE CELL)" FOR EACH LUMINAIRE WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.

ITEM 625 - BRACKET ARM, (BY SIZE), AS PER PLAN

THIS ITEM SHALL BE AS PER 625 AND 713 EXCEPT THE ARM SHALL HAVE A BLACK FINISH AND SHALL BE TREATED AND PAINTED BLACK BY THE MANUFACTURER AS PER ITEM 632 COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, (BY DESIGN), AS PER PLAN.

PAYMENT WILL BE MADE AT THE CONTRACT UNIT PRICE AND WILL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND OTHER INCIDENTALS NECESSARY FOR EACH SUPPORT FURNISH, IN PLACE, COMPLETE AND ACCEPTED.



[illegible]

SHEET NUMBER									PARTICIPATION			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
		71		74		79			01/MPO/ OT		02/MPO/ OT/DEL						
																TRAFFIC SIGNALS	
						39			39			625	25400	39	FT	CONDUIT, 2", 725.04	
						280			280			625	25500	280	FT	CONDUIT, 3", 725.04	
						296			296			625	25900	296	FT	CONDUIT, JACKED OR DRILLED, 3"	
						3			3			625	30706	3	EACH	PULL BOX, 725.08, 24"	
						158			158			625	29000	158	FT	TRENCH	
						4			4			625	32000	4	EACH	GROUND ROD	
						2			2			632	04801	2	EACH	VEHICULAR SIGNAL HEAD, (LED), 1 SECTION, 12" LENS, 1-WAY, AS PER PLAN	65
						5			5			632	04911	5	EACH	VEHICULAR SIGNAL HEAD, (LED) BLACK, 3-SECTION, 12" LENS, 1-WAY, WITH BACKPLATE, AS PER PLAN	65
						1			1			632	04921	1	EACH	VEHICULAR SIGNAL HEAD, (LED) BLACK, 5-SECTION, 12" LENS, 1-WAY, WITH BACKPLATE, AS PER PLAN	65
						8			8			632	25000	8	EACH	COVERING OF VEHICULAR SIGNAL HEAD	
						971			971			632	40700	971	FT	SIGNAL CABLE, 7 CONDUCTOR, NO. 14 AWG	
						3			3			632	64010	3	EACH	SIGNAL SUPPORT FOUNDATION	
						23			23			632	68200	23	FT	POWER CABLE, 2 CONDUCTOR, NO. 6 AWG	
						18			18			632	68300	18	FT	POWER CABLE, 3 CONDUCTOR, NO. 6 AWG	
						1			1			632	70001	1	EACH	POWER SERVICE, AS PER PLAN	65
						3			3			632	77231	3	EACH	SIGNAL SUPPORT, MECHANICAL DAMPER FOR TC-81.21 MAST ARM (GREATER THAN 59' IN LENGTH), AS PER PLAN	66
						1			1			632	81091	1	EACH	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 13, AS PER PLAN	66
						2			2			632	81095	2	EACH	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 14, AS PER PLAN	66
						1			1			633	01551	1	EACH	CONTROLLER UNIT, TYPE TS2/A2, WITH CABINET, TYPE TS2, AS PER PLAN	66
						2			2			633	67000	2	EACH	CABINET RISER	
						1			1			633	67101	1	EACH	CABINET FOUNDATION, AS PER PLAN	68
						1			1			633	67201	1	EACH	CONTROLLER WORK PAD, AS PER PLAN	68
						1			1			633	74001	1	EACH	UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN	66
						1			1			633	67301	1	EACH	PREEMPTION, AS PER PLAN	67
						1			1			809	69000	1	EACH	ADVANCE DETECTION	67
						2			2			809	69100	2	EACH	STOP-BAR DETECTION	68
						1			1			633	74001	1	EACH	UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN, ALPHA TECHNOLOGIES - ALTERNATE BID	60
						1			1			633	67301	1	EACH	PREEMPTION, AS PER PLAN, OPTICOM - ALTERNATE BID	67
						1			1			625	18201	1	EACH	LIGHTING BRACKET ARM, 15', AS PER PLAN	68
						2			2			625	18511	2	EACH	BRACKET ARM, 30', AS PER PLAN	68
						3			3			625	26251	3	EACH	LUMINAIRE, CONVENTIONAL, AS PER PLAN	68
						529			529			632	30980	529	FT	SIGNAL CABLE, 3 CONDUCTOR, NO. 10 AWG	


[illegible]

SHEET NO.	REFERENCE NO.	NOTE: POST LENGTHS WERE CALCULATED WITH A 7' CLEARANCE EXCEPT AS FOLLOWS: EXPRESSWAY SIGNS WITH SECONDARY SIGNS WERE CALCULATED WITH A 6' CLEARANCE - SEE TC-42.20					GROUND MOUNTED SUPPORT, NO. 2 POST FT	GROUND MOUNTED SUPPORT, NO. 3 POST FT	GROUND MOUNTED SUPPORT, NO. 3 POST, AS PER PLAN FT	GROUND MOUNTED SUPPORT, NO. 4 POST FT	SIGN POST REFLECTOR EA	SIGN HANGER ASSEMBLY, MAST ARM EA	SIGN SUPPORT ASSEMBLY, POLE MOUNTED EA	SIGN, FLAT SHEET SQ FT	SIGN, DOUBLE FACED, STREET NAME, AS PER PLAN EA	SIGN, STREET NAME, AS PER PLAN EA	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL EA	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION EA	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL EA	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL EA	REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL EA	REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL EA	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE TC-12.30 EA	CALCULATED MGS CHECKED JML	SIGNING SUBSUMMARY	DEL - 23 - 13.17	72 103																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
		LOCATION	STATION	SIDE	CODE	SIGN SIZE (INCHES)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
75		U.S. 23																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									


SHEET NO.	REFERENCE NO.	NOTE: POST LENGTHS WERE CALCULATED WITH A 7' CLEARANCE EXCEPT AS FOLLOWS: EXPRESSWAY SIGNS WITH SECONDARY SIGNS WERE CALCULATED WITH A 6' CLEARANCE - SEE TC-42.20					630																	
		LOCATION	STATION	SIDE	CODE	SIGN SIZE (INCHES)	GROUND MOUNTED SUPPORT, NO. 2 POST	GROUND MOUNTED SUPPORT, NO. 3 POST	GROUND MOUNTED SUPPORT, NO. 3 POST, AS PER PLAN	GROUND MOUNTED SUPPORT, NO. 4 POST	SIGN POST REFLECTOR	SIGN HANGER ASSEMBLY, MAST ARM	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	SIGN, FLAT SHEET	SIGN, DOUBLE FACED, STREET NAME, AS PER PLAN	SIGN, STREET NAME, AS PER PLAN	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL	REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL	REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE TC-12.30	
							FT	FT	FT	FT	EA	EA	EA	SQ FT	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
77		U.S. 23																						
	S22		694+15	LT	R9-3-18	18" X 18"						1	2.3											
					R9-3-18	18" X 18"							1	2.3										
					R5-10B-30	30" X 18"								1	3.8									
	S23		695+07	RT	R10-12-24	24" X 30"					1		5.0											
	S24		695+07	RT	D3-MOD-12	VAR.					1				1									
	S25		695+10	LT	R9-3-18	18" X 18"						1	2.3											
	S26		695+50	LT	D3-MOD-12	VAR.					1				1									
	S27		695+55	LT	R9-3-18	18" X 18"						1	2.3											
					R9-3-18	18" X 18"								1	2.3									
	S28		696+00	LT	R3-H8CB-48	48" X 30"	13.4/13.5						10.0											
	S29		699+70	LT	R3-H8CB-48	48" X 30"	12.9/13.3						10.0											
	S30	↓	701+50	LT	D1-H1A-120	120" X 24"			13.3/13.6				20.0											
		N. SANDUSKY ST.																						
	S31		309+50	RT	W3-3-30	30" X 30"		14.0					6.3											
	S32		309+50	LT	R2-1-24	24" X 30"	13.0						5.0											
	S33		310+45	LT	W1-8R-18	18" X 24"	12.5			1			3.0											
	S34		310+45	LT	W1-8L-18	18" X 24"	12.5			1			3.0											
	S35		310+62	RT	R3-9DP-24	24" X 6"		14.0					7.0											
					R3-9B-24	24" X 36"																		
	S36		310+77	LT	R3-9CP-24	24" X 6"		14.0					7.0											
					R3-9B-24	24" X 36"																		
	S37		311+12	LT	W1-8R-18	18" X 24"	12.5			1			3.0											
	S38		311+12	LT	W1-8L-18	18" X 24"	12.5			1			3.0											
	S39		311+77	LT	W1-8R-18	18" X 24"	12.5			1			3.0											
	S40		311+77	LT	W1-1L-18	30" X 30"		15.5					8.5											
					W13-1P-18	18" X 18"																		
	S41		312+00	RT	R3-5R-30	30" X 36"		13.5					7.5											
	S42		312+42	RT	R3-2-24	24" X 24"					1		4.0											
	S43	↓	312+42	RT	R10-17A-36	36" X 48"					1		12.0											
											</													

ms consultants, inc.





FOR LEGEND, SEE SHEET 75



FOR LEGEND, SEE SHEET 75

NOTES:

1. FOR SIGNING AND PAVEMENT MARKING SEE SHEET 75.
2. SIGNAL HEADS 1,2,3,4,5,7,8 SHALL BE SUSPENDED BELOW THE MAST ARM.
3. SIGNAL HEAD 6 SHALL BE RIGIDLY MOUNTED TO THE SIGNAL POLE SUCH THAT THE GREEN LENS IS 15' ABOVE THE POLE BASE.
4. WIRELESS COMMUNICATION (ANTENNA AND CABLES) TO BE INSTALLED BY OTHERS.

POLE A COMBINATION SIGNAL SUPPORT

62" ARM & 30' BRACKET ARM
W/ (2)-ADV. RADAR,
(1)-PREEMPT LIGHT
STA. 694+15, 61' LT

(2)-3" CONDUIT
W/ (5)-7/C, (3)-3/C LTG,
(3)-RADAR CABLE,
(1)-PREEMPT RECEIVING
UNIT CABLE,
(2)-PREEMPT LIGHT CABLE,
(1)-ANTENNA CABLE (BY OTHERS)
IN TRENCH = 5'

GROUND MOUNTED CONTROLLER
& UPS CABINETS W/ WORK PAD
STA. 695+55, 83' LT

(1)-2" CONDUIT
W/ (1)-3/C POWER
IN TRENCH = 7'
(BYPASS PULL BOX)

AEP POWER POLE

24" PULL BOX
STA. 695+51, 80' LT

(2)-2" CONDUIT
W/ (2)-7/C, (1)-3/C LTG,
(1)-RADAR CABLE,
(1)-PREEMPT RECEIVING
UNIT CABLE,
(1)-PREEMPT CONFIRM.
LIGHT CABLE,
(1)-ANTENNA CABLE (BY OTHERS)
IN TRENCH = 5'

POLE B COMBINATION SIGNAL SUPPORT

65" MAST ARM & 13' BRACKET ARM
W/ (1)-POLE MTD. POWER SERVICE,
(1)-POLE MTD. SIGNAL HEAD,
(1)-ADV. RADAR,
(1)-PREEMPT RECEIVING UNIT,
(1)-PREEMPT LIGHT,
(1)-ANTENNA (BY OTHERS)
STA. 695+55, 76' LT

POLE C COMBINATION SIGNAL SUPPORT

66" ARM & 30' BRACKET ARM
STA. 695+10, 67' RT

(2)-2" CONDUIT
W/ (2)-7/C, (1)-3/C LTG,
IN TRENCH = 6'

24" PULL BOX
STA. 695+15, 65' RT

(2)-3" CONDUIT
W/ (2)-7/C, (1)-3/C LTG,
JACKED OR DRILLED = 148'

SIGNS

S1

N. Sandusky St.
D3-(MOD)-96

S2

LEFT TURN
YIELD
ON GREEN
R10-12-24

S3

R3-2-24

S4

RIGHT
ON RED
ARROW
AFTER
STOP
R10-17a-30

S5

R9-3-18

TRAFFIC SIGNAL LEGEND

- VEHICULAR SIGNAL HEAD W/TURN ARROW (5 SEC.)
- VEHICULAR SIGNAL HEAD W/TURN ARROW (3 SEC.)
- VEHICULAR SIGNAL HEAD (3 SEC.)
- VEHICULAR SIGNAL HEAD (1 SEC.)
- STOP LINE RADAR DETECTOR
- ADVANCE/DILEMMA RADAR DETECTOR
- PREEMPTION CONFIRMATION LIGHT
- PREEMPTION RECEIVING UNIT
- GROUND MOUNTED CONTROLLER AND UPS CABINETS, W/ WORKPAD
- MAST ARM SIGNAL SUPPORT
- BRACKET ARM W/ LUMINAIRE
- PULL BOX, 725.08
- SIGN SUPPORT



CALCULATED
CHECKED


TRAFFIC SIGNAL PLAN
U.S. 23 & N. SANDUSKY ST.

DEL-23-13.17

VEHICULAR ZONE DETECTORS

ZONE NUMBER	RADAR	SIZE (WXL)	ASSOC. PHASE	DELAY (SEC.)	EXT. (SEC.)	DELAY INHIBITED DURING	LABEL
DZ1	SL1	6'X30'	φ1	4	-	φ1	NBLT
DZ2	SL2	6'X30'	φ1	12	-	φ1	EBRT
DZ3	A1	6'X18'	φ2	-	2	-	SB ADV.

SIGNAL PHASING



SIGNAL TIMING IN SECONDS


TIMING INTERVAL	NBLT/EB	SB				NB		
	φ1	φ2	φ3	φ4	φ5	φ6	φ7	φ8
MIN. GREEN	10	30				-		
VEH. EXTENSION	3	3				-		
MAX. GREEN I	25	60				-		
MAX. GREEN II	-	-				-		
YELLOW CLEAR	4.3	4.5				-		
RED CLEAR	2.0	2.5				-		
WALK	-	-	-	-	-	-	-	-
PED CLEAR	-	-	-	-	-	-	-	-
RECALL	NONE	MAX				MAX		
LOCK/NON-LOCK	NON-LOCK	LOCK				LOCK		

SUBSUMMARY OF TRAFFIC SIGNAL ITEMS

ITEM	QUANTITY	UNIT	ITEM DESCRIPTION	REFERENCE
625	39	FT	CONDUIT, 2", 725.04	
625	280	FT	CONDUIT, 3", 725.04	
625	296	FT	CONDUIT, JACKED OR DRILLED, 3"	
625	3	EA	PULL BOX, 725.08, 24"	
625	158	FT	TRENCH	
625	4	EA	GROUND ROD	
632	2	EA	VEHICULAR SIGNAL HEAD, (LED), 1 SECTION, 12"	
			LENS, 1-WAY, AS PER PLAN	
632	5	EA	VEHICULAR SIGNAL HEAD, (LED), BLACK, 3-SECTION, 12"	
			LENS, 1-WAY, WITH BACKPLATE, AS PER PLAN	
632	1	EA	VEHICULAR SIGNAL HEAD, (LED), BLACK, 5-SECTION, 12"	
			LENS, 1-WAY, WITH BACKPLATE, AS PER PLAN	
632	8	EA	COVERING OF VEHICULAR SIGNAL HEAD	
632	971	FT	SIGNAL CABLE, 7-CONDUCTOR, No. 14 AWG	
632	3	EA	SIGNAL SUPPORT FOUNDATION	
632	23	FT	POWER CABLE, 2-CONDUCTOR, NO. 6 AWG	
632	18	FT	POWER CABLE, 3-CONDUCTOR, NO. 6 AWG	
632	1	EA	POWER SERVICE, AS PER PLAN	
632	3	EA	SIGNAL SUPPORT, MECHANICAL DAMPER FOR TC-81.21	
			MAST ARM (GREATER THAN 59' IN LENGTH)	
632	2	EA	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 14, AS PER PLAN	B,C
632	1	EA	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 13, AS PER PLAN	A
633	1	EA	CONTROLLER UNIT, TYPE TS2/A2, WITH CABINET, TYPE TS2, AS PER PLAN	
633	2	EA	CABINET RISER	
633	1	EA	CABINET FOUNDATION, AS PER PLAN	
633	1	EA	CONTROLLER WORK PAD, AS PER PLAN	
633	1	EA	UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN	
633	1	EA	PREEMPTION, AS PER PLAN	
809	1	EA	ADVANCE DETECTION	
809	2	EA	STOP-BAR DETECTION	
633	1	EA	UNINTERRUPTIBLE POWER SUPPLY (UPS), AS PER PLAN, ALPHA TECHNOLOGIES - ALTERNATE BID	
633	1	EA	PREEMPTION, AS PER PLAN, OPTICOM - ALTERNATE BID	


LIGHTING ITEMS

625	1	EA	BRACKET ARM, 15', AS PER PLAN	
625	2	EA	BRACKET ARM, 30', AS PER PLAN	
625	3	EA	LUMINAIRE, CONVENTIONAL, AS PER PLAN	
633	529	FT	SIGNAL CABLE, 3 CONDUCTOR, NO. 10 AWG	




LEGEND

- VEHICULAR SIGNAL HEAD (1 SEC.)
- VEHICULAR SIGNAL HEAD (3 SEC.)
- VEHICULAR SIGNAL HEAD W/ TURN ARROWS (3 SEC.)
- VEHICULAR SIGNAL HEAD W/ TURN ARROWS (5 SEC.)
- ADVANCE RADAR SENSOR
- STOP LINE RADAR SENSOR
- LUMINAIRE
- PREEMPTION RECEIVING EQUIPMENT
- PREEMPTION CONFIRMATION LIGHT
- 2-1/C (POWER) #6 AWG
- 3-1/C (POWER) #6 AWG
- 3/C #10 AWG (FOR LUMINAIRE POWER)
- 3/C #14 AWG
- 7/C #14 AWG
- METER BASE
- DISCONNECT SWITCH
- RADAR CABLE
- UNINTERRUPTIBLE POWER SUPPLY CABLE
- ANTENNA CABLE (BY OTHERS)
- PREEMPTION RECEIVING UNIT CABLE

[illegible]


POLE A ELEVATION DETAIL

NOT TO SCALE




POLE B ELEVATION DETAIL

NOT TO SCALE



POLE C ELEVATION DETAIL

NOT TO SCALE






ORIENTATION DETAIL NOTES:

- 1.) ALL ANGLES MEASURED
CLOCKWISE.
- 2.) BASE PLATE IS ORIENTED SQUARE
TO MAST ARM "A" EVEN IF SUPPORT
HAS TWO MAST ARMS.

[illegible]


SHEET NO.	STATION		SIDE	POLE NO.	625	625	625	625	625	625	625	625	625	625	625	625											CALCULATED PES 06/14	CHECKED DRB 06/14
					CONNECTION, FUSED PULL APART	CONNECTION, UNFUSED PERMANENT	LIGHT POLE, DECORATIVE, AS PER PLAN	LIGHT POLE FOUNDATION, AS PER PLAN	NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	NO. 12 AWG POLE AND BRACKET CABLE	CONDUIT, 2", 725.04	CONDUIT, 3", 725.04	LUMINAIRE, DECORATIVE, 100 W HPS, 240 VOLT, AS PER PLAN	TRENCH, 24" DEEP	PULL BOX, 725.08, 18"	GROUND ROD	POWER SERVICE, AS PER PLAN	PLASTIC CAUTION TAPE										
	EACH	EACH			EACH	EACH	FT	FT	FT	FT	EACH	FT	EACH	EACH	EACH	FT												
	N. SANDUSKY ST.																											
85	302+51		RT	AB-7	2		1	1		30			1			1												
	302+51	302+56	RT						45	5			5				5											
	302+56		RT			3											1											
	302+56		LT/RT						171			47	47					47										
	302+56		LT											1														
	302+56	303+25	LT						237	69			69					69										
	303+25		LT	AA-5	2		1	1		30			1			1												
	303+25	304+75	LT						480	150			150					150										
	304+75		LT	AA-5	2		1	1		30			1			1												
	304+75	305+00	LT						90	25			25					25										
	302+56	303+99	RT						459	143			143					143										
	303+99		RT	AB-6	2		1	1		30			1			1												
▼	303+99	305+00	RT						318	101			101					101										
86	305+00	306+22	LT						381	122			122					122										
	306+22		LT	AA-4	2		1	1		30			1			1			148									
	306+22	307+70	LT						474	148			148															
	307+70		LT	AA-3	2		1	1		30			1			1												
	307+70	309+00	LT						405	130			130					130										
	305+00	305+48	RT						159	48			48					48										
	305+48		RT	AB-5	2		1	1		30			1			1												
	305+48	306+96	RT						474	148			148					148										
	306+96		RT	AB-4	2		1	1		30			1			1												
	306+96	308+47	RT						483	151			151					151										
	308+47		RT	AB-3	2		1	1		30			1			1												
▼	308+47	309+00	RT						174	53			53					53										
87	309+00	309+21	LT						78	21			21					21										
	309+21		LT	AA-2	2		1	1		30			1			1			169									
	309+21	310+90	LT						537	169			169					169										
	310+90		LT	AA-1	2		1	1		30			1			1												
	309+00	309+95	RT						300	95			95					95										
	309+95		RT	AB-2	2		1	1		30			1			1												
▼	309+95	311+56	RT						513	161			161					161										
	311+56		RT	AB-1	2		1	1		30			1			1												




FOUNDATIONS SHALL BE:

- * 42" DEEP
- * 24" DIAMETER
- * REINFORCED WITH #6 REBAR WITH #4 TIE BARS AS PER PLAN DETAIL
- * TOP IS A 27" X 27" X 6" SQUARE WITH A 1" CHAMFER
- * FOUNDATION TOP IS 4" ABOVE CURB ELEVATION.

LIGHT POLE FOUNDATION, AS PER PLAN
NTS





SECTION A-A
SCALE: NONE




EACH HOLE PROVIDE FOR THE BANNER ARM. BRACKETS SHALL BE PROVIDED WITH A PAINTED PLASTIC OR METAL REMOVABLE CAP TO SEAL THE HOLE FROM MOISTURE AND INSECTS WHEN THE BANNER ARM SUPPORT POLES ARE NOT BEING UTILIZED.

FINISH:
POWDER COATED
BLACK, 37031



LIGHT POLE, DECORATIVE, MAIN STREET BRAND,
AS PER PLAN - ALTERNATE BID
NTS



NOTES:

1. OFFSET TO POST TOP LIGHT POLES & PULL BOXES ARE FROM FACE OF CURB.
2. CONDUITS SHALL BE INSTALLED IMMEDIATELY BEHIND BACK OF CURB WHEN RUNNING PARALLEL TO CURB.




- NOTES:
1. OFFSET TO POST TOP LIGHT POLES & PULL BOXES ARE FROM FACE OF CURB.
 2. CONDUITS SHALL BE INSTALLED IMMEDIATELY BEHIND BACK OF CURB WHEN RUNNING PARALLEL TO CURB.

FOR LEGEND SEE SHEET 85


Batchplot Spec: \\0330share\060\06655\standards\plotdrv\batchplot.spc
Pen Table: \\060\06655\standards\tables\Lighting_V8.ms_std.tbl
Plot Driver: S:\std\plotting\usin\VB\PDF\pltrig

Model: Sheet
Printed: 10/8/2015 4:28:52 PM By: hbrendlinger
File: \\0330share\060\06655\Lighting\Sheets\06655\PO03.dgn



- NOTES:
1. OFFSET TO POST TOP LIGHT POLES & PULL BOXES ARE FROM FACE OF CURB.
 2. CONDUITS SHALL BE INSTALLED IMMEDIATELY BEHIND BACK OF CURB WHEN RUNNING PARALLEL TO CURB.
 3. SEE SIGNAL PLANS FOR LIGHTING QUANTITIES ASSOCIATED WITH COMBINATION SIGNAL/LIGHT POLES.


FOR LEGEND SEE SHEET 85



SANDUSKY STREET AND U.S. 23 INTERSECTION

PLANTING NOTES:

- A. SEE SHEET 94 FOR DETAILS AND PLANT SCHEDULE.
- B. ALL PLANTING BEDS AND FREE STANDING TREES TO BE MULCHED WITH GRADE "A" DOUBLE PROCESSED 'ABSOLUTE BLACK' HARDWOOD MULCH.



LOCATION MAP

UTILITY LIST

ELECTRIC AEP 850 TECH CENTER DRIVE GAHANNA, OH 43230-6605 ATTN: PAUL PAXTON (614) 883-6831	COMMUNICATIONS AT&T (LOCAL) 111 NORTH 4TH STREET 8TH FLOOR COLUMBUS, OH 43215 ATTN: GARY VanAlmsick (614) 223-7276
AEP (TRANSMISSION) 700 MORRISON ROAD GAHANNA, OH 43230 ATTN: TINA HAIRSTON (614) 552-1801	AT&T (LONG DISTANCE & LS METRO) 5980-G WILCOX PLACE DUBLIN, OH 43016 ATTN: TONY LYLE (614) 760-8320
SANITARY & STORM SEWER DELAWARE COUNTY REGIONAL SEWER DISTRICT 50 CHARRING STREET DELAWARE, OH 43015 (740) 833-2240	AT&T METRO 8372 EAST BROAD STREET REYNOLDSBURG, OH 43068 ATTN: ANITA NUCKOLS (614) 868-2347
WATER DEL-CO WATER CO., INC. 6773 OLENTANGY RIVER ROAD DELAWARE, OH 43015 ATTN: SHANE F. CLARK (740) 548-7746/(800) 521-6779	TIME WARNER CABLE 3760 INTERCHANGE DRIVE COLUMBUS, OH 43216 ATTN: RAY MAURER (614) 481-5262
TRAFFIC ODOT DISTRICT 6 400 E. WILLIAM STREET DELAWARE, OH 43015 (740) 833-8000	VERIZON 550 LEADER STREET MARION, OH 43302 (740) 383-0575
GAS COLUMBIA GAS OF OHIO 3550 JOHNNY APPLESEED CT. COLUMBUS, OH 43215 ATTN: HEIDI ZACHER (614) 818-2107	CITY OF DELAWARE PUBLIC UTILITIES 225 CHERRY STREET DELAWARE, OH 43015 ATTN: BRAD STANTON & PERRY MICKLEY (740) 203-1900

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES
CALL TWO WORKING DAYS
BEFORE YOU DIG
CALL
1-800-362-2764
(TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY
OIL & GAS PRODUCERS PROTECTIVE
SERVICE CALL: 1-800-925-0988

NOTES: THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE OBTAINED FROM THE OWNER OF THE UTILITIES AS REQUIRED BY SECTION 153.64 O.R.C.

PLAN PREPARED BY:
ms consultants, inc.
engineers, architects & planners
2221 Schrock Road
Columbus, Ohio 43229-1547
Tel 614.898.7100 Fax 614.898.7570
www.msconsultants.com

RIGHT OF WAY LEGEND SHEET DEL-23-13.17

COUNTY OF DELAWARE CITY OF DELAWARE & DELAWARE TOWNSHIP FARM LOT 3, QTR. TWP.4, TWP.5, R.19 UNITED STATES MILITARY DISTRICT

INDEX OF SHEETS:

LEGEND	1
CENTERLINE PLAT	2
PROPERTY MAP	3
SUMMARY OF ADDITIONAL R/W	4
DETAIL SHEETS	5-9

CONVENTIONAL SYMBOLS

County Line	-----	Ditch / Creek (Ex)	-----
Township Line	-----	Ditch / Creek (Pr)	-----
Section Line	-----	Tree Line (Ex)	-----
Corporation Line	----- or -----	Ownership Hook Symbol	Example
Fence Line (Ex)	----- x ----- (Pr)	Property Line Symbol	Example
Center Line	-----	Break Line Symbol	Example
Right of Way (Ex)	----- Ex R/W -----	Tree (Pr)	Tree (Ex) Shrub (Ex)
Right of Way (Pr)	----- R/W -----	Tree (Remove)	Shrub (Remove)
Standard Highway Ease.(Ex)	----- Ex SH -----	Evergreen (Ex)	Stump
Temporary Right of Way	----- TMP -----	Evergreen (Remove)	Stump (Remove)
Channel Ease. (Pr)	----- CH -----	Wetland (Pr)	Grass (Pr) Aerial Target
Utility Ease. (Ex)	----- Ex U -----	Post (Ex)	Mailbox (Ex) Mailbox (Pr)
Railroad	----- or -----	Light (Ex)	Telephone Marker (Ex) TEL
Guardrail (Ex)	----- (Pr)	Fire Hydrant (Ex)	Water Meter (Ex)
Construction Limits	-----	Water Valve (Ex)	Utility Valve Unknown (Ex)
Edge of Pavement (Ex)	-----	Telephone Pole (Ex)	Power Pole (Ex)
Edge of Pavement (Pr)	-----	Light Pole (Ex)	
Edge of Shoulder (Ex)	-----		
Edge of Shoulder (Pr)	-----		

STRUCTURE KEY

	RESIDENTIAL
	COMMERCIAL
	OUT-BUILDING

PARCEL IDENTIFIER LEGEND

WD - FEE SIMPLE RESERVATION OF ACCESS
T - TEMPORARY EASEMENT

PLANS PREPARED BY:

FIRM NAME: ms consultants, inc.
R/W DESIGNER: Chad S. Snow
R/W REVIEWER: Richard John Swan
FIELD REVIEWER: Alan Buck
PRELIMINARY FIELD REVIEW DATE: 09/27/13
TRACINGS FIELD REVIEW DATE: 04/07/14
OWNERSHIP UPDATED BY: Chad Snow
DATE COMPLETED: 04/08/14
PLAN COMPLETION DATE: 04/08/14

I, Richard John Swan, P. S. have conducted a survey of the existing conditions for the Ohio Department of Transportation on April, 2012. The results of that survey are contained herein. The horizontal coordinates expressed herein are based on the Ohio State Plane Coordinates System North Zone on NAD 83(CORS 96) datum. The Project Coordinates (US Survey Feet) are relative to State Plane Grid Coordinates (Meters or US Survey Feet) by a Project Adjustment Factor of 1.000023762. As a part of this project I have reestablished the locations of the existing property lines and the existing centerline of Right of Way for property takes contained herein. As a part of this project I have established the proposed property lines, calculated the Gross Take, present roadway occupied (PRO), Net Take and Net Residue; as well as prepared the legal descriptions necessary to acquire the parcels as shown herein. As a part of this work I have set right of way monuments at the property corners, property line intersection, points along the right of way and/or angle points on the right of way, Section Corners and other points as shown herein. All of my work contained herein was conducted in accordance with Ohio Administrative Code 4733-37 commonly known as "Minimum Standards for Boundary Surveys in the State of Ohio" unless noted. The words I and my as used herein are to mean either myself or someone working under my direct supervision.


Richard John Swan, Professional Land Surveyor 6574

Date: 04/08/2014

SURVEYORS SEAL



TOTAL NUMBER OF :															FEDERAL PROJECT NO. E130216																													
4 OWNERSHIPS		0 TOTAL TAKES																																										
7 PARCELS		1 OWNERSHIPS W/ STRUCTURES INVOLVED 'SIGN'																																										
ALL AREAS IN ACRES															NET TAKE = GROSS TAKE - PRO IN TAKE																													
															NET RESIDUE = RECORD AREA - TOTAL PRO - NET TAKE																													
PARCEL NO.	OWNER	SHEET NO.	OWNERS	RECORD	AUDITOR'S PARCEL	RECORD AREA	TOTAL P.R.O.	GROSS TAKE	P.R.O. IN TAKE	NET TAKE	STRUC-TURE	NET RESIDUE		TYPE FUND	REMARKS	AS ACQUIRED																												
			BOOK	PAGE								LEFT	RIGHT			BOOK	PAGE																											
1 - 19	NOT USED													CITY/ STATE																														
20	Teresa M. Beach	5	D.V. 0553 D.V. 0059	PG. 762 PG. 1006	51942309031000	0.302	0.0000				N			↑	NO TAKE																													
21	Zyrone White	5	D.V. 0685	PG. 0003	51942002001000	0.4198 (c)	0.0000				N				NO TAKE																													
22	ROBIN E. FOGLE	5	D.V. 0088 D.B. 1214	PG. 1580 PG. 1785	51942301040000	0.497	0.0000				N				NO TAKE																													
23	David G. Ames and Deborah B. Ames	5	D.V. 0317	PG. 2494	51942301042000	0.197	0.0000				N				NO TAKE																													
24	CHRISTOPHER J. SCHMOTZER AND MOLLIE A. SCHMOTZER	5 - 6	D.V. 0697	PG. 1714	51942301043000	0.239	0.0000				N				NO TAKE																													
25	M. Dale Nelson, Jr.	6	D.V. 0478	PG. 1114	51942301044000	0.218	0.0000				N				NO TAKE																													
26 WD	Fidelity Federal Savings and Loan Association of Delaware, Ohio	6 - 7 6 - 7	D.V. 1000	PG. 2617	51942301046001 51942301047001 TOTAL	7.100 0.400 7.500	0.3015 0.0116 0.3131	1.1667 0.0784 1.2451	0.3015 0.0116 0.3131	0.8652 0.0668 0.9320	N N	5.9333 0.3216 6.2549			ROADWAY IMPROVEMENTS - OVERLAPS MUTUAL EASEMENT FOR IGRESS/EGRESS BETWEEN PARCELS 26, 27 & 28 (D.V. 0588 PG. 1746). *26 WD OVERLAPS W/MUTUAL & SANITARY EASEMENTS BY 0.3597 ACRES																													
26 T					51942301046001 51942301047001 TOTAL 51942301045000	7.100 0.400 7.500 7.400	0.3015 0.0116 0.3131 0.0000	0.0027 0.0206 0.0233	0.0000 0.0000 0.0000	0.0027 0.0206 0.0233	N N N				DRIVEWAY IMPROVEMENTS & GRADING NO TAKE FROM THIS AUDITOR'S PARCEL NUMBER																													
27 WD	P.D. Paykoff Companies LLC	7 - 9	D.V. 0658	PG. 0586	51942301047000	8.536	3.7345	4.3937	3.7345	0.6592	N	4.1423			ROADWAY IMPROVEMENTS - MUTUAL EASEMENT NOTE *27 WD OVERLAPS W/MUTUAL, SANITARY & ELECTRIC EASEMENTS BY 0.3138 ACRES																													
27 T		7 - 9				8.536	3.7345	0.2637	0.0000	0.2637	N				DRIVEWAY IMPROVEMENTS, GRADING & WATERLINE																													
28 WD	Tap Holdings LLC	7 - 8	D.V. 0658	PG. 0583	51942301048000	8.005	0.3600	0.4414	0.3600	0.0814	N	7.5636			DRAINAGE DITCH & SLOPE PROTECTION-MUTUAL EASE. NOTE *28 WD OVERLAPS W/MUTUAL, SANITARY & ELECTRIC EASEMENTS BY 0.0814 ACRES																													
28 T		7 - 8			51942301048000 51942301047002	8.005 0.485	0.3600 0.0000	0.0193	0.0000	0.0193	N N				DRIVEWAY REMOVAL, GRADING & WATERLINE NO TAKE FROM THIS AUDITOR'S PARCEL NUMBER																													
29 WD	Diners LLC	8	D.V. 0638	PG. 2418	51942301048001	0.995	0.0000	0.0618	0.0000	0.0618	Y "S(1)"	0.9332			GRADING, DRAINAGE DITCH & SLOPE PROTECTION *29 WD OVERLAPS W/SAN. & ELECT. EASEMENTS BY 0.0618 ACRES																													
30	BARRY A SMITH & PATRICIA L SMITH	8	D.V. 0572	PG. 346	51942301049000	1.310	0.4125				N				NO TAKE																													
														CITY/ STATE																														
NOTE: ALL TEMPORARY PARCELS TO BE OF 24 MONTH DURATION.																																												
NOTE: UNDER NO CIRCUMSTANCES ARE TEMPORARY EASEMENTS TO BE USED FOR STORAGE OF MATERIAL OR EQUIPMENT BY THE CONTRACTOR UNLESS NOTED OTHERWISE.																																												
PARCEL IDENTIFIER LEGEND WD - FEE SIMPLE RESERVATION OF ACCESS T - TEMPORARY CONSTRUCTION EASEMENT																																												
GRANTEE: ALL RIGHT OF WAY ACQUIRED IN THE NAME OF CITY OF DELAWARE & STATE OF OHIO, DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE SHOWN.																																												
<table><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr><tr><td>REV. BY</td><td>DATE</td><td>DESCRIPTION</td></tr><tr><td colspan="2">FIELD REVIEW BY : ALAN BUCK</td><td>DATE: 09/27/13</td></tr><tr><td colspan="2">OWNERSHIP VERIFIED BY : CHAD SNOW</td><td>DATE: 04/08/14</td></tr><tr><td colspan="3">DATE COMPLETED : 04/08/14</td></tr></table>																																	REV. BY	DATE	DESCRIPTION	FIELD REVIEW BY : ALAN BUCK		DATE: 09/27/13	OWNERSHIP VERIFIED BY : CHAD SNOW		DATE: 04/08/14	DATE COMPLETED : 04/08/14		
REV. BY	DATE	DESCRIPTION																																										
FIELD REVIEW BY : ALAN BUCK		DATE: 09/27/13																																										
OWNERSHIP VERIFIED BY : CHAD SNOW		DATE: 04/08/14																																										
DATE COMPLETED : 04/08/14																																												
4 / 9																																												
98 103																																												



REV. BY	DATE	DESCRIPTION
DATE COMPLETED : 04/08/14		



PROJECT DESCRIPTION

THE EXISTING SOUTHBOUND US 23 ROADWAY WILL BE WIDENED TO INCLUDE A TURN LANE AND THE EXISTING SANDUSKY STREET RAMP WILL BE REALIGNED TO ALLOW FOR TWO-WAY TRAFFIC FLOW. A CENTER TURN LANE WILL BE ADDED TO NORTHBOUND US 23. THE VERTICAL ALIGNMENT OF US 23 WILL REMAIN RELATIVELY UNCHANGED. THE NEW SANDUSKY STREET RAMP WILL BE CONSTRUCTED BELOW EXISTING GRADE. UP TO APPROXIMATELY 18 FEET OF ROADWAY CUT IS EXPECTED BELOW EXISTING GRADE ALONG THE NEW ALIGNMENT.

HISTORIC RECORDS

PLAN AND PROFILE INFORMATION (CIRCA 1962) FOR THE US 23 RELOCATION THROUGH THE CITY OF DELAWARE WAS AVAILABLE, BUT DID NOT INCLUDE DETAILED GEOTECHNICAL INFORMATION FOR THE PROPOSED ALIGNMENT.

S&ME ACCESSED THE ODOT OFFICE OF GEOTECHNICAL ENGINEERING’S ON-LINE GEOTECHNICAL DOCUMENT MANAGEMENT SYSTEM TO SEARCH FOR ANY OTHER EXISTING HISTORICAL GEOTECHNICAL EXPLORATIONS WITHIN THE LIMITS OF THIS PROJECT; HOWEVER, NO EXISTING ADDITIONAL INFORMATION WAS LOCATED.

GEOLOGY

THIS PROJECT SITE IS LOCATED IN A PREVIOUSLY GLACIATED AREA. SILTY CLAY TILL OF LATE WISCONSINAN AGE THAT IS FLAT TO GENTLY UNDULATED IS PRESENT IN THE AREA OF THE SITE (QUARTERNARY GEOLOGY OF OHIO, OHIO DEPARTMENT OF NATURAL RESOURCES (ODNR), GEOLOGICAL SURVEY). GEOLOGIC BEDROCK MAPPING (ODNR, GEOLOGICAL SURVEY) INDICATES THE PRESENCE OF OLENTANGY SHALE CONSISTING OF GREENISH GRAY SHALE IN THE UPPER PORTIONS TO GRAY SHALE IN THE LOWER PORTIONS. THE ODNR “OHIO KARST AREAS” MAP DOES INDICATE THE PRESENCE OF ACTIVE KARST TERRAIN IN THE AREA. ODNR MAPPING INDICATES THAT UNDERGROUND MINES ARE NOT KNOWN TO BE IN THE PROJECT AREA.

RECONNAISSANCE

ON JULY 18, 2013 A SITE RECONNAISSANCE WAS PERFORMED BY AN S&ME PROJECT ENGINEER. THE ROAD SURFACE OF BOTH THE SANDUSKY STREET RAMP AND US 23 VISUALLY APPEARED TO BE IN GOOD CONDITION.

SUBSURFACE EXPLORATION

DURING THE PERIOD OF JULY 24 TO JULY 26, 2013, FOUR (4) PAVEMENT CORES AND SIX (6) ROADWAY BORINGS WERE PERFORMED ALONG THE PROPOSED INTERCHANGE ALIGNMENT. THE BORING LOCATIONS WERE SELECTED AND FIELD LOCATED BY S&ME BASED A PROPOSED INTERCHANGE ALIGNMENT DRAWING PROVIDED BY MS CONSULTANTS. THE ROADWAY BORINGS (B-001-0-13, B-002-0-13, B-003-0-13, B-004-0-13, B-005-0-13 AND B-006-0-13) WERE ADVANCED TO BETWEEN 7.0 AND 25.0 FEET BELOW THE TOP OF THE EXISTING GROUND SURFACE BY AN ALL-TERRAIN VEHICLE-MOUNTED DRILL RIG USING 3-1/4-INCH I.D. HOLLOW-STEM AUGERS. AT REGULAR INTERVALS, DISTURBED, BUT REPRESENTATIVE, SOIL SAMPLES WERE OBTAINED BY LOWERING A 2-INCH O.D. SPLIT-BARREL SAMPLER TO THE BOTTOM OF THE BORING AND THEN DRIVING THE SAMPLER INTO THE SOIL WITH BLOWS FROM A 140-POUND HAMMER FREELY FALLING 30 INCHES (ASTM D1586 – STANDARD PENETRATION TEST). ALL DISTURBED SAMPLES WERE EXAMINED IN THE FIELD AND REPRESENTATIVE PORTIONS WERE PRESERVED IN AIRTIGHT GLASS JARS. THE RECOVERED SOIL SAMPLES WERE THEN TRANSPORTED TO THE SOILS LABORATORY OF S&ME FOR FURTHER EXAMINATION AND TESTING. UPON COMPLETION, WATER LEVELS WERE MEASURED AND THE BORINGS WERE BACKFILLED OR SEALED IN ACCORDANCE WITH ODOT REQUIREMENTS.

IN ACCORDANCE WITH ODOT SPECIFICATIONS, THE HAMMER SYSTEM ON THE DRILLING RIG WAS CALIBRATED ON MARCH 25, 2011, IN ACCORDANCE WITH ASTM D4633 TO DETERMINE THE DRILL ROD ENERGY RATIO (80.9%).

EXPLORATION FINDINGS

BORINGS B-005-0-13 AND B-006-0-13 ENCOUNTERED 4.5 INCHES OF ASPHALT AT THE SURFACE. BORING B-001-0-13 ENCOUNTERED 11 INCHES OF ASPHALT. CORE X-003-1-13 ENCOUNTERED 6 INCHES OF ASPHALT. CORE X-003-1-13 AND BORINGS B-005-0-13 AND B-006-0-13 ENCOUNTERED BETWEEN 9 AND 9.5 INCHES OF CONCRETE. BORINGS B-005-0-13 AND B-006-0-13 ENCOUNTERED BETWEEN 9 AND 9.5 INCHES OF GRANULAR BASE. BORING B-003-0-13 ENCOUNTERED 16 INCHES OF GRANULAR BASE AT THE GROUND SURFACE. BORING B-004-0-1 ENCOUNTERED APPROXIMATELY 10 INCHES OF GRAVEL FILL AT THE GROUND SURFACE. APPROXIMATELY 3 INCHES OF TOPSOIL WAS ENCOUNTERED AT THE GROUND SURFACE IN B-002-0-13.

BENEATH THE SURFICIAL MATERIALS, EXISTING FILL WAS ENCOUNTERED TO DEPTHS RANGING FROM 2.5 TO 5.5 FEET IN THE FIVE (5) BORINGS ALONG US 23 AND THE EXISTING EXIT RAMP. THE EXISTING FILL CONSISTED PRIMARILY OF VERY-STIFF TO HARD BROWN AND GRAY SILT AND CLAY (A-6A) CONTAINING DISCONTINUOUS SEAMS AND ZONES OF MEDIUM-DENSE BROWN AND GRAY GRAVEL WITH SAND (A-1-B), VERY-STIFF BROWN AND DARK-BROWN CLAY (A-7-6), AND HARD BROWN SANDY SILT (A-4A).

THE NATURAL SOILS ENCOUNTERED WITHIN THE BORINGS ALONG US 23 AND THE EXISTING EXIT RAMP GENERALLY CONSISTED OF VERY-STIFF TO HARD BROWN AND GRAY SILT AND CLAY (A-6A), WITH LAYERS OF MEDIUM-STIFF TO VERY-STIFF BROWN AND BROWN MOTTLED WITH GRAY CLAY (A-7-6), AND MEDIUM-DENSE BROWN AND GRAY GRAVEL WITH SAND, SILT AND CLAY (A-2-6).

LEGEND			
DESCRIPTION	ODOT CLASS	CLASSIFIED MECH./VISUAL	
GRAVEL	A-1-a	0	2
GRAVEL WITH SAND	A-1-b	1	2
GRAVEL WITH SAND AND SILT	A-2-4	1	0
GRAVEL WITH SAND, SILT AND CLAY	A-2-6	0	1
COURSE AND FINE SAND	A-3a	0	1
SANDY SILT	A-4a	1	0
SILT AND CLAY	A-6a	7	10
CLAY	A-7-6	2	2
	TOTAL	12	18
PAVEMENT OR BASE = X = APPROXIMATE THICKNESS	VISUAL		
SOD AND TOPSOIL = X = APPROXIMATE THICKNESS	VISUAL		
BORING LOCATION - PLAN VIEW			
CORING LOCATION - PLAN VIEW			
DRIVE SAMPLE AND/OR ROCK CORE BORING PLOTTED TO VERTICAL SCALE ONLY. HORIZONTAL BAR INDICATES A CHANGE IN STRATIGRAPHY.			
WC	INDICATES WATER CONTENT IN PERCENT.		
N ₆₀	INDICATES STANDARD PENETRATION RESISTANCE NORMALIZED TO 60% DRILL ROD ENERGY RATIO.		
W—	INDICATES FREE WATER ELEVATION.		
*	INDICATES A SAMPLE TAKEN WITHIN 3 FEET OF PROPOSED GRADE.		
SS	INDICATES A SPLIT SPOON SAMPLE, STANDARD PENETRATION TEST.		

EXPLORATION FINDINGS CON’T

BORING B-004-0-13 ENCOUNTERED 9.7 FEET OF VERY -STIFF TO HARD GRAY OR GRAY MOTTLED WITH BROWN SILT AND CLAY (A-6A) BENEATH THE 10 INCHES OF COARSE AGGREGATE. THE BORING THEN ENCOUNTERED 7.5 FEET OF MEDIUM-DENSE BROWN AND GRAY GRAVEL WITH SAND AND SILT (A-2-4) OR BROWN GRAVEL WITH SAND (A-1-B). BENEATH THESE LAYERS WAS 2.9 FEET OF MEDIUM-DENSE BROWN AND GRAY COARSE AND FINE SAND (A-3A) AND 4.1 FEET OF VERY-DENSE GRAVEL (A-1-A). THE BORING WAS TERMINATED AFTER REACHING AUGER REFUSAL.


SEEPAGE WAS ENCOUNTERED IN ONLY ONE BORING, B-004-0-13, AT A DEPTH OF 18.5 FEET. GROUNDWATER WAS ENCOUNTERED AT 20.0 FEET BENEATH THE EXISTING GROUND SURFACE AT THE SAME BORING LOCATION. WATER DID NOT ACCUMULATE IN THE BORINGS PRIOR TO BACKFILLING. THE GROUNDWATER MEASUREMENTS OBTAINED DURING DRILLING SHOULD BE CONSIDERED SHORT-TERM INDICATIONS OF GROUNDWATER LEVELS AND MAY NOT REPRESENT THE LONG-TERM GROUNDWATER LEVELS BENEATH THE SITE.

SPECIFICATIONS

THE SUBSURFACE INVESTIGATION WAS GENERALLY PERFORMED IN ACCORDANCE WITH THE ODOT SPECIFICATIONS FOR GEOTECHNICAL EXPLORATIONS (SGE), REVISED JANUARY 20, 2012.


AVAILABLE INFORMATION

ALL AVAILABLE SOIL AND BEDROCK INFORMATION THAT CAN BE CONVENIENTLY SHOWN ON THE GEOTECHNICAL EXPLORATION SHEETS HAS BEEN SO REPORTED. ADDITIONAL EXPLORATIONS MAY HAVE BEEN MADE TO STUDY SOME SPECIAL ASPECT OF THE PROJECT. COPIES OF THIS DATA, IF ANY, MAY BE INSPECTED AT THE DISTRICT DEPUTY DIRECTOR’S OFFICE, THE OFFICE OF GEOTECHNICAL ENGINEERING AT 1600 WEST BROAD STREET OR THE OFFICE OF STRUCTURAL ENGINEERING AT 1980 WEST BROAD STREET.



LOCATION MAP
SCALE IN MILES

PARTICLE SIZE DEFINITIONS



INDEX OF SHEETS				
LOCATION FROM STA. TO STA.	PLAN VIEW SHEET	PROFILE SHEET	CUT MAX.	FILL MAX.
SANDUSKY STREET 302+27.4 TO 312+82.3	3	3	18.2’	0.6’
U.S. 23 688+49.97 TO 700+23.86	4	4	-	-

RECON. - JDR (7/18/13)
DRILLING - S&ME (7/24-26/13)
DRAWN - PRR (10/30/13-11/6/13)
ZWA (10/30/13-11/6/13)
REVIEWED - JDR (4/3/14)



○


○

SUMMARY OF SOIL TEST DATA SANDUSKY STREET														
EXPLORATION NUMBER AND LOCATION	SAMPLE INTERVAL (FROM - TO)	SAMPLE ID	% REC	% AGG	% CS	% FS	% SILT	% CLAY	LL	PL	PI	% WC	OHIO CLASS	
B-001-0-13 STA 302+90.5, 0.7' Lt. Latitude = 40.312961601 N Longitude = 83.066491999 W	1.0 - 2.5	SS-1	56	Hard gray and brown SILT AND Clay (Fill)								18	A-6a (V)*	
	2.5 - 4.0	SS-2	100	4	5	12	38	41	30	19	11	16	A-6a (8)*	
	4.0 - 5.5	SS-3	100	4	4	11	40	41	33	18	15	15	A-6a (10)	
	5.5 - 7.0	SS-4	100	Same as SS-3								17	A-6a (V)	
B-002-0-13 STA 306+14.2, 16.1' Rt. Latitude = 40.313855470 N Longitude = 83.066488570 W	1.0 - 2.5	SS-1	100	Medium-dense brown & gray GRAVEL WITH SAND (FILL)								12	A-1-b (V)*	
	2.5 - 4.0	SS-2	100	16	12	13	30	29	33	19	14	13	A-6a (6)*	
	4.0 - 5.5	SS-3	100	12	10	13	31	34	35	20	15	15	A-6a (8)*	
	5.5 - 7.0	SS-4	100	Very-stiff dark gray SILT AND CLAY								19	A-6a (V)	
B-004-0-13 STA 310+25.5, 36.0' Rt. Latitude = 40.314859884 N Longitude = 83.067141255 W	1.0 - 2.5	SS-1	100	Hard gray mottled with brown SILT AND CLAY								17	A-6a (V)*	
	3.5 - 5.0	SS-2	100	Very-stiff gray SILT AND CLAY								16	A-6a (V)*	
	6.0 - 7.5	SS-3	100	Same as SS-2								16	A-6a (V)*	
	8.5 - 10.0	SS-4	67	Same as SS-2								16	A-6a (V)*	
	11.0 - 12.5	SS-5	67	53	18	9		9	27	18	9	7	A-2-4 (0)*	
	13.5 - 15.0	SS-6	33	46	24	11	12	7	25	19	6	7	A-1-b (0)	
	16.0 - 17.5	SS-7	67	Medium-dense brown GRAVEL WITH SAND								11	A-1-b (V)	
	18.5 - 20.0	SS-8	56	Medium-dense brown & gray COARSE AND FINE SAND								16	A-3a (V)	
	21.0 - 22.5	SS-9	56	Very-dense gray GRAVEL								15	A-1-a (V)	
	23.5 - 25.0	SS-10	67	Same as SS-9								8	A-1-a (V)	


SUMMARY OF SOIL TEST DATA U.S. ROUTE 23														
EXPLORATION NUMBER AND LOCATION	SAMPLE INTERVAL (FROM - TO)	SAMPLE ID	% REC	% AGG	% CS	% FS	% SILT	% CLAY	LL	PL	PI	% WC	OHIO CLASS	
B-003-0-13 STA 690+51.8, 46.8' Lt. Latitude = 40.314160229 N Longitude = 83.066281624 W	2.0 - 3.5	SS-1	100	7	9	14	35	35	33	20	13	17	A-6a (8)*	
	3.5 - 5.0	SS-2	89	4	5	10	38	43	46	23	23	20	A-7-6 (14)	
	5.0 - 6.5	SS-3	100	Very-stiff brown mottled with gray CLAY								21	A-7-6 (V)	
	6.5 - 8.0	SS-4	100	Same as SS-3								32	A-7-6 (V)	
B-005-0-13 STA 695+10.1, 51.1' Lt. Latitude = 40.315299965 N Longitude = 83.066944930 W	2.0 - 3.5	SS-1	56	22	13	15	28	22	24	15	9	10	A-4a (3)*	
	3.5 - 5.0	SS-2	100	6	11	19	23	41	43	20	23	26	A-7-6 (11)	
	5.0 - 6.5	SS-3	67	Very-stiff brown and dark-brown SILT AND CLAY								22	A-6a (V)	
	6.5 - 8.0	SS-4	39	Medium-dense GRAVEL W/ SAND, SILT AND CLAY								22	A-2-6 (V)	
B-006-0-13 STA 698+66.7, 39.8' Lt. Latitude = 40.316198965 N Longitude = 83.067457052 W	2.0 - 3.5	SS-1	56	10	11	13	33	33	29	18	11	14	A-6a (7)*	
	3.5 - 5.0	SS-2	44	36	14	10	21	19	28	16	12	11	A-6a (2)	
	5.0 - 6.5	SS-3	100	Very-stiff to hard brown and dark-br SILT and CLAY								21	A-6a (V)	
	6.5 - 8.0	SS-4	100	Same as SS-3								27	A-6a (V)	



SUMMARY OF PAVEMENT SECTION COMPONENT THICKNESS					
EXPLORATION ID	ROADWAY	ASPHALT (in)	CONCRETE (in)	GRANULAR BASE (in)	TOTAL SECTION THICKNESS (in)
B-001-0-13	US 23, SB EXIT RAMP	11.0	-	-	11.0
X-003-1-13	US 23 MEDIAN	6.0	9.5	◇	15.5◇
B-005-0-13	US 23, SB SHOULDER	4.5	9.0	9.5	23.0
B-006-0-13	US 23, SB SHOULDER	4.5	9.5	9.0	23.0

◇ Depth of base not determined.



FOR SOIL PROFILE FOR
U.S. 23 SEE SHEET NO. 4





SPECIAL PROVISIONS

OLENTANGY NPDES

CO-RT-SEC: DEL-23-13.17

PID: 94527

DATE: 6-2-2014

UPDATES FOR SUPPLEMENTAL SPECIFICATION 832 FOR COVERAGE UNDER OHIO EPA PERMIT NO. OHCO00002

ALL REFERENCES TO THE OHIO ENVIRONMENTAL PROTECTION AGENCY (OEPA) NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) STORM WATER CONSTRUCTION GENERAL PERMIT NO. OHC000004 IN SUPPLEMENTAL SPECIFICATION 832 (SS832) AND APPENDIX E WILL BE REPLACED WITH THE OEPA GENERAL PERMIT NO. OHCO00002, AUTHORIZATION FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY LOCATED WITHIN PORTIONS OF THE OLENTANGY RIVER WATERSHED UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM ("THE OHCO00002 PERMIT"). A COPY OF THE OHCO00002 PERMIT IS ATTACHED.

THE CONTRACTOR NEEDS TO FULLY UNDERSTAND ALL REQUIREMENTS OF THE OHCO00002 PERMIT BEFORE BEGINNING ANY WORK. FOR ANY DISCREPENCIES BETWEEN SS832 AND THIS SPECIAL PROVISION, RESOLUTION SHOULD BE BASED ON THE OHCO00002 PERMIT.

THE CONTRACTOR IS REQUIRED TO OBTAIN SEPARATE COVERAGE UNDER THE APPROPRIATE OHIO EPA NPDES GENERAL PERMIT FOR ANY OFFSITE CONTRACTOR EDA THAT REQUIRES NPDES COVERAGE AND STORM WATER MITIGATION. ONSITE CONTRACTOR EDA THAT DOES NOT REQUIRE MITIGATION MAY BE CONDUCTED UNDER THE PROJECT STORM WATER PERMIT COVERAGE.

ALL ITEMS COVERED IN SS832 WILL APPLY WITH THE EXCEPTION OF THE ITEMS NOTED BELOW:

A. SECTION 832.04 REQUIREMENTS AND PROVISIONS.

1. POST CONSTRUCTION CONTROLS AND MITIGATION FOR RIPARIAN SETBACK DESCRIBED IN THE OHCO00002 PERMIT ARE NOT TEMPORARY EROSION CONTROL FEATURES. CONSTRUCTION REQUIREMENTS AND COMPENSATION FOR POST CONSTRUCTION CONTROLS AND STORM WATER RELATED MITIGATION FOR RIPARIAN SETBACK ARE DETAILED IN THE PROJECT PLANS.

B. SECTION 832.05(H) - LOCATE AND FURNISH BMP SEDIMENT BASINS AND DAMS

1. CONSTRUCT BASINS ACCORDING TO THE CONDITIONS AND VOLUME REQUIREMENTS INDICATED IN THE OHCO00002 PERMIT.
2. SEDIMENT BASINS MAY BE SHOWN ON THE PROJECT PLANS TO SHOW THAT CAPACITY FOR SEDIMENT IS AVAILABLE TO MEET PERMIT REQUIREMENTS. IF THE CONTRACTOR DETERMINES CAPACITY IS AVAILABLE OUTSIDE OF THE BASIN LOCATIONS SHOWN ON THE PROJECT PLANS, THE CONTRACTOR MAY ELECT TO LOCATE THE SEDIMENT BASINS IN OTHER LOCATIONS PROVIDED THE BASINS SATISFY THE PERMIT AND CONTRACT REQUIREMENTS. REVISED SEDIMENT BASIN LOCATIONS MUST BE SUBMITTED IN WRITING WITH APPROPRIATE CALCULATIONS FOR DISTRICT APPROVAL.

C. SECTION 832.09 STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

1. SPECIFICALLY IDENTIFY THE LOCATION OF THE RIPARIAN SETBACKS AND SEDIMENT BASINS AS SHOWN IN THE PLANS ON THE SWPPP. THE CONTRACTOR CANNOT AMEND THE LOCATIONS OF THE RIPARIAN SETBACKS. MODIFICATION TO ANY SEDIMENT BASIN LOCATION REQUIRES WRITTEN DISTRICT APPROVAL.
2. FOR EACH SEDIMENT BASIN OR DAM, PROVIDE THE SETTLING VOLUME, CONTRIBUTING DRAINAGE AREA, AND DESIGNATE EACH WITH A UNIQUE THREE DIGIT NUMBER ON THE SWPPP.
3. ALL WATERSHEDS, AS IDENTIFIED ON THE STORM WATER SITE PLANS, MAY REQUIRE SITE SPECIFIC TEMPORARY BMP DESIGN AND IMPLEMENTATION THAT HAS THE CAPACITY TO CONTROL SEDIMENT AND EROSION IMPACTS WITHOUT UTILIZING FULL SEDIMENT POND VOLUME REQUIREMENTS. STORM WATER DESIGNER IS REQUIRED TO SHOW CALCULATIONS FOR ALL BMPs INSTALLED.

THE SWPPP DESIGNER IS REQUIRED TO INCLUDE A DETAILED DESCRIPTION OF ALL STRUCTURAL BMP PRACTICES THAT STORE RUNOFF AND COLLECT SEDIMENT. DIVERT FLOWS AWAY FROM EXPOSED SOILS TO THE MAXIMUM EXTENT PRACTICAL. INSTALL COMPLIANT SEDIMENT CONTROL PRACTICES PRIOR TO THE INITIATION OF EARTH DISTURBANCE. THE SWPPP DESIGN IS REQUIRED TO INCLUDE A DETAILED SEQUENCE OF OPERATIONS THAT IS COORDINATED WITH THE CONTRACTOR'S PROGRESS SCHEDULE. THE SEQUENCE OF OPERATIONS IS REQUIRED TO DESCRIBE ALL CONSTRUCTION OPERATIONS THAT TAKE PLACE IN AND AROUND ANY EXPOSED SOIL AND HOW THE BMPs WILL BE SCHEDULED, IMPLEMENTED AND MAINTAINED. ALL DISTURBED AREAS WILL BE STABILIZED WITHIN 14 DAYS WITH TEMPORARY OR PERMANENT MEANS INCLUDING BUT NOT LIMITED TO MULCH WITH TACTIFER OR NETTING, SOIL STABILIZERS AND/OR PERMANENT SEEDING & MULCH TO SERVE AS AN ALTERNATIVE SEDIMENT CONTROL MEASURE. ALL INSPECTION LOGS MUST CLEARLY REFLECT IF THIS CONDITION IS VIOLATED.

D. SECTION 832.11

1. IN ADDITION TO THE WEEKLY INSPECTION REPORTS, THE SWPPP DESIGNER SHALL SPECIFICALLY IDENTIFY THE % EDA AND % STABILIZED (PERMANENT AND TEMPORARY) IN THE WATERSHEDS, AS IDENTIFIED ON THE STORM WATER SITE PLANS. DOCUMENT THE % EDA AND % STABILIZATION VALUES FOR EACH OF THE SUBJECT WATERSHEDS IN THE WEEKLY INSPECTION REPORTS.
2. ALL INSPECTION LOGS MUST CLEARLY REFLECT IF DISTURBED AREAS ARE NOT STABILIZED WITHIN 14 DAYS.